THE SINGLE BOARD SYSTEMS JOURNAL

February 1984

No. 16

TABLE OF CONTENTS

Extending MicroSphere's Color Graphics System	4
Double Density on the BB I	6
Interfacing the Microline to WordStar 3.30	8
KayPro Column	12
Slicer Column	18
SBasic	20
BB II: Modifying Andy Bakkers' Interface	25
FORTHwords	26
C'ing Clearly	28
Pascal Procedures	30
Xerox 820 Column	34
On Your Own	38
"Inside CP/M" Review	39
Using DBase II Down Under	40
Technical Tips	44

"THE ORIGINAL BIG BOARD"


OEM - INDUSTRIAL - BUSINESS - SCIENTIFIC

SINGLE BOARD COMPUTER KIT! Z-80 CPU! 64K RAM!

(DO NOT CONFUSE WITH ANY OF OUR FLATTERING IMITATORS!)



For All Sockets Installed
And Soldered Add \$50.
(Not For Blank PCB) PARTIALLY ASSEMBLED



and WANT MORE INFO? Full Documentation Schematics

THE BIG BOARD PROJECT: With thousands sold worldwide and over two years of field experience, the Big Board may just be one of the most reliable single board computers available today. This is the same design that was licensed by Xerox Corp. as the basis for their 820 computer.

The Big Board gives you the right mix of most needed computing features all on one board. The Big Board was designed from scratch to run the latest version of CP/M*. Just imagine all the off-the-shelf software that can be run on the Big Board without any modifications needed.

FULLY SOCKETED! FEATURES: (Remember, all this on one board!) 900 (64K KIT BASIC I/O)

> SAME AS AN 8 IN. DRIVE. REQUIRES: +5V @ 3 AMPS + - 12V @ .5 AMPS

64K RAM

Uses Industry standard 4116 RAM's. All 64K is available to the user, our VIDEO and EPROM sections do not make holes in system RAM. Also, very special care was taken in the RAM array PC layout to eliminate potential noise and glitches.

7-80 CPU

Running at 2.5 MHZ. Handles all 4116 RAM refresh and supports Mode 2 INTERUPTS. Fully buffered and runs 8080 software.

SERIAL I/O (OPTIONAL)

Full 2 channels using the Z80 SIO and the SMC 8116 Baud Rate Generator. FULL RS232I For synchronous or asynchronous communication. In synchronous mode, the clocks can be transmitted or received by a modem. Both channels can be set up for either data-communication or data-terminals. Supports mode 2 Int. Price for all parts and connectors: \$39.95

BASIC I/O

Consists of separate parallel port (Z80 PIO) for use with an ASCII encoded keyboard for input. Output would be on the 80 x 24 Video Display.

BLANK PC BOARD - \$99.95

The blank Big Board PC Board comes complete with full documentation (including schematics), the character ROM, the PFM 3.3 MONITOR ROM, and a diskette with the source of our BIOS, BOOT, and PFM 3.3 MONITOR.

24 x 80 CHARACTER VIDEO

With a crisp, flicker-free display that looks extremely sharp even on small monitors. Hardware scroll and full cursor control. Composite video or split video and sync. Character set is supplied on a 2716 style ROM, making customized fonts easy. Sync pulses can be any desired length or polarity. Video may be inverted or true. 5 x 7 Matrix - Upper & Lower Case.

FLOPPY DISC CONTROLLER

Uses WD1771 controller chip with a TTL Data Separator for enhanced reliability. IBM 3740 compatible. Supports up to lour 8 inch disc drives. Directly compatible with standard Shugart drives such as the SA800 or SA801. Drives can be configured for remote AC off-on. Runs CP/M* 2.2.

TWO PORT PARALLEL I/O (OPTIONAL)

Uses Z-80 PIO. Full 16 bits, fully buffered, bi-directional. Uses selectable hand shake polarity. Set of all parts and connectors for parallel I/O: \$19.95

REAL TIME CLOCK (OPTIONAL)

Uses Z-80 CTC. Can be configured as a Counter on Real Time Clock. Set of all parts: \$9.95

CP/M* 2.2 FOR BIG BOARD

The popular CP/M* D.O.S. to run on Big Board is available for \$139.00.

DOUBLE DENSITY ADAPTER BOARD -- \$149.95 (A&T)

Requires no cuts or MODS to an existing Big Board. Gives up to 670K storage on a single sided 8 in. diskette. With software to patch your CP/M° 2.2.

PFM 3.3 2K SYSTEM MONITOR

The real power of the Big Board lies in its PFM 3.3 on board monitor. PFM commands include: Dump Memory, Boot CP/M*, Copy, Examine, Fill Memory, Test Memory, Go To, Read and Write I/O Ports, Disc Read (Drive, Track, Sector), and Search PFM occupies one of the four 2716 EPROM locations provided. Z-80 is a Trademark of Zilog.

Digital Research Computers

P.O. BOX 461565 • GARLAND, TEXAS 75046 • (214) 271-3538

TERMS: Shipments will be made approximately 3 to 6 weeks after we receive your order. VISA, MC, cash accepted. We will accept COD's (for the Big Board only) with a \$75 deposit. Balance UPS COD. Add \$4.00 shipping.

USA AND CANADA ONLY

MICRO CORNUCOPIA

P.O. Box 223 Bend, Oregon 97709 503-382-8048

Editor & Publisher David J. Thompson

Assistant Editor Eric Belden

Graphic Design Sandra Thompson

Technical Department Dana Cotant

Advertising Director Alice Holbrow

> Staff Assistants Dorcas Dsenis Tracey Braas

Typography Patti Morris & Martin White Irish Setter

MICRO CORNUCOPIA is the single board systems journal supporting systems programming languages and single board systems—including the Big Board, Big Board II, Xerox 820, Kaypro, and Slicer.

MICRO CORNUCOPIA is published six times a year by Micro Cornucopia of Oregon, P.O. Box 223, Bend, Oregon 97709.

SUBSCRIPTION RATES:

1 yr.(6 issues)	\$16.00
1 yr.(first class)	\$20.00
1 yr.(Canada & Mexico)	\$20.00
1 yr.(other foreign)	\$26.00
Make all orders payable	in U.S.
funds on a U.S. bank, plea	se.

ADVERTISING RATES: Available on request.

CHANGE OF ADDRESS: Please send your old label and new address.

SOFTWARE, HARDWARE, AND BOOK VENDORS: We would very much like to review your CP/M & MSDOS compatible products. Send materials to the Review Department, Micro Cornucopia.

CP/M is a trademark of Digital Research, Inc. Copyright © 1983 by Micro Cornucopia All rights reserved

MICRO CORNUCOPIA

February 1984

The Single Board Systems Journal

No. 16

Home Sweet Home



Change

Change has been no stranger to Micro C these last three years. That's right, we were madly putting together a promotional piece on Micro Cornucopia for the Computer Faire, exactly three years ago. We didn't know what the magazine would look like but that didn't keep us from promoting it.

Anyway, we have seen a lot of change over those three years. First came the magazines (we were hoping to be able to fill 16 pages), then the users disks appeared, followed shortly by my decision to leave Tektronix and the first SOG (celebrating the first anniversary of issue #1).

Immediately after the first SOG, we took 10 days vacation. We chose to vacation in Central Oregon and it was during that vacation that we decided to move Micro C from Portland, Oregon, to the Bend area. So we spent the last half of the vacation on a guided tour of vacant houses. Take my word for it, real estate agents are not cut out to be travel guides.

Finding the right house was a nightmare because we needed space for living and space for Micro C. After searching for three months we finally signed the papers on our house and started moving. In early November, 1982, we were actually here. Micro C was running a bit late, but we were settled in and we had lots of space (the whole daylight basement) for Micro C.

Well, in one year we went from two of us (Sandy and me) to five (Dana, Dorcas, and Alice). But five weren't enough and our basement was quickly becoming a compression chamber (as attendees to SOG 2 can attest).

So we purchased a small house in a commercial district for Micro C. It's a

neat feeling little place right on the edge of downtown. And we purchased it so we'd have space for two more people.

Eric, Text Co-processor

Our latest addition is Eric Belden. Eric has a bachelor's in math and a masters in journalism and he has been teaching computer literacy and math at our local community college. Eric is trying to fill the "One good person" spot. So far he feels he is in way over his head—which means he feels like the rest of us.

Eric will be receiving the article submissions and columns so I will have more time to handle the serious business of publishing (such as making sure the garbage gets picked up and someone cuts the grass). See "On Your Own" in this issue for more information about my plans.

Anyway, Eric will be handling scheduling of articles and he will be doing the initial editing. New submissions should be sent to his attention. (Don't forget to indicate which disk etc. you would like in return.)

Submissions

As long as we're on the subject, here are a few guidelines for submissions.

1. Over-explain everything. Show it step by step. It's a lot easier for us to cut than add. (And safer.)

2. Include illustrations, if appropriate. They don't have to be pretty—Sandy redraws practically everything—just make them clear.

3. We'd appreciate it if you'd send your submission on disk if it's longer than a page. Please include a printout just in case the disk gets zapped in the mail.

4. Fancy formatting (justification) makes the typesetter throw up (not a pretty sight). We can unformat WordStar files pretty easily but don't add any hyphens (soft or otherwise). We have to remove all hyphens by hand so please don't add them.

Please put your name, address, and phone number on the disk, in the disk, and on the printout. Let us know if you

(continued on page 48)

LETTERS

Dear Editor,

I would like to thank you all for creating such a fine periodical and offering such useful information on hardware and software (some with considerable price savings over the 7-11 type computer shops).

I purchased FlowCharter from Haven Tree Software Limited. It is a great package and a much needed tool for maintaining documentation on a software project. We all know how important flow charts are and how much of a pain in the backsides they are to produce and maintain.

The Bloodthirsty License Agreement and Honest Disclaimer for the package are worth a million.

Howy Kyrk 18100 SW Augusta Aloha OR 97006

Dear Editor,

Wow! The gang at Micro Cornucopia is making the humble little Kaypro into one hot machine. First 5 MHz and now 800K per drive. Those PC clones better watch out.

There is one mod that many of us would love to see on the Kaypro and it's a 256K RAM disk. It ought to make PW swap files and TW work like a dream. I'm sure you'd have a lot of interest, especially from those of use who can't afford (and see little use for) a full-blown coprocessor.

One question: will the PRO-Monitor ROMs (II, 4, and 8) work with the Uniform software and still enable the Kaypro to read and write disks formatted for other machines?

Mike Perry 6035 40 th Ave NE Seattle, WA 98115

Editor's note:

Check with MicroSphere (503-388-1194) on the schedule for the RAM-disk. Tony did the design and it's fancier than the one he did for the BB I. It will do self diagnostics and print buffering as well as acting as a RAM disk. They are working on making it support 512K as well as 256K and it will be pretty cheap because you provide the RAM. (Also check with them on the price for the unpopulated color graphics board.)

About Uniform. This program takes information from CP/M when it interfaces with drive A: so drive A: can be any type of drive (II, 4 or 8). Drive B:, however, must be correct for your version of Uniform. (So if you have Uniform for the II then drive B: has to be a single-sided 40 track model.)

Dear Editor,

I had a real problem soldering parts onto the Xerox 820 board I got from BG Micro. After I wrote to Billy about the problem I got a telephone call from him.

He apologized most profusely and thanked me for bringing the problem to his attention. It turns out that about half of his boards are nickel plated and he is now including a warning notice with the board. They can be soldered with a very hot iron but you have to avoid heating the joint too long or the solder will wick up into the socket. This happened on to me on 4 pins.

He impressed me as a responsible businessman who wanted to keep me as a customer.

Victor R. Frank 12450 Skyline Blvd. Woodside CA 94062

Editor's note:

High quality circuit boards are sometimes plated with nickel before they are tinned. My guess is that someone simply forgot the tinning when they were manufacturing the boards.

Dear Editor,

I tried the Gilderfluke Z19 graphics converter in my Kaypro and pulled it out. It was not compatible with P.P.S software.

Al Paarmann 368 El Gaucho Rd. Santa Barbara CA 93111

Editor's note:

I assume you are talking, Al, about Perfect software. Doug Mobley of Gilderfluke says that out of over 100 boards in use no one has had trouble with Perfect, at least not when running in the ADM-3A mode. (Perfect would have to be reconfigured for the H-19 terminal to run H-19 mode.) A few people have asked how to get graphics once they have installed the system. All they have to do is give the command to enter Heath mode.

Doug has added installation instructions for Wordstar 3.0 and 3.3 (distributed by Kaypro) so you can take advantage of Gilderfluke's reverse video and the fast reverse scroll. The board was designed in the

first place to run WordStar. The board is available for the Kaypro II and 4 and is \$175.

The only bug they've found is that the new board will barf if it sees an esc X or esc Y followed by a control character. It is, however, very unlikely that you'd need to enter such a sequence.

Kaypro II H19 Graphics Adapter \$175 GilderFluke & Co 120 Midway Dr Space 013 Anaheim, CA 92805 714-776-2207

Dear Editor,

How do I get new schematics from Cal-Tex?

Wayne R. Olson 5342 Frost Point Circle SE Prior Lake MN 55372

Editor's Note:

If you've already tried Bill Siegmund at Cal-Tex without success, try contacting Jim Ferguson at Ferguson engineering. See his ad in this issue for the address.

Dear Editor,

Could I have more information about your Kaypro ROM? I'm particularly interested in using it if it qualifies as the "fast monitor ROM" needed to do the 5 MHz modification.

I bought your C diskettes a few months back, and recently read the Kernighan/Ritchie text. Now I'm ready to give it a try only I don't want to create 60K object files that print "Hello, World," nor do I want to wait until I "grow with C" to make them smaller.

Could you give a few hints? Do I have to manually dissect the assembly routines to pull out the ones I need? Or do I need a macro assembler? Or what?

David Hillman 2006 NE Davis Portland OR 97232

Editor's Note:

Yes, the monitor ROM we offer is a very fast part. You can use it to run 5 MHz.

Also, the version of the Small C II compiler that generates .ASM files does make them a bit large. We also have a version of this compiler that generates output for Microsoft's M80 and L80 assembler and linker. It generates smaller code. If you have that assembler package (about \$200 I think), send back your copy of K7 and ask for the M80 version.

However, if you really want to get into C you might check out the C compilers from Software Toolworks or Aztec C. Both advertise in Micro C.

Dear Editor,

My system BB I is still not stable even after a year (and me, a designer of sophisticated micro equipment). I don't have much time to debug it! It crashes reliably at room temperature (70 degrees F) until it warms up. I believed my problem was in the RAM chips and I replaced them with 64K chips. That didn't fix it.

Then I found I could make it run when I used freeze spray on a few chips so I replaced them. Now it's still as bad and the freeze spray no longer helps. So, I beat the shit out of it to see if it was a bad connection. It wasn't. I removed a few sockets and soldered parts in, that didn't help. (I'm using a linear power supply with line filters and a parallel keyboard.)

Has anyone else had a similar experience? (I've learned to live with it.) Great magazine, hope you keep it going. Byte is so big, it takes a week to find all the articles.

David Shaw RR 3 Elgin, Ontario Canada

Editor's note:

This is an example of how much computers can teach us. You, for instance, are learning an invaluable skill and it's one that you should be able to market at top dollar.

You could teach seminars on "Learning to cope with an Incalcitrant Computer." I know dealers here in the Bend area who would purchase tickets for all their customers.

As for me, I don't have a clue. All three of our BB Is have been great. We've had trouble keeping more than one of our three BB IIs in service at any one time, however.

Dear Editor.

I would like to know how to program the character set EPROM for the Kaypro II

John Whittaker 2151 McNab Long Beach CA 90815

Editor's note:

See Issue #6 "Do it Yourself Character Set."

Dear Editor,

As a BB II user, I hope to see more articles and programs for its use. It seems the BB II does not share the popularity of the BB I and both will soon be replaced with 16 bit/32 bit machines. Keep doing the good job.

Hap Patterson 1714 Heritage Circle Lynchburg VA 24502

CP/M 2.2 License and disk for Scull-Tek Big Board	\$95.00
Reconfiguration of above for Ferguson Big Board or Xerox 820	
CP/M manuals	
C-DIFF file compare utility for CP/M	\$29.95

With an assortment of public domain utilities to fill the disk.

plus S2 shipping per box of 10



CP/M Public Domain Software Collections

Add \$2.00 each to copy CPMUG, RCPM or SIGM disks onto new disks Specify which disk numbers you want. There are over 200 disks full of public domain software available in these three collections. The best way to find out what is available is to order a box of 10 disks plus \$20 for copying and specify that you want the catalogs and abstracts, which will fill all tenthen after you read the abstracts order the disks you have picked out. Quantity discounts and custom CP M configurations available. Send \$1 for catalog which describes the above and other items in more detail.

NILCOX • ENTERPRISES

Illinois residents add 5% sales tax.
CP/M is a trademark of Digital Research. Inc.

P.O. BOX 395 • NAUVOO, ILLINOIS 62354 • (217) 453-2345

Dear Editor,

I have a Big Board I (called a Big Bore by my friends who have DMA chips). I plan to go Slicer and I was wondering if they will be coming up with PC-DOS/MS-DOS so we can develop systems for WANG-PC and IBM-PC on the Slicer.

Stefan Gunnarsson Spangavagen 53 161 48 Bromma Sweden

Editor's Note:

Yes Stephen, the Slicer should make a very good development system for PC-DOS software as soon as the PC compatible board is finished. As for the Big Bore, I think your friends would be hard-pressed to tell much difference between a BB I with a winchester and a BB II on the same drive. We have two systems here, one with DMA and one without. Their benchmark times are very close. Very close.

Dear Editor,

Once again, I have to say how pleased I have been with the Kaypro disks I have received. The Crowe assembler works great, especially with my .PRN file printer.

Incidentally, I found a bug in the Crowe Assembler. It apparently has problems with decimal literals larger than 1000. To get around the problem, just enter these large values in hex.

By the way, I don't dare use ZCPR when I'm in Perfect writer because if I accidentally enter cntl-C, I get dumped back to the system and lose my text.

If you would like to pass on my thanks to the authors, here is my list of favorite "Micro-C, Kaypro Disk Software".

- 1. Adventure—I can't deny it first place.
- 2. D.COM
- FMAP, UCAT, CAT—Hove good documentation.

4. FINDBD54—Works like a champ on those Elephant and Maxell disks. For your information, I have yet to have a failure on a 3M disk. By the way, if you're ever asked to recommend bulk disks, I got 100 from ALF Copy Service in Denver.

5. CRC.COM—It makes me comfortable.

I sure look forward to each issue's arrival. You are really doing a great job.

Robert O. Berry Canyon State Systems and Software P.O. Box 86 Sedona AZ 86336

Editor's note:

Thanks for the note about the Crowe assembler. See the Kaypro column in this issue for the ZCPR fix.

Dear Editor.

Will the Co-Power 8088 board be available for the BB II soon? Also, which assemblers will assemble Russell Smith's CBIOS for the BB II? I would like to add an AM9511 math chip so I can run Pascal MT+ faster.

Inge Sanden Nedre Blekkan N-7062 Bjorkmyr Norway

Editor's note:

I doubt that SWP will be working on the BB II in the near future, they are scrambling to get versions out for the Morrow system and some others (I understand). It looks like Russell Smith has his hands full at SWP.

Russell used Microsoft's M80 assembler and L80 linker to generate the code for the BB II. I suggest that you use this package; it is very powerful and has become the standard of the industry.

(Letters continued on page 47)

Extending MicroSphere's Color Graphics System

By Dana Cotant

We don't often promote add-on boards for the computers we support but there is a local group that is producing a really nice color graphics board for the Kaypro II and 4, as well as the Big Board I.

The board is designed around the Texas Instruments 9918 video display processor (VDP). The 9918 has all the block graphics capabilities of most standard graphics systems plus it is capable of sprite graphics.

A sprite is an opaque image that can easily be manipulated by software control. To move the sprite only requires writing the x and y coordinates to the VDP. Moving images on a standard block graphics system requires removing the image from its present location and replotting it at its new location. This can be very cumbersome. The sprite graphics system is much faster and easier to program.

 One thing very nice about this system is that you use an external color monitor for the graphics. This means you will have your original screen for such things as menus. Anyone who has worked with a graphics that swaps back and forth between two screen images (one for text and one for the graphics image) knows how time consuming and irritating it can be.

Programming the Color Graphics Board

The board comes with an impressive amount of software. One of the disks contains graphics editors which give you complete control over shapes, patterns and colors on the graphics screen. The other disk contains programming examples.

I have written some SBASIC programs for the board. The graphics procedures provided on this disk made the task a simple matter of writing the main loop.

The procedures included with the board take most of the burden out of graphics programming by providing the math routines necessary to do the basic graphics manipulation. By stringing the procedures together in different ways, sophisticated graphics programs are quite easy.

Here at Micro Cornucopia we have agreed to be the software exchange center for programs that run on the MicroS- phere board. I am just finishing a disk that contains some very interesting programs.

A Joy Stick Interface

There is a joystick connection on the color board so I went to the local K-Mart and picked up a cheap generic version designed for the ATARI and VIC 20 (so any sticks for these machines should work with my software). The stick uses switch closures to tell the computer of the stick position. (In fact, this interface will not work with the older potentiometer based joy sticks unless you add a comparator to convert the stick's outputs to TTL levels.)

The stick I purchased has 6 connections on the 9-position plug. One of these is common, one is the fire button switch, and the other 4 are the direction switches. As the joy stick is moved, the direction pin on the plug that corresponds with the direction the stick is moved is tied to the common pin by a switch closure.

On my particular stick, diagonal positions are coded by closing two switches. For example, moving the stick to the position between up and right closes the up and right pins on the plug. If we decide to let the signals be active low, the interface design becomes obvious.

Using the programmable PIO to our best advantage, the hardware design is trivial. Each of the signal pins can be pulled up by 10K resistors and the common pin tied to ground.

Now, only the direction pins closed by the stick will be pulled low. Decoding the joy stick becomes a matter of determining which of the pins is low and translating it to a direction.

The only hardware needed to complete the interface is a connector, 5 10K resistors, and a bypass capacitor. The connector is usually called a 9-position subminiature D male connector. I found one at Radio Shack for \$1.99 (RS part #276-1537). It had solder type connections on the back side.

The color graphics board has provisions for a 14-pin socket for the joy stick connections, but it is just as easy to solder jumpers between the D connector and the solder pads where the socket would go. Using this method would also

save the price of two 14-pin sockets and a 14-pin dip jumper. If you're careful, you can build up the terminating network on the color board itself.

Selecting the VDP or the PIO

The VDP chip uses the same address as the B side of the PIO it is plugged into. If we want to add a joy stick, it will need to use the B side of the PIO as well.

The VDP does not really use the PIO (it is a port itself) so all we need do is provide a method of selecting between the PIO (when we want to read the stick) and the VDP (when we want to read and write to the graphics screen). The board has the necessary decoding circuits to select either the PIO or the VDP depending on the state of a single input. As shipped this line is tied high so that the VDP is always selected. To free this input, remove R1. One end of R1 was tied to 5V and the other end ran to an open solder pad (marked J2 pad 3 on the schematic). Attach a jumper wire to this pad.

The destination of the free end of this jumper depends on the system you have. Big board owners would probably use the user definable bit of the system port. Kaypro folks should use the unused B side of the general purpose PIO. The A side on the Kaypro is used for the printer port but the B side is simply brought out to solder pads E7-E14.

The user definable bit on the Big Board is bit 4 so let's use that bit on the Kaypro port as well. Add the free end of the jumper to E10 on the Kaypro or terminal 8 of the power connector (TB1) on the big board. Now when bit 4 on the port is high, the graphics chip is selected and when it is low the joy stick port is selected.

Software Drivers

There are several constants to be defined in order to write the port initialization software. I will use SBASIC for the examples here because it allows the use of long identifiers and can be easily translated to another structured language for those writing in C or Pascal. The constants are shown in Figure 1.

PIO Programming

If you are not familiar with PIO programming, some of the constants will

need some explanation.

We will be using both of the ports in the control mode (mode 3). In this mode the PIO is a bidirectional bit port. To set this mode, first you need to send 0CFh (mode3) to the control port of the PIO. The PIO will expect a second byte in this mode which will select which bits are to be inputs and which will be outputs.

A zero in a bit position will set that bit of the PIO as an output and a one will set it as an input. For the Big Board BIT-PORT, bit 3 is the only bit that is an input. It is used as a keyboard data available signal. So 4isoutput has a one in bit position 3. On the Kaypro, it really doesn't matter which bits we set to input since none of them are used on this port. The only important thing is to make sure there is a zero in bit position 4.

The first order of business is setting up the BITPORT so that we can use it to select between the VDP and the PIO.

procedure set_bit_port

out BITCNTL, mode_3
out BITCNTL, 4_is_output

end of set_bit_port

Now we will be able to select between the VDP chip and the PIO with the following procedure. The flag should be true to select the VDP chip or false to select the PIO (constants PIO = 0000h and VDP = offffh can be used by the calling program as flags, e.g. portselect PIO would select the PIO).

procedure port_select (flag = integer)

var status = integer
 status = inp(BITPORT)
IF (flag) THEN
 out BITPORT, status OR on_mask
 ELSE
 out BITPORT, status AND off_mask

end of port_select

With this complete we may now initialize the joy stick port. This need only be done once at the beginning of the program. Notice that we use the portselect procedure to select the PIO before attempting to set it up for the joy stick. When we exit we will first turn the VDP back on.

procedure set_up_stick

port_select PIO
 out Joy_Control, mode_3
 out Joy_Control, stick_bits
 out Joy_Port, 0E0h

:REM this sets the unused bits :REM to ones for ease of decoding

port_select VDP

end of set_up_stick

Now read joy stick with the following:

procedure read_stick

port_select PIO
 direction = inp (Joy_Port)
port_select VDP

end of read_stick

All that is left to do is decode the direction. The following hex values will be returned for each of directions listed:

UP	OFEh	RIGHT-UP	0F6h
DOWN	OFDh	RIGHT-DOWN	0F5h
LEFT	OFBh	LEFT-UP	OFAh
RIGHT	0F7h	LEFT-DOWN	0F9h

If the fire button is pressed, the high nibble will become E hex. The directions can be decoded with a CASE statement or bit wise depending on the application.

New Disk

Kaypro disk K20 has the following graphics programs:


SKETCH.COM lets you move a pen around the screen under keyboard or joystick control. Lets you plot and unplot points at will and select any of 16 colors at the pen location. Includes source in SBASIC.

PACMAN.COM which is Don Brittain's very realistic version of the arcade game with keyboard and joystick versions. Now it also works with the Kaypro keypad. Includes source in C for Aztec C from Manx.

Plus, this disk contains four new SBA-SIC procedures for the color graphics board. Procedures include: unplot, improved screen control, and joystick control.

Figure 1 - Constants for SBASIC

Identifier	Meaning	Kaypro	Big Board
VDPDATA	Data port for VDP chip	30	10
VDPCNTL	Control port for VDP	31	11
Joy Port	Joy stick data port	30	10
Joy_Control	Joy stick control port	31	11
on mask	Byte mask for selecting VDP	010h	010h
off mask	Byte mask for selecting PIO	OEFh	OEFh
BITPORT	Fort that controls select bit	OOAh	01Ch
BITCNTL	Control of BITDATA	00Bh	01Dh
mode 3	Byte that sets port as bitport	OCFh	OCFh
4 is output	Byte that sets bit 4 as output	008h	008h
stick_bits	PIO bits used by joy stick	01Fh	01Fh



Double Density on the BB I

By Robert Carroll

216 Oswego Huntington Beach, CA 92648

This article is part design article and part review. Either way, it covers how you can get double density going on your BBI without paying double density prices.

Do It Yourself

This double density add-on can be built in one evening and you can run it single density with your present BB I CP/M until you get software for double density.

Even to run single density, however, you will need to make one change to your monitor (or patch it in RAM) if your drives will not handle a 3 ms step rate. You need to change RAM location FF6A (step rate) from 00H to 01H to go back to a 6 ms step rate.

And, once you go double density, your processor will need to be running at least 4 MHz. You can even use Trevor Marshall's 5 MHz modification (see Issue #11, page 14).

The 2795 disk controller is really three chips in one. After you put together the controller circuit, you can align it in about 10 minutes.

All you need is a 2 MHz clock (available on the BB) and +5V plus an oscilloscope and frequency counter. The scope (which can substitute for the counter) needs to be able to measure 200 ns.

I am using Jim Monesmith's software and PROM set. If you send Jim a disk with CP/M on it and two 2716-1s, he will incorporate his double density BIOS into your CP/M and he will burn his deluxe monitor into your ROMs. All this, including ZCPR and the source listings, for \$50

Jim Monesmith 438 Patterson Rd Dayton, OH 45419 513-298-6926 home

I've had his software package running here for a year without any trouble (outside of operator error).

To wire in the new socket, follow the wiring list in Figure 1.

Modifications to the Big Board

- 1. Remove and store U98.
- 2. Remove U104 and bend out pins 4, 5, 6, 8, 9, and 10 and reinstall it.


- 3. Jumper U102 pin 27 to U101 pin 6.
- 4. Cut trace running to U102 pin 37.
- 5. Jumper U102 pin 37 to TB1 pin 8 (PA4 DDSEL).

Alignment

- 1. Connect 2 MHz clock to pin 24.
- 2. Connect +5V to pin 21, return to pin 20.
- 3. Jumper pin 37 to ground and turn on supply.
- 4. Momentarily ground pin 19 (reset). Then jumper pin 22 to ground.
- 5. Attach scope to pin 31 and adjust 10K pot until the pulse width is 200 ns.
- 6. Attach scope to pin 29 and adjust 50K pot until the pulse width is 250 ns.
- 7. Connect frequency counter (or scope) to pin 16 and adjust variable capacitor to set frequency to 500 KHz.
- 8. Remove jumper from pin 37 and verify that the frequency on pin 16 becomes 250 KHz. (Pin 37 is the SD/DD switch.)
- Disconnect power, clock, and pin 22 jumper.
- 10. Remove and store the 1771 and plug your new 40-pin header into the 1771's socket. (Make sure pin 1 is right.)
- 11. Now reconnect as in steps 1 through 4.
- 12. Note pin 22 must be high whenever the system is reset.

AstroTronics Board

If you prefer to save a little time and effort you can purchase the AstroTronics 2795 board, available for \$19 (bare board) or \$79 for the kit. The board is well laid out, but it would be nice if it were silk screened and solder masked. The documentation is clear but there is no parts list. John says a parts list is coming.



Wiring U104
(See Modifications to the BB, step 2)

Figure 1 - Wiring List for the 1771 Socket

1771 socket		2795 socket
Pin#		Pin#
1 -5V	1042000	1 (to 2795 pin 29)
2 WE	TO	2
3 CS	TO	3
4 RE	TO	4
5 AO	TO	5
6 A1	TO	6
7 DAL 0	TO	7
8 DAL 1	TO	8
9 DAL 2	TO	9
10 DAL 3	TO	10
11 DAL 4	TO	11
12 DAL 5 13 DAL 6	TO	12
14 DAL 7	TO	13 14
15 STEP/PH1	TO	15
16 DIRC/PH2	TO	16
17 PH3	10	17 (5"/8" SELECT)
18 3PM		18 RPW
19 MR	TO	19
20 GND	TO	20
21 +5V	TO	21
22 TEST	TO	22
23 HLT	TO	40 HLT
		NOTE PIN DIFFERENCE)
24 CLK	TO	24
25 XTDS		25 SSO
26 FDCLK		26 VCO
27 FDDATA	TO	27
28 HLD	TO	28
29 TG43	TO	29
30 WG	TO	30
31 WD	TO	31
32 READY	TO	32
33 WF		33 WPW
34 TROO	TO	34
35 IP	TO	35
36 WPRT	TO	36
37 DINT	TO	37 DDSEL
38 DRQ	TO	38
39 INTRQ	TO	39
40 +12V		23 CHARGE PUMP


Connect together the pin from the 1771 socket with the pin from the 2795 socket wherever there is a "TO" in the above table. If there is no "TO" then the pins are not connected.

Parts List

1 WD 2795 controller 1 40-pin DIP socket 1 10K trim pot 1 50K trim pot 1 1K 1/4 watt resistor 1 1N914 diode 1 5-60 pf variable cap. 1 .15 uf capacitor 1 .1 uf 25V bypass cap. Wiring the 2795 into the 1771 Socket

WD 1771 SOCKET

WD 2795



RP/M

By the author of Hayden's "CP/M Revealed."

New resident console processor RCP and new resident disk operating system RDOS replace CCP and BDOS without TPA size change.

User 0 files common to all users; user number visible in system prompt; file size and user assignment displayed by DIR; cross-drive command file search; paged TYPE display with selectable page size. SUBMIT runs on any drive with multiple command files conditionally invoked by CALL. An automatic disk flaw processing mechanism isolates unuseable sectors. For high capacity disk systems RDOS can provide instantaneous directory access and delete redundant nondismountable disk logins. RPMGEN and GETRPM automatically self-install RP/M on any computer currently running CP/M® 2.2. Source program assembly listings of RCP and RDOS appear in the RP/M user's manual.

Manual alone \$55; manual with RPMGEN.COM and GETRPM.COM with utilities on 8" SSSD \$75. Shipping \$5 (\$10 nonUS). MC, VISA.

microMethods

VIDEO TERMINAL WITH

MANY HIGH END FEATURES

P.O. Box G Warrenton, OR 97146 118 SW First St. (503) 861-1765

ABLE II VT
INTELLIGENT STAND ALONE

• Easy Emulation • A Very Powerful Low Cost Terminal Board • 6502 CPU & 6845 Video Controller • 4K Control in 2732 EPROM • Emulate or Customize with powerful download feature • Custom programs and escape tables retained during power down • Defaults to control ROM tables (H19 Compatible) when not modified • Month to MSEC Real Time Clock; Display to Sec, Transmit to MSEC • Reliable battery interface for clock and 2K user RAM • Menu driven set-up • Powers up as previously configured • History, for communications analysis, displays last 256 video, escape, and control char received • 2 Program/Menu selectable RS-232 compatible ports, with Daisy Chain • 16 Program/Menu selectable baud rates (50 to 19,200) • TTL and RS-232 level baud clock outputs • 6 Program/Menu selectable bell tones • 9 Menu cursor selections (Box, underline, overline/solid, blink fast or slow) . Menu selectable auto LF on CR and/or Auto CR on LF or neither • Local, full duplex, simplex operation • 80x50 video with 80x24 screen window • Up/Down scroll with non-destruct mode Transmit screen from top to cursor • cursor home, forward, backward, up, down . Horz. tab . full X-Y cursor control including save, restore, and report cursor • cursor on/off • clear screen, clear line, erase to end of screen, to beginning of screen, to end of line, to beginning of line • Char selectable, normal, inverse, blink, and low intensity • 96 Upper and Lower case with descenders • 32 interconnecting line/block graphic set • type ahead buffer • 81/2x11 silk screened, double sided, glass-epoxy PC board • only uses easy to get parts • requires parallel ASCII keyboard and standard composite

Bare Board, Programmed Control & Char. Gen EPROMS, Complete Detailed Documentation including Schematic and Source Listing.

video monitor • made in U.S.A. •

— NOW ONLY \$79.95 —

Complete Documentation — \$10 (Refundable with purchase)

Will Accept MC & VISA

*** CALL OR WRITE ***

LINGER ENTERPRISES, INC.

PO Box 5783

Newport News, VA 23605 804-244-3874

Add \$2 shipping & handling (VA residents add 4% tax)

Interfacing the Microline to WordStar 3.30

By Mike Hirasuna

10528-C1 Cross Fox Lane Columbia MD 21044

WordStar and the Okidata Microline 92 aren't bad together even when they are not properly interfaced. However, with a little help, they can do great things.

This combination was my first word processing system and I was quite pleased until I discovered everything I couldn't do: superscripts, subscripts, continuous underlining, enhanced printing, emphasized printing, correspondence quality, character width selection, and line spacing selection. However, all these were possible if my WordStar could just speak properly to my Microline.

The solution? Use WINSTALL (which comes with WordStar) to define the user patches. WINSTALL is self-explanatory and easy to use. What follows are some suggestions on how to use WINSTALL to interface WordStar to an Okidata Microline 92 printer.

Escape Sequence

Even though there are only four user patches, it is possible to define all of the important printer options. The trick is to define one of the user patches as just 1Bh, which is the hex code for ESC. Cntl-PE seems an obvious choice. The character which follows becomes the printer control character. The following is a brief list; there is a complete list in the printer's manual.

Printer Options

ESC 0 Data quality
ESC 1 Correspondence quality
ESC 2 User programmed
ESC 6 Use 6 1/inch
ESC 8 Use 8 1/inch
ESC 0 Start cont underlining
ESC D Stop cont underlining
ESC T Enter emphasized print
ESC T Enter emphasized print
ESC I Enter normal print
ESC J Start superscript
ESC K Stop superscript
ESC L Start subscript
ESC M Stop subscript

Note: You must use capital letters where shown. Lower case letters have a different ASCII code (and besides they don't look as nice).

Character Pitch

Unfortunately, not all printer functions can be defined as an escape sequence. There are four control characters which define character pitch. The hex codes for these controls are:

1C Hex For 12 cpi 1D Hex For 17 cpi 1E Hex For 10 cpi 1F Hex Double present width

Note: There is no command to undouble at the current pitch. The printer will automatically exit the double-width mode when a new pitch is specified.

Three of these controls can be defined with user patches. I use cntl-PR for 12 cpi, cntl-PQ for 17 cpi, and cntl-PW for double width. The control for 10 cpi will be explained below. The following is a summary of user patches:

cntl-PQ 1Dh 17 cpi (sQueezed printing)
cntl-PW 1Fh double width(Width doubled)
cntl-PE 1Bh ESC lead-in (Escape sequence)
cntl-PR 1Ch 12 cpi (Reduced printing)

The normal pitch, 10 cpi, can be set with the pitch controls, cntl-PA and cntl-PN. Both commands must be used for this function. WordStar will only issue the command sequence for cntl-PN if the last pitch control was a cntl-PA.

The alternate pitch mode, entered with cntl-PA, should not be used to print anything. In this mode, WordStar will issue the command sequence for cntl-PA at the start of every line, and issue the command sequence for cntl-PN at the end of every line.

These control sequences can be defined in the pitch control section of WIN-STALL. The alternate pitch command sequence, cntl-PA, should be empty. The normal pitch command sequence, cntl-PN, should be 1Eh, for 10 cpi. When editing a document in WordStar, the normal pitch is invoked with cntl-PA cntl-PN. It is used to return from 12 cpi, 17 cpi, or double width modes.

Superscript and Subscript

Some of the printer functions may have alternate definitions. Superscript and subscript may be defined with their escape sequence or with the standard WordStar controls, cntl-PT for superscript and cntl-PV for subscript. These may be defined in the carriage roll section of WINSTALL.

The roll-up carriage sequence should be defined as ESC J. The roll-down carriage sequence should be defined as ESC L. These controls act as toggles. The first occurrence of cntl-PT will roll up the carriage; the second occurrence will roll down the carriage. The first occurrence of cntl-PV will roll down the carriage; the second occurrence will roll up the carriage.

Continuous Underlining

Since the Microline 92 does not use a two-color ribbon, the WordStar ribbon control, cntl-PY, can be used for continuous underlining. WordStar uses cntl-PY as a toggle to start and stop this function.

In WINSTALL, the cntl-PY function is defined in the ribbon selection section. The alternate selection control should be set as ESC C to start the underlining. The standard selection control should be set as ESC D to stop the underlining.

The ribbon selection control has one advantage over its equivalent escape sequence. When in the alternate selection, WordStar will automatically revert back, momentarily, to the standard section to print out headers and footers.

Double Strike and Boldface

One of the nicer features of the Microline 92 is the correspondence quality printout. There are, however, some anomalies. Enhanced or emphasized printing has no effect when you are in the correspondence mode. More importantly, correspondence mode cannot be used with the 17 cpi pitch (or its double width form).

This problem may be solved by using the double strike or the boldface controls in WordStar. Because the Microline 92 does not allow micro-spacing, there is no difference between the default double strike and the default boldface.

With WINSTALL, you can define boldface to be four overstrikes. This gives a sharp image which is almost as good as correspondence quality.

Page Offset

The WordStar default for text indentation is 8 characters. This means that it outputs 8 spaces at the start of every line. This can cause problems with the Okidata printer in an alternate pitch or in the

continuous underlining mode. The solution is to set WordStar's page offset to 0, and then use an escape sequence to tell the printer what indent you want.

The page offset can be defined with the PO dot command, but it is better to use WINSTALL to default the page offset to 0 in the "Menu of WordStar Features" section.

The left margin is defined with ESC % C N1 N2 N3, where the N's represent three decimal digits which define the print column. The first column is 001, and there are 12 columns to the standard character position. Hence, cntl-PE%C097 will define the left margin at column 97, which is equivalent to 8 character positions.

An easier way to set the left margin is with the initialization sequence defined in WINSTALL. The initialization sequence is sent at the start of every document printed by WordStar. It can be programmed to contain the escape sequence for setting the left margin at column 97. The left margin should be set back to column 1 with the reset sequence which is sent at the end of every document.

Clearing the Printer

The printer can be cleared with an 18h. The printer will return to the data mode, go to 10 cpi and 6 lpi, and stop any special printing feature. However, it will not affect the left margin or the down-line character set. The clear command should also be included in the initialization and reset sequences.

Command Summary

A summary of command sequences for standard WordStar controls is given below. Note that the initialization sequence has an additional command, 0Dh, which will return the carriage.

entl-PA		empt	· v	
entl-PN		1Eh		
cntl-PY	(alternate)	1Bh	43h	
cntl-PY	(standard)	1Bh	44h	
cntl-PT		1Bh	4Ah	
cntl-PV		1Bh	4Ch	

Boldface: Page Offset:

Initialization: 18h ODh 1Bh 25h 43h 30h 39h 37h 18h 1Bh 25h 43h 30h 30h 31h

Using PIP

Before installing these options, you may want to experiment with them. The Okidata manual suggests you write small BASIC programs to send the con-

trols. There is an easier way.


Using PIP, you can redirect the keyboard to the printer (LST:=CON:). The ASCII code of anything typed on the keyboard will be sent to the printer (except cntl-Z which is used to terminate the transmission). Fortunately, you don't usually need to send cntl-Z code (1Ah) to the printer.

The printer will not print until its line buffer is full or it receives a carriage return or line feed. If it is not obvious how to send the first 32 codes, the following table will help:

00h	cntl-@				
01h	entl-A				
02h	ent1-B				
03h	entl-C				
	4				
	E .				
19h	entl-Y				
1Ah	ent1-Z				
1Bh	ent1-[(or E	SC)		
1Ch	entl-\				
1Dh	entl-]				
1Eh	entl-^	(i.e.	control	^)	
1Fh	entl	(i.e.	control	-)	

not used alone entl-PAcntl-PN starts 10 epi starts continuous underlining stops continuous underlining defines superscripts defines subscripts

A NEW TWIST



FAT JACK READING RACK

- SEE COPY-SCREEN/KEYBOARD AT THE SAME TIME.
- **★ EASILY ATTACHED TO** ANY KAYPRO
- ★ 16" WIDE AND STRONG FULLY SUPPORTS - BOOKS MAGAZINES . REPORTS WITH UNIQUE PAGECLIP™

Dealer and group inquiries invited.

ONLY \$17.95 + \$1.50 Shipping Washington Residents Add \$1.45 Sales Tax.
Cashier Checks & Money Orders Shipped Promptly.
(Personal Checks Must Clear - 2 Weeks.) (Price & Configuration subject to change without notice.)

The Best Accessory You'll Ever Buy For Your Kaypro[™]

ORDER FROM: TWIST, INC. P.O. Box 1406, Renton, WA 98057

EXPAND YOUR PROTENTIAL

HARD DISK ADAPTOR

Allows you to add megabytes of storage. Easy to install. Includes complete software and documentation. \$95.00 single unit quantity.

☆ CP/M 3.0 BIOS UPGRADE

Allows installation of CP/M 3.0 giving you a faster more powerful system. \$50.00 single unit quantity.

PRONET

 local network for Kaypro computers. Call to order or for information

DEM/DEALER INQUIRIES WELCOME Quantity Discount Available.



Solutions that work for you

307 SIXTH STREET **HUNTINGTON BEACH, CA 92648** (714) 960-7498

Shedding some light on the best EProm Eraser on the market.

The unique Orbital EProm
Eraser—multiple exposure multiplies productivity. Here's how to improve your productivity by 140%. Without multiplying your overhead by the same factor. It's easy, with the Orbital EProm Eraser, which erases up to 14 units at a time. All in just twenty minutes.

Totally unique, but conforms to all data sheet specifications erasing manuals. There's no other product like it on the market, yet the Orbital EProm Eraser performs like a proven winner. With even ultra-violet exposure that conforms to Federal Standards for UV radiation at 2537 angstroms.

Design features include:

· Automatic safety switch

- Custom designed long-life lamp (replacements available)
- LED indicator
- U.L. Approval another unique feature

The most unique feature of all—the price: \$4005

including shipping.
Shipped UPS: Master Charge or VISA
Order 1-800-241-8003, ext. 2537.
Check or Money Order payable to:

EProm Eraser Co.

1753 Tully Circle, Atlanta, Ga. 30329

Big Board and Xerox 820 EPROM programmer kit



\$75.00

Backed by our "Money Back Customer Satisfaction Policy"

- One of the BEST values in EPROM programmers
- Plugs into parallel port
- Kit includes all parts, including ribbon cable and ZIF socket
- User friendly menu-driven software written in RDS C
- Includes all 1800 lines of source code
- Verifies erased EPROMs
- Programs
- Displays contents in Hex and ASCII
- Saves EPROM to disk
- Loads EPROM from disk
- Verifies programming
- Calculates EPROMs checksum
- Programs 2516, 2716 (5V), and 2532 EPROMs


Send for a complete documentation package or send your check or money order in the amount of \$80 in U.S. funds (includes \$5 shipping and handling) for immediate delivery. (N.Y. State residents add 7% sales tax.)



Kenmore Computer Technologies P.O. Box 635 Kemmore, NY 14217 (716) 877-0617

"BIG BOARD II"

4 MHz Z80-A SINGLE BOARD COMPUTER WITH "SASI" HARD-DISK INTERFACE



\$795 ASSEMBLED & TESTED

\$545 "UNKIT"*

\$245 PC BOARD WITH 16 PARTS

Jim Ferguson, the designer of the "Big Board" distributed by Digital Research Computers, has produced a stunning new computer that Cal-Tex Computers has been shipping for a year. Called "Big Board II", it has the following features:

■ 4 MHz Z80-A CPU and Peripheral Chips

The new Ferguson computer runs at 4 MHz. Its Monitor code is lean, uses Mode 2 interrupts, and makes good use of the Z80-A DMA chip.

■ 64K Dynamic RAM + 4K Static CRT RAM + 24K E(E)PROM or Static RAM

"Big Board II" has three memory banks. The first memory bank has eight 4164 DRAMs that provide 60K of user space and 4K of monitor space. The second memory bank has two 2Kx8 SRAMs for the memory-mapped CRT display and space for six 2732As, 2Kx8 state FAMs, or pin-compatible EEPROMS. The third memory bank is for RAM or ROM added to the board via the STD bus. Whether bought as a bare board, an "unkit", or assembled and tested, it comes with a 2732 EPROM containing Russell Smith's superb

Multiple-Density Controller for SS/DS Floppy Disks

The new Cal-Tex single-board computer has a multiple-density disk controller, it can use 1793 or 8877 controller chips since it generates the side signal with TTL parts. The board has two connectors for disk signals, one with 34 pins for 5.25" drives, the other with 50 pins for 6" drives.

Vastly Improved CRT Display

The new Ferguson SBC uses a 6845 CRT controller and SMC 8002 video attributes controller to produce a display rivaling the display of quality terminals. There are three display modes Character, block graphics, and line-graphics. The board emulates an ADM-31 with 24 lines of 80 characters formed by a 7x9 dot matrix.

STD Bus

The new Ferguson computer has an STD Bus port for easy system expansion

M DMA

The new Ferguson computer has a Z80-A DMA chip that will allow byte-wise data transfers at 500 KBytes per second and bit-senal transfers via the Z80-A SIO at 880 Kbits per second with minimal processer overhead. When a hard-disc subsystem is added the DMA chip makes impressive disk performance possible.

SIZE: 8.75" x 15.5"

POWER: +5V @ 3A, +-12V @ 0.1A

■ "SASI" Interface for Winchester Disks

Our "Big Board II" implements the Host portion of the "Shugart Associates Systems interface." Acding a Winchester disk drive is no harder than attaching a floppy-disk drive. A user simply 1) runs a lifty-conductor ribbon cable from a header on the board to a Xebec controller that costs only \$295 and implements the controller portion of the SASI interface, 2) cables the controller to a Seagate Technology ST-506 hard disk or one compatible with it, and 3) provides power for the controller-card and drive. Since our CBIOS contains code for communicating with hard-disks, that's all a user has to do to add a Winchester to a system!

■ Two Synchronous/Asynchronous Serial Ports

With a Z80-A SIO/O and a Z80-A CTC as a baud-rate generator, the new Ferguson computer has two full RS232-C ports. It autobauds on both

■ A Parallel Keyboard Port + Four Other Parallel Ports for User I/O

The new Cal-Tex single-board computer has one parallel port for an ASCII keyboard and four others for user-defined I/O.

■ Two Z80-A CTCs = Eight Programmable Counters/Timers

The new Ferguson computer has two Z80-A CTCs. One is used to clock data into and out of the Z80-A SIO/O, while the other is for systems and applications use.

■ PROM Programming Circuitry

The new Cal-Tex SBC has circuitry for programming 2716s, 2732(A)s, or pincombatible EEPROMs.

■ CP/M 2.2**

CP/M with Hussell Smith's CBIOS for the new Cal-Tex computer is available for \$150 The CBIOS is available separately for \$25.

* The "unkit" is a fully-socketed, wave-soldered "Big Board II". It requires NO soldering All an "unkit" purchaser must do is carefully insert the prime ICs we supply in the proper sockets and systematically proceed to bring up and test the board.

**CP M is a registered trademark of Digital Research

CAL-TEX COMPUTERS, INC.

780 E. TRIMBLE ROAD #504 • SAN JOSE. CA 95131 • (408) 942-1424

Terms: Orders paid for with a cashier's check or bank card will be shipped within three working days. Orders paid for with a personal check will be shipped within three weeks. Add \$5 for packing & shipping in North America.

The Kaypro Column

By David Thompson

If you're wondering whether your Kaypro II is really 4, just wait. Kaypro Corp is changing things all around again. Only this time the Kaypro 4 and 10 will share the same processor board and the II will have a 4 board. OK?

The new Kaypro 4 uses the Kaypro 10 board and two non-Tandon half-wide drives. (Rumors are coming in that Tandon was sending its best drives to IBM and everyone else is getting the dregs so Kaypro is looking for a source of dependable units.)

The Kaypro II will have the original Kaypro 4 board and ROM. In fact, the present Kaypro II and 4 systems have a simple monitor sign-on that says "Kaypro" rather than Kaypro II or Kaypro 4. That way they can use the exact same board and ROM. The only thing you have to do to this version of the Kaypro II to turn it into a 4 is change the drives to double sided 48 tpi units.

The new Kaypro 4 will actually have some features that the 10 won't have (at least for a while). It will have a new CTC timer and a modem built in. However, they aren't quite ready to ship the new 4. They are still cleaning up the software and the FCC has not yet certified that they pass the radiation restrictions.

Disk Alignment

I've been getting calls from dealers who have aligned Tandon drives down to a gnat's eyelash only to have them get strange again after they are re-installed in a Kaypro.

As I mentioned in a previous issue, the Tandon drives don't have much metal (mettle) so any stress you put on them when screwing them back into place will put them out of alignment.

Ideally, you would align them in place but that would be more difficult than doing dental work on an ant. So you have to take them out, align them, and then replace them as carefully as possible.

If you don't have a real alignment disk, find a factory distribution disk and then adjust the small concentric screw on the back of the drive until you have maximum output from the heads. Do this on track 13 hex (the middle track). After aligning on track 13, check tracks 0 and 27. If either 0 or 27 alignment is quite different than track 13 then you probably

have a warped frame and you might as well junk the drive.

You can use one of the disk utilities like DU.COM or our Kaypro diagnostic disk to get the the drive to step out to the proper track.

Morrow MD-11

I took a byte out of the Morrow MD-11 in Issue #14, page 21 and immediately got a nibble out of David Block, product manager for the 11.

I mentioned in #14 that their release didn't make sense because it inferred that they were not using a winchester controller. Well, it turns out that the Z80 is the winchester controller and it's the floppy controller (yep, no 1793 . . .). In fact, he mentioned that there were only 3 LSI chips in the system, the Z80, an SIO and a DART (asynchronous version of the SIO).

Well, after he told me that, I was too stunned to speak hardly (so I spoke softly). Everyone else is plugging in a Western Digital floppy controller chip and winchester controller card and calling it good. Not Morrow.

Speed

It turns out that they are using a few TTL chips, a small CRC generator chip (to check for bad disk sectors) and the Z80 to transfer data from disk to memo-

ry. They force the Z80 to execute a NOP instruction (a NOP means No OPeration) which it does very quickly. The Z80 then increments the address lines to point to the next instruction. The Morrow folks force-feed it another NOP, and on and on for the number of bytes being read off the disk.

Meanwhile, the little TTL chips have taken over the data bus and are transferring data into memory at the addresses selected by the Z80. Using this process, it takes 1.6 us per byte (5 Megabits per second) to transfer data into memory. The average disk access time is 80 ms. Since they are running 128 K and CP/M 3.0, they are also buffering the directory in RAM and doing track reads any time they go to the disk.

When you think about the speed they are getting and the bucks they are saving by removing most of the big chips (have you tried to buy a winchester controller card lately?), the system looks mighty interesting.

Wanted Typing Tutor

I've been getting a number of calls from Kaypro folks about a typing training program. Look, they have really great ones for Apples, Commodores, Ataris and Timex's. How about the Kaypro? After all, this would be a perfect project for SBASIC.

Figure 1 - ZCPR Patch for Kaypro

```
Note (cr) stands for carriage return.
Now enter:
A>ent1-C
           (hit the "C" key while holding down the cntl key)
               (it will ask you for source drive, answer A<cr>)
A>sysgen (cr>
               (it will ask for destination or return, answer (cr>)
               (you have just put a copy of your system tracks into memory)
A>save 34 zcpm.com (now you have put the memory copy into xcpm.com on disk)
A>ddt zcpm.com (now we load it back in under ddt so we can modify it)
  DDT VERS 2.2
 NEXT PC
 2300 0100
-s0c7a<cr>
               (the "s" lets you directly set the contents of memory)
0C7A 21 00<cr>
               (the contents were "21" we'll change them to "00")
0C7B 38 . (cr>
               (enter a period to tell ddt we're through setting bytes here)
-s0c83<cr>
               (now we're going to set bytes beginning at "0c83")
0C83 18 00(cr>
               (replace the 18 with 00)
0C84 F3 00(cr)
               (replace the F3 with 00)
0C85 CD .<cr>
               (end the set)
-cnt1-C
               (get out of ddt)
A>sysgen(cr>
               (it will ask for you source drive, answer <or> only)
               (it will ask for destination drive, answer A(cr>)
               (then answer (cr) alone to exit system)
```

Probably the best way to start would be to try out a few of the programs on those other systems. I happen to like the Apple program that has ships approaching the star base. Each ship has a word on it and the length of the word and the difficulty of its letters are determined by your level of expertise. If a ship reaches your starbase, you lose. A ship disappears if you enter its word correctly but another ship immediately starts from the left edge of the screen to take its place.

The speed at which the ships move across the screen should be adjustable. The letters that are being typed should show up on the screen (reduces the temptation to look at the keyboard). The backspace key should delete characters and the user must hit the spacebar to end a word.

There are a number of differing views about the order in which people should learn the characters. One study indicates that people should learn all the letters under the index fingers first. Another indicates that they should learn words as soon as possible. So combining the two you would begin with "frtgbv" with the left hand and "juyhnm" with the right hand.

That doesn't give you too many words, but once you add the third fingers "edc" and "ik," you have many words to work with, including word endings like "ing" and "ed."

Software Technical Support

If you have questions about any of the Kaypro software (particularly SBASIC), try calling their software technical support group. The direct dial number is 619-481-3920. No guarantees, but they try.

ZCPR Fix

We've received some calls from people who have ZCPR (disk K9) and have found two problems. First, they can't use the numeric keypad and second, when they hit cntl-C (when inside a text editor), they warm-boot out of the editor. (We've fixed the problem on the current disks.)

If you want to fix these problems, make up a disk with ZCPR in the system tracks (follow the instructions with disk K9 if you don't already have ZCPR in your system), then add DDT.COM and SYSGEN.COM from your original Kaypro system disk. Put this disk in drive A:. (See Figure 1 for the procedure.)

Now hit the reset button on the back of your Kaypro and after the reboot, you should have your keypad back.

Null Program

An empty file can be a lifesaver if you accidentally exited a program before saving the data. What you really want to do is be back in the program without writing over your work. With some programs, re-entering simply resets the data pointers so you don't save your data but it is worth a try. (See C'ing Clearly in this issue for another possible solution if this doesn't work.)

Anyway, if you find yourself back in the operating system when you'd rather be in the program, try this: (assuming you are on drive A:)

A>SAVE 0 REPEAT.COMcr> A>REPEATcr>

What you are doing is creating an empty file and then telling CP/M to run that file. Of course, when CPM loads RE-PEAT, it loads nothing, then it jumps to memory location 100H where it assumes the code for REPEAT begins. Well, of course, the code for your previous program should still begin at 100H so you are off and running.

Shugart Floppy Drives

One of the types of drives that Kaypro particularly likes is the Shugart SA 455. Bill MacDonald has had some of these drives reading and writing for 4 days straight without a single disk error. He also mentioned that Panasonic is making these drives for Shugart.

"When we first tried the Shugart we found that it wasn't practical. You'd find out that it was on track 17 but the track 0 line was being driven true so the computer thought that the head was on track 0 and all kinds of strange things happened. The problem turned out to be a programming error in the drive's microprocessor," Bill said.

He noted that Shugart threw out all

(Kaypro Column continued next page)

COLOR GRAPHICS BOARD — KayPro II & 4, and Big Board I. Assembled and tested color board has 16 colors, 32 sprites, and 16K of RAM. TMS 9918A color processor, 2 disks of software includes screen dump to disk and printer. Developed by Don Brittain. \$29995

COMPOSITE VIDEO
BOARD for KayPro II & 4
... generates standard
composite video for an
external monitor ... \$5095

PRO CHARACTER
ROM . . . a fast EPROM
with standard g's, q's and
colons; clears the snow on
some KayPro II's. \$2995

PASSWORD SECURITY LOCK for

KayPro II & 4. Accepts up to 12 character password. Please tell us which model KayPro you have. Monitor ROM also gives solid block cursor and better modem operation.

\$4995

ZENITH ZVM121 green 12" monitor, 40/80 column. \$9900

TMS 9918A COLOR PROCESSOR and 10.7368+ crystal. \$2995

RF MODULATOR

\$1995

COMING SOON

DISC for KayPro.
COMPOSITE VIDEO
BOARD for KayPro 10.
Call for details.

Dealer Inquiries Invited



Microsphere, Inc. P.O. Box 1221 - Bend, OR 97709 (503) 388-1194

DISK DRIVES

DIOIZDIII 4 TO
WINCHESTERS
MiniScribe 1006 \$295.00 (5%" Full Height, 6 Megabyte (unformated))
MiniScribe 2012 \$755.00 (5%" Full Height, 12 Megabyte (unformated))
MiniScribe 3012
MiniScribe 4020 \$905.00 (5¼" Full Height, 20 Megabyte (unformated))
FLOPPIES (Used)
CDC 9406 \$285.00 (8" Double Sided, Double Density)
SHUGART 801R \$150.00 (8" Single Sided, Double Density)
(O Olligio Siere) =


WARRANTY ON ALL DRIVES QUANTITY DISCOUNTS AVAILABLE

VISA & MASTER CHARGE ACCEPTED (Add 3% for Credit Card Charges) Shipping & Handling, Additional Charge

WESTERN AUTOMATION LABORATORIES, INC.

Call toll free: (800) 227-4637 Inside Colorado (303) 449-6400

5595 Arapahoe Road, Suite C, Boulder, Colorado 80303



ON-LINE TYPER

\$25

- o Converts your KayPro system into an electric typewriter
- Relocates to protected high memory where it's safe from warm boots and application programs
- Just type Control-1 even in the middle of a command or text entry, etc OLT saves everything, returning to the exact point where you left off
- Spaces, tabs and returns move the printhead at once so you always know just where you're typing
- Great for envelopes, printed forms, hasty notes. You can even change printer set-up codes on-the-fly, etc
- Ready to run for Epson-compatible printers including Gemini and IBM-PC. Easily installed for most others

\$ 25 SNAPSHOT

- o Print a copy of your KayPro screen anytime!
- Relocates to protected high memory where it's safe from warm boots and application programs
- Does not affect screen contents or program operation
- o Capture intermediate game and program results on paper
- Ready to run for all printers

*** SPECIAL ***

SST - Both On-Line Typer and SnapShot in one integrated package for only \$30

- K-FIX Permanently alters KayPro II CP/M (actually the BIOS) to:
- Automatically shut off drive motors when they are not in use a must for Perfect Writer Extinguish drive LEDs except during disk read or write - Find out what's really going on in there
- Change the default cold boot/reset serial baud rate to any of the 16 KayPro values No more BAUD.COM
- See September Byte, page 598, for more details New BIOS remains reproducible with SYSGEN, COPYNEW, etc
- Prices include airmail and handling Source code and U-Print manual included on disk Personal checks accepted for immediate shipment Please add 15% if remitting in Danadinf funds Guaranteed satisfaction or complete refund

(Kaypro Column continued)

the buggy drives and now the little Tandons look great.

However, just lately, someone called him offering him a bunch of Panasonic drives (about 2000 of them). Of course they turned out to be the buggy ones. So, be careful about special offers on Panasonic and Shugart drives. If they are the buggy ones, they will work just fine on systems that ignore the track 0 line but they'll do strange things on a Kaypro.

Bill noted that the quality of mini floppy drives has been improving substantially and that the highest quality drives have been Japanese imports (sounds familiar doesn't it).

Kaypro Publications

The original Kaypro users group magazine is \$12 per year from Kaypro Users' Group, Box 100, Malverne, NY 11565.

People's Computer has started its own national Kaypro users group and if you send them \$8.00, they'll send you their newsletter for a year. You can reach them at Peoples Computer, PO Box 28360, Queens NY, 11428.

NWKug (Northwest Kaypro Users

Group) has really done a good job putting together a newsletter for beginning users. And, they've been publishing as long as the Malverne based newsletter. Send \$10 for a year's subscription to NWKUG, PO Box 11, Portland, Or

The Spokane MicroComputers Users Group (SMUG) is aimed at CP/M users in general, but they have a very active Kaypro contingent. It's an interesting newsletter for \$12 per year. Contact them at PO Box 1753, Spokane, WA 99210.

"BASIC-K Magazine" is just a disk with a few Microsoft BASIC programs on it. They say you can use the programs as examples when you are doing your own MBASIC programming. However, after one look at the software, it was obvious to me that the programmer didn't want anyone figuring out what he was doing. The programs didn't do anything memorable either. The price is high (\$95 per year). You can contact them at 119 S 10th, Duncan, OK 73533.

And, of course, there is Profiles, the corporate rag from Kaypro. You are supposed to get a free year's subscription when you return your warranty card. This is a very nice looking magazine that does justice to the system. However, they've had trouble with their mailing list. If you aren't getting it, write to them at PO Box N, Del Mar, CA 92014. (Don't call; writing seems to work better.)

Drives for the PRO-8

I just found out that you can get the TEAC model 55F quad density halfheight drives for only \$215 each from National Diskon Corp. Their phone number is 415-490-7150. The TEACs draw about half the power of the Tandons and, like the CDC drives, they are supposed to be much better than Tandons.

I haven't ordered anything from Diskon yet so I can't endorse them, but at this price they might be worth a try. Plus, we are already working on a 4 drive version of the PRO-8 monitor.

Computer Components Unlimited has CDC quad density drives for \$219 each (at least they had about 100 left the last time I talked to them). I ordered a couple from them and they plugged right in. (Short the drive number you want and the M on the shunt.) head load relays so the heads aren't constantly riding on the disk. You can contact them at 1-800-847-1718.

Attention HP 3000 Users:

KAYPRO*

Terminal Emulator

Termtype-10 Compatible

ONLY \$50

* Kaypro is a trademark of Kaypro Corporation

PRINT

on parallel printer emulates HP thermal

MOVE ASCII files between HP disk and Kaypro disk. (Upload requires one-time access to SPL)

UNPROTECTED floppy disk

includes manual

SCroll: 255 Characters wide 200-700 lines vertical

Order MuNet/Kaypro from:

Computer Service Department • Southern College • Collegedale, TN 37315 • (615) 238-2080

THE LITTLE BOARD®

OEM - INDUSTRIAL - SCIENTIFIC SECOND GENERATION SINGLE BOARD COMPUTER KIT!


4 MHZ Z80* CPU!

DOUBLE DENSITY!



FREE CP/M* 2.2!!! A \$139 VALUE! A FREE 5-1/4 IN. CP/M 2.2 DISKETTE IS INCLUDED WITH EACH KIT.

> A. & T. UNITS \$349



(COMPLETE KIT)

MINI-SIZE: ONLY 5-3/4 x 7-3/4 INCHES

FULLY SOCKETED! PERFECT MATE TO OUR ZRT-80 TERMINAL BOARD. THROUGH SPECIAL ARRANGEMENT WITH AMPRO COMPUTERS, WE ARE PLEASED TO OFFER THEIR LITTLE BOARD® IN KIT FORM. **FEATURES:**

4 MHZ Z80 CPU!

DOUBLE DENSITY (5-1/4 IN.) FLOPPY CONTROLLER

64K DYNAMIC RAM!

CENTRONICS STYLE PARALLEL PRINTER PORT

USES +5VDC @ .75 A. AND +12VDC @ 50MA

TWO RS232 SERIAL PORTS


SAME SIZE AS A MINI FLOPPY

2732 BOOT EPROM

Digital Research Computers P.O. BOX 461565 • GARLAND, TEXAS 75046 • (214) 271-3538

TERMS: Shipments will be made approximately 3 to 5 weeks after we receive your order. VISA, MC, cash accepted. We will accept COD's with a \$75 deposit. Balance UPS COD. Add \$4.00 shipping.

USA AND CANADA ONLY



A LOW COST ALTERNATIVE TO EPROM PROGRAMMING

Reads and programs 2716, 2732, 2764, and 27128 EPROMS. Reads 2-16K ROMS.

Direct connect to any RS232C terminal or computer.

Plug selectable as either a data set or data terminal.

All voltages made on board, (no power supplies needed).

(User supplies power Xformer, 25.2 to 30 VAC C.T.1 Amp.).

Power electronically switched, (can't damage EPROMS).

Zero insertion force socket for EPROM.

Programs, verifies, and dumps in both ASCII and hex.

Edit buffer (like DDT).

Saves hex and/or image files to and from disk.

Saves or loads all or partial buffer.

Completely menu driven for ease of operation.

Commands of Test, Read, Display, Save, Load, Program and more.

Check sum calculation.

All software on disk including well commented source code.

Detailed owners manual including schematic

All chips socketed.

Not a kit! Completely built and tested.

48 hour dynamic burn-in and test before shipment.

90 day limited warranty on parts and workmanship.

24 hour return policy on repairs.

Delivery from stock.

NOTICE TO PREVIOUS CUSTOMERS: Send us your old disk and a suitable S.A.S.E. for your free copy of our new software, ver. 1.6. PROGRAMMER 4+ WITH OWNERS MANUAL AND DISK. \$199.95

Order from



VISA and MASTERCARD telephone orders welcome.

Please specify Disk format CP/M 8" IBM format, KAYPRO II, XEROX 820, OSBORNE I, others.

Please specify method of shipment, UPS or Postal Service. California residents add 6% Sales Tax. Dealer Inquiries invited.

Slicer Column

By Earl Hinrichs

245 Marshall St. NE Minneapolis, MN 55418

Just a note on some things happening here. I have spent the last few days tracking down some undocumented features in the software. (Some people might call them bugs, but those of us who write software know better, right?)

BDOS Errors

The first time you select a hard disk after a boot, the system does a disk recalibration. If the disk operation is not completed in time, then the system times out with a BDOS select error. We do this to keep the system from hanging if there is no drive.

Since you can assume that your hard disk is always there, you could remove this check from the BIOS. On the latest EPROMS, I have replaced the recalibrate command with a test drive ready. This gives you the same information but is much faster.

SASI Port

We were running the SASI port with three wait states. On a 6 MHz Slicer, this is too long. Some experimentation showed that two wait states worked for both 6 MHz and 8 MHz.

You can change the wait states by changing a register in the 80186's peripheral control block. To change to two wait states, change the least significant bit of FFA2H and FFA6H (in the I/O space) to 0. The 80186 data sheet has the details. Also, in some of the early 1.3 EPROMS, the timer's time constant was not set. This can be fixed by outputting 9C40H (4000 decimal) to I/O location FF62H. Use 3000 decimal for a 6 MHz Slicer.

Winchester Controllers

I am now convinced that the Xebec controller is very slow. I have tried several different things to speed up the hard disk operation with very little luck. A number of folks who have used the Xebec on other systems tell me it is slow on theirs. In fact, I have been able to optimize floppy operations enough that the hard disk does not seem any faster than my 8" floppy.

I know that one Slicer owner is running an Adaptec controller and she says

(Slicer Column continued on page 18)


FLOWCHARTER

- * ENGINEERS
- * TEACHERS
- * EXECUTIVES
- * SYSTEMS ANALYSTS
- * DRAFTSMEN
- * OFFICE MANAGERS
- * BANKERS
- * SERVICE PEOPLE

- * TECHNICAL WRITERS
- * CONSULTANTS
- * PROGRAMMERS
- * YOU

```
/# Flowchart showing which Big-Board I pins to
jumper depending on the installed I/O options #/
```

```
IS SID OPTION INSTALLED ?:
                  NO GOTO C; ELSE YES;
IS CTC OPTION INSTALLED ?;
ZA:
        IF
                   YES GOTO D: ELSE NO:
                   STOP;
ZB:
                   JUMPER SID PIN-6 TD PIN-7;
ZC:
                  A XB ET;
IS 6.P. PIO OPTION INSTALLED ?;
NO GOTO E;
YES GOTO B XB ET;
        GOTO
ZD:
        IF
        IF
        SKIP
                   JUMPER GPPIO PIN-22 TO PIN-24;
ZΕ:
        BOTO
                   B XB ET:
```



Two years in the making! Doing what they thought couldn't be done on a micro! EasyFlow is a high-level language for producing neat, accurate flowcharts. You describe the flowchart using a simple command language; EasyFlow then produces a complete flowchart.

Not just for programmers! EasyFlow is for everyone needing flow type charts: engineers, executives, systems analysts, draftsmen, office managers, bankers, service people, technical writers, you name it – anyone who needs to be able to explain things in clear and understandable manner.

People have been using flow charts for a long time, for both programming and other uses. The problem is producing them: if you do them quickly by hand, they look awful; if you take your time they look better, but they take forever and are impossible to update or revise without starting over. Really good looking flowcharts require a typesetter, a draftsman and a lot of patience. With EasyFlow you can produce excellent flowcharts quickly, and then modify, correct and update them with very little effort.

EasyFlow is a lot like a high-level language; it accepts source statements, processes them and outputs an object file, but the object file is a flowchart instead of a program. To produce a flowchart you create a source file (using ED or whatever) that describes the flowchart. EasyFlow reads the source file, builds the flowchart in memory and then outputs it. The flowchart is normally output to disk, but it can be redirected to the console, punch or printer.

The EasyFlow command language has facilities for describing what shapes are to go where, what text is to go inside the shapes (centered in the shape automatically by EasyFlow), and the lines that are to connect the shapes. Input to EasyFlow is free-format in much the same manner as C programs, and each statement is terminated with a semicolon. Comments are indicated by "/*" and "*/"; comments can be nested, allowing you to "comment out" an entire section of source, even if it contains other comments.

The example above shows both the source text describing a simple flowchart and the actual flowchart produced. This particular flowchart explains how to setup the interrupt daisy chain jumpers on a Big-Board-I, for all possible combination of installed options. This IS explained in the BB-I documentation, but the flowchart makes it a lot more clear.

EasyFlow works with just about any printer; some are better than others for producing flowcharts, but even a teletype can produce useful flowcharts. A "full sized" flowchart is five shapes wide, eleven shapes high, and requires a printer capable of printing at least 132 columns wide. Printers capable of 80 columns can print flowcharts three shapes wide. A "full sized" flowchart printed at ten characters per inch and eight lines per inch is thirteen inches wide and twenty inches high; reducing such a flowchart by 50% yields a standard-page sized chart. The example chart shown here was a full-sized chart that was reduced. Special printer programs are available for printers such as the MX80, MX100 and u92 which allow flowcharts to be produced on standard 8.5" x 11" paper directly.

EasyFlow comes equipped with twenty standard flowcharting shapes. User defined shapes can be easily added to cover just about any application – it is as simple as editing the EasyFlow configuration file which defines the shapes.

In addition to user definable shapes, EasyFlow allows user selected line drawing characters. The characters for "horizontal line", "vertical line", "upper left corner" and so on are user selectable. You can make you own choice and even take advantage of printers that have special line drawing characters available.

EasyFlow is written in Z80 assembly language and is fast and efficient. A rather large flowchart typically takes about ten seconds of computing time; the example chart shown here is very small, and took less than three seconds. Execution time will vary depending on CPU speed and the type of disk drive, but in any case it is quite fast. Since the source programs tend to be small (one hundred lines of source gets you a very full flowchart), and since EasyFlow needs only a single pass, disk I/O time tends to be modest. EasyFlow was developed on a 2.5MHz system with floppies, and it produces charts at a very respectable speed.

In addition to producing great flowcharts from perfect instructions, EasyFlow also produces meaningful error messages from imperfect instructions. A typical EasyFlow error message is:

046 INVALID EXIT-DIRECTION FOUND WHILE PROCESSING CELL B2. IF NO GOTO BAFFY XV ET

The first line is an english-language error report that outlines, as clearly as is possible in one line, what the problem is and where we were in the flowchart when the problem was detected. The second line is the source text that EasyFlow was processing at the time. The third line (the question-mark) points to the exact word that was being processed. Every EasyFlow error message has a number (046 in this case) so that you can quickly look up a detailed explanation of an error in the Error Description Appendix of the manual. This explains, in detail, what the error is, why it might have occurred, and how to go about correcting it.

The EasyFlow manual is complete, and is designed for both novices and experienced users. For the novice it explains (in the correct order, starting from the beginning of the manual) how to install EasyFlow on your system, how to back up the distribution diskette, and how to produce your first flowchart using one of the included demo charts. This is followed by a tutorial that explains the use of EasyFlow through the use of examples. The source text of all the examples in the manual is included on the EasyFlow distribution diskette, giving you a starting point for experimentation. For more experienced users there is a detailed syntax and operation description of all the EasyFlow commands, a chapter on configuring EasyFlow to produce the best charts with your particular printer, the error appendix and a chapter on defining your own shapes.

EasyFlow runs on Z80 CP/M machines that have a TPA of 38K or more. EasyFlow is available on SSSD 8" diskettes and KayPro format 5" diskettes. Other five inch formats: call.

\$49.95 (\$59.95 in Canada; Ontario residents add 7% PST).

Send check or money order today to:

HavenTree Software Limited R.R. #1, Seeley's Bay, Ontario, Canada K0H 2N0 (613) 542-7270



it is very fast. I have one here but have not written any drivers for it yet. Maybe it is time I got going. Meanwhile, if speed is super important, get one of the new memory boards. On a 512K Slicer, you can set up a 400K memory disk.

Speeding Up CPM86

Here is an interesting experiment which reveals something about CP/M. First, reset the Slicer while CP/M is running. This will put you in the monitor with CP/M still intact in memory. Then try this:

+G80:2500,2518

80:2500 is the CP/M cold start location. It is a good way to return to CP/M from the monitor without booting a disk. 2518 is the jump table location for the BIOS home disk function. So control will return to the monitor when CP/M tries to home the drive. After the sign-on message, in place of the familiar disk prompt, you'll see a '+'. Now type:

+TG,2518 &

Don't type return yet, let me explain this command. T is for trace; it displays the registers (like the X command) and executes one instruction. G,2518 says to start executing code at the present location but set a breakpoint at 2518. The & says repeat the command.

Putting all this together, CP/M will run normally, except that each time it calls the BIOS home disk function, the CPU registers are displayed. The point of doing this is to see how often CP/M is homing the drive.

You'd expect it to home the drive once on a cold boot perhaps, but that's about all since CP/M86 does not use the disk on a warm boot and the system is kept in a file rather than on track 0. There is nothing at all on track 0 that would interest CP/M86, but you'll find it homing the drive all the time. In fact, it'll home as many as ten times during one PIP!

OK, since our screen is getting filled with our register dumps let's reset the system again and enter:

+ \$80:2518 2518 CC C3 2519 E5 . + \$G80:2500 This puts a return in the home disk entry in the jump table, then reboots CP/M. Now the BIOS will ignore the disk home requests. I have been running my CP/M just fine this way and it's, of course, a bit faster. Unless I find a situation where home is really needed, I am going to remove it from everything we ship. (Editor's note: I've heard you can't be too sentimental when you're an engineer, but a guy's home is his home.)

By the way, "&" (repeat) is a most underrated command. It is particularly useful when you are using an oscilloscope. Otto has some examples of this in the check-out procedures in the manual. Another interesting experiment is to watch how many times CP/M calls the BIOS read command and how often the BIOS actually reads. You will be surprised how many reads are eliminated by the track buffering.

One of these days I will add conditional branching to the repeat command so you could have it repeat for, say, 10 iterations or until something happened.

Floppy Drive Fix

When I changed the floppies' step rate from 6 ms to 3 ms they would do everything but boot. The problem was that during a restore the head would move out to track 0 and immediately step back in a track or two. Unfortunately, at 3 ms, the first step in was read as a step out by the drive, so I added a short delay to the restore and the problem went away. The problem didn't show up in regular operation since a seek was followed by a read or write so there was no quick change in direction.

Upgrade Policy

A major upgrade (from 1.2 to 1.3) costs \$25. We send a new set of EPROMS and a disk with the monitor source, the latest BIOS, and other utilities. We ask recipients to return their old disk and EPROMs. We then reuse them so we can keep the cost of upgrades to a minimum. There are many nice additions in the upgrade which make it one of the best bargains you'll see.

Figure 1 - Sieve Times for Slicer

We do not make any money on the upgrades, but we want all Slicer owners to have the latest software (happy customers are our best advertising). So it is fine with us if a group of Slicer owners want to go in together and buy an upgrade and then make copies for themselves.

Bug Killing

When we released monitor I.3 and BI-OS 3.0, I was sure I had finally written prefect software. (Editor's note: That's how Earl spelled perfect, which goes to show you that even "perfect" isn't always prefect. Or whatever.)

Well, we are now shipping monitor I.3E and BIOS 3.2. The differences are small (and I've mentioned most of them here) but the bugs can be annoying. So, if you will send in your EPROMs and \$10, we will burn them and send you a list of the changes. I wish we did not have to charge for this upgrade, but we can't afford to give it away.

Editor's note (again)

The following letter was addressed to Byte magazine but it got forwarded to Micro C, which is only right since we're the largest computer magazine in Central Oregon (as well as the only one).

Anyway, to paraphrase the letter, it appears that Turbo Pascal running on the Slicer is almost too fast to be any fun. See Figure 1 for proof.

The letter also mentioned that the Turbo test/demo program contains 1200 lines of code and it compiles into a .CMD file in 12 seconds.


You can check these times against the benchmark figures for the Sieve of Eratosthenes program in the January 1983 Byte, page 283.

The information was actually passed on to Micro C by Otto Baade and came from a letter to Byte written by:

Edward Dayhoff 1618 Tilton Dr Silver Spring MD 20902

Time	to	load	Turbo	from	SSSD	811	floppy	12	sec
Time	to	load	SIEVE	into	TURBO)		1	sec
Time	to	comp	ile int	o . C	D fil	e		. 1	sec
Time	to	exect	ute 10	itera	ations	3		6.2	зес
Bytes	01	f code	e comp	iled				288	
Bytes	3 0	f data	a					8208	
Bytes	3 0	f sta	ck/heap	9				62176	

GET REAL 16 BIT POWER



A SINGLE BOARD COMPUTER FEATURING THE INTEL 80186 (see Byte margazine April 1)

(see Byte magazine April '83)

THE SLICER

- Full 8MHz 16-bit microprocessor having complete software compatibility with the 8086 and 8088
- 256K Bytes of RAM plus 32K Bytes of EPROM memory capacity on board
- Floppy disk controller can run the combination of 8", 5-1/4", 3-1/2" drives simultaneously
- SASI port for hard disk controller
- Two full function RS232C serial ports with individually controlled baud rates from 50 to 38.4K baud
- 8K of EPROM contains drivers for peripherals, commands for hardware checkout and software testing

- Source for monitor and bios included on disk
- Bios for CP/M 86* supports 8", 5-1/4", 3-1/2" drives and the Xebec 1410 controller for hard disks
- Board size 6" x 12" power requirements +5 @ 3A, +12V @ 60mA, -12V @ 50mA
- Complete documentation included.

Sold in various forms:	
Assembled and tested	\$1,075.00
Full Kit	
Easy Kit (hard to get parts)	. , 450,00
Bare Kit (board, Rom, doc, and disk) .	150.00
CP/M 86* available	85.00
Regular U.P.S. shipping within contin	nental U.S.
is included	

THE NEW SLICER EXPANSION BOARD

- 256K bytes dynamic RAM using the RESTMS4500 DRAM controller
- 2 RS232C serial asynchronous ports using the Signetics SC2681 serial communications circuit with baud rates selectable from 38.4K baud to 50 baud
- 2 RS232C serial asynchronous ports using the Zilog 8530 SCC with header connectors for synchronous communications personality cards
- Real Time Clock with battery back-up using the CDP6818 RTC circuit, on-board or off-board battery

- Parallel printer port for Centronics-type printers
- Same size as the SLICER, Power: 5V @ 1.5A, +12 @ 200 mA — 12V @ 100 mA

Sold in various forms:	
Assembled and tested	\$850.00
Full Kit	650,00
Memory Board	
3 Port Board and Clock	
Bare Board and Doc	. 95.00
Regular U.P.S. shipping within contine	ntal U.S.
is included.	



Choose 8 MHz CPU for speed 6 MHz CPU for speedy delivery SLICER COMPUTERS INC. 2543 Marshall St. N.E. Minneapolis, MN 55418 (612) 788-9481

Mastercard, Visa, check, money order or C.O.D. orders accepted. Please allow 4 weeks for delivery.

*CP/M a trademark of Digital Research, Inc.

By Staff

Since we announced that Micro C was going to support SBASIC, we've been deluged by calls, cards, and letters—each writer feeling he is the lone SBASIC programmer. (And when he comments on the manual he sounds like the lone harranger). We haven't seen such interest since the Banks raised their loan rates.

Well, climb off your white horse, masked programmer, you're not alone. The following is an index, a better guide to SBASIC's trails than an Indian scout (Ohnystly!).

Of course, finding the information in the manual might not help much so we'll be taking the manual on in pieces. After using the manual, one reader noted, "There is no doubt in my mind that a beginner who could read the documentation and begin writing useful programs could get a PhD in Computer Science from MIT or Cal Tech without taking any course work."

The following index was constructed from the combined efforts of John Gruver and Rick Yount. Bill Boulton supplied the note on the CALL procedure.

Heeding the Call

In the older editions of the manual, the CALL statement is described on page 36 of Chapter 4, "Control Structures," paragraph 4.11, and in the appendix, in the Ap-Note dated June 1, 1980, "Merging and Using Assembly Language Routines."

The discussion of the CALL statement has all but vanished from the most recent manual, but the Ap-Note is still there, now on page 140. Study it!

For the enlightenment of those who don't have one of the old manuals, I here repeat the text of the explanation (this detailed explanation was replaced by three lines on page 128 of the new manual. Wonders will never cease).

"The following information and statement is for the experienced programmer used to working with assembly language routines. Sometimes a given task can best be accomplished using assembly language routines. Structured BASIC provides a method by which such routines can be invoked. The form of the statement is: CALL ([exp], [name1], [name2], [name3], [name4]), where [exp] is an integer expression that determines

what memory address is to be called, i.e., where in memory the routine is. The [name x] are integer variables whose values will be stored in the CPU registers according to the following format:"

[name1] HL register pair [name2] DE register pair [name3] BC register pair [name4] Register A, PSW

"The second form of the statement is: CALL [exp]. This form is used to execute a routine without passing any arguments. [exp] is an integer expression that determines what memory address is to be called. This expression should not start with a left bracket. Both forms should use not more than 4 levels of stack space. If more is needed then the routine should set up its own stack, and when done restore BASIC's stack. Upon return from the subroutine the values of the registers are saved back into the integer variables given by [name x]. The subroutine is CALLed and should return control with a RET instruction."

INDEX FOR THE SBASIC MANUAL

```
Reserved Character, 83
   Reserved Character, 15
   Reserved Character, 37,
   Reserved Character, 85
$$
    Reserved Character, 37
    Reserved Character, 83
   Reserved Character, 37
    Reserved Character, 84
    Reserved Character, 14, 84
**$ Reserved Character, 85
    Reserved Character, 14,
    reserved Character, 37, 84
    Reserved Character, 14, 84
    Reserved Character, 14, 83
    Reserved Character, 37
    Reserved Character,
    Where Prohibited, 48
    Reserved Character, 14
    Reserved Character, 14
    Reserved Character, 14
    (Exponent), 14, 41
E
H
    (Hexadecimal Entry), 15, 16
    Reserved Character, 37
[]
    Reserved Character, 14, 84
{}
    Reserved Character, 37
    Reserved Character, 37
$CONSTANT, 124
$END.MODULE, 125
 $INCLUDE, 125
 $LINES, 122
 $LIST, 126
```

```
$LOADPT, 127
$MODULE, 125
$PAGE, 124
$STACK, 126
$TRACE, 122
ABS (RS), 39,114
Access to Data Files, 90
Address
  Array data, 49,50,140
  Error Code, 64
  File Address, 100,130,131
  File control block(fcb), 137,141
AND (Logical function), 14,39,55,56
                               57,59
Application notes, 136-139
Arrays, 47-49,101,131,140
 ASCII (S)/ASC(S), 39,114
ASCII, 34,37,39,43,45,77,88,89
  102-105, 114,117,118,136,138
 ASCII files & channel #s, 102-105
 Assembly language routines, 140-148
 ATN (R), 39,114
 Attaching and detaching files from
 a file channel, 93
 BAD CHANNEL NUMBER (Error), 64
 BASE (Storage), 39,47-50,64,100,130
                 137,145
```

```
BASED (Storage) 39,47,50,64,100,130
                 137,145
Base located area - See BASE
Based variables - see BASED
BASIC. 32
BAS File Extension, 3,4,36
BEGIN...END, 20,21,24,25,34,37,39,51
                  52,65-67,70,128,145
Binary file, 136
Binary disk format, 96,105
Block structure, 20,21,24-26,33,34
                      51-53,65,67,68
CALL (Machine Lang.), 39,128,140-148
CASE, 26,34,39,66-67,135
CCP, 136-138,140
CHAIN, 39,71-73,128,140
CHANNEL (BASIC I/O), 74,102-103
CHANNEL (DISK FILE), 90-105
CHAR (Variable type), 14,16,22,30,34
41,44,46,48,49,69,76,77,100,107,140
 145,147
CHR (I)/CHR$(I), 30,39,110,114
CLOSE, 39,95,97,134
Comma, 75,76,78,80,84,104,109,131
Commands (compilation), 122-127
COMMENT, 10,35,39-40,132,145
COM/COMMON (Storage area), 39,47-48
                             50,53,130
```

Console, 39,74,79,103,121,131 CNTL-C TRAP, 39,77,129 Control Statements, 61
CONTROL> statements "R" 77 "S" 27
"T" 27 "U" 77
COS (R), 115 CREATE (Disk File), 39,92,135
D
D (Dummy device character), 102-103 DATA, 39,88,89,128 Data types, 34,41-44
Data Storage Area, 45
Defining logical functions, 58
Determining expression type, 54 Designating an I/O source, 74
DELETE, 92,134
Devices, I/O, 74 DIM, 47-49, 51,100,130
Disk Files, 90-105
E
ECHO ON/OFF, 77,131
ELSE (IF THEN ELSE), 34,39,67-68
EOF (End of file) Not Implemented END, 20,21,24-26,29,300,34,37,39,40
52,65-68,70,77,106,107,109-111,113
131,132,133,135,144-146 Equal Sign, 14,57
EQV, 14,55,57,59
ERROR Messages Table - Run Time, 64
ERROR Statement, 63 EXCAPE, 74,85
EXECUTE, 39,71-73,128,136,137
Exponential Notation, 85 EXP (R), 115
EXPRESSIONS, 54-60
Extent, file 3, Required for Disk
I/O but not alluded to in manual
F
FCB (S)/FCB\$ (S), 39,115
Features, 31 FFIX (F), 115
FILES Command, 90-105,134
FINT (F), 115 FIX (R), 115
FIXED, 15,34,41,42,55
Finding data struct at run-time, 49
Filenames, 3 FLOAT (See REAL)
FLOAT.DOUBLE Same as REAL.DOUBLE
FRE (I), 39,115 FORNEXTSTEP, 27,28,39,68,97,135
FUNCTION, 29,39,44,106-108,133,145
Function, User Def See FUNCTION
Functions, Intrinsic, 114-119
G
Global Variables, 21,44,52
GO (Appears in ASCII dump but not described), 39
GOTO, 22,39,61-63,132
GOSUB, 22,39,61,62,132

```
HEX$ (I), 116
IF.. THEN.. ELSE, 19,20,67,68,130
IMP (Logical funct), 14,39,55,57,59
INITIALIZE (Disk), 93,134
INPUT, 7,8,11,17,18,19-23,29,30,39,
74-77, 79,88,102-105,107,131
INPUT/OUTPUT, 74-89
INP (I), 39,116
INSTR (I<S1,S2K), 39,116
INT (R), 39,116
INTEGER Variables Type, 14-17, 19, 20,
21,24,27,29,30,34,39,41,43,45-47,49,
50,52,55,56,69,76,78,96,100,107,113,
                     116,133,145,147
LEFT$ (S,I), 39,116
LEN (S), 39,116
Line Numbers, 37
LET (Statement), 6-13
LOCATE, 39,48,49,100,130
LOCATION, 39,49,100,131,145
LOG(R) Natural Log Function, 39,116
LOG10 (R) Appears in ASCII dump
    under DDT but not in manual
Logical Functions, 14,57-60
LPRINTER, 39,79,80,132
Machine Language, 31,140-148
MID$ (S,I1,I2), 39,57,116
Multiplication, 8,14,57
NEXT See FOR..NEXT
NOT, 14,39,55,57,59
NUMERIC FIELDS, 83-88
NUM$ (R)/STR$(R), 39.117
OPEN (DISK FILES), 39,91-93,97,134
OR (Logical OR), 14,39,55,57,59
OUT, 39,129
OUTPUT, PRINTING, 78-88
OUTPUT, CONSOLE, 79
OUTPUT, DISK FILES, 90-105
OUTPUT, PORTS - See OUT
PEEK (I), 39,117
POKE (I1, I2), 39,129
POS (I), 39,117
Precedence, Table of, 14,57
PRINT, 4-10,78,131
PRINT USING, 81-88,131
PROCEDURE, 30,44,109-113,133
```

```
Random Files, 34,90-105,134,135
READ, 39,89,93,94,98-100,129,134
Reading Data, 88
REAL Variable type, 14,41
REAL.DOUBLE, 15,41
RECORD. SEQUENTIAL, 39,129
Recursion, 111-113
Relational Symbols, 60
REM/REMARK, 10,39,40,132
RENAME, 39,92,134
REPEAT.. UNTIL, 24,39,65,129
RESTORE, 39,89,129
RETURN, 24,25,39,74,123,124,132
RIGHT (S,I), 39,43,117
RIGHT$ (S,I), 39,43,117
RND (RS), 39,117
Save (CP/M), 140,148
S-BASIC Files, 36
S-BASIC Statements, 128-135
Sequential Files, 90-105
Serial Files - Same as Sequential Files
SGN (R), 39,118
SIN (R), 39,118
SIZE (S), 39,118
SPACE$ (I)/SPC (I), 39,118
SQR (R), 39,118
Statements, 37,38,128-135
STEP, 28,68
STOP, 39,131
Storage areas of disks, 90
STRING (Variable), 39,41,43,118
String Fields, 82
Strings, 97
String - Special Form, 57
STRING$(11,12)/STRING(11,12), 39,118
System Load Map, 50
TAB (I), 39,118
TAN (R), 39,118
TEXT, 39,80,81,131,132
THEN - See IF.. THEN.. ELSE
Tracing, 27,123,124
Translator (Compiler), 32
VAL (S), 39,119
VAR, 14,39,45-53,130
Variables, 14,39,45-56
WHILE..DO, 24,39,65,66,129
WRITE, 39,94,100,134
XLATE (S1, X2), 39,119
XOR, 14,39,55,57-59
```








FOR THE II AND 4's. GRAPHICS ADAPTER FOR KAYPRO COMPUTERS

This simple board adds most of the features of the popular Heath/Zenith H-19 terminal to your Kaypro. These include Reverse Video, Character Mode Graphics, and other advanced features. And because it emulates an existing terminal, there is a wealth of Graphics Game and Business Software packages already available for it. On all but those machines in which the ICs have been soldered in, installation is a simple matter requiring only about 15 minutes.

The Gilderfluke & Co. Graphics Adapter retails for \$175.00 (California residents must add 61/2% sales tax). Please include your Kaypro's serial number with order. If you have a Kaypro II which says "KAYPRO" on the boot prompt rather than "KAYPRO II", please indicate this when you order. Dealer inquiries are invited.

AVAILABLE SOON FOR THE '+' AND 10's.

The features it will add to your Kaypro include:





120 Midway Drive Space 013 Anaheim, Calif. 92805 (714) 776-2207

EPROM PROGRAMMER

interfaces to the BBI (XEROX 820) parallel port Requires +5v. @ .3A, +25v. @ .1A, interface cable

29.95
39.95
64.95
99.95
129.95
149.95
5.00
10.00
29.95

Software is delivered on a 8 inch SS SD floppy disk

- Program, Verify, Load and check for Erased Intel Eproms 2716, 2732(A), 2764, 27128
 T.I. Eproms 2516, 2532, 2564
 Xicor EEprom 2816A
- Uses 16k bytes of system memory as a buffer, allowing you to work with up to 8-2716 EPROMs at the same time
- Upload and Download Intel Hex Files
- Edit the data in the 16k byte memory buffer
- Define your own addresses for the memory buffer
- Complete screen error messages
- Software source included
- Menu driven
- Interfaces with most Z80 CP/M systems

options (available later)

- EPROM emulator
- Adapters for single chip processors

WADE-I

Universal Interface Expander

Use the WADE-I U.I.E.for Intelligent Communications
Printer Buffer Parallel driven RAM disk
System multiplexer P/S to S/P converter
AND as a BIG BOARD I or XEROX 820 PORT EXPANDER
Power requirements +5 volts @3A, +/-12 volts @.1A

1. Bareboard	85.95
2. Printer buffer EPROM	14.00
3. Printer buffer source on 8" SSSD diskette	25.00
4. 4 MHz Kit (64k) with printer buffer EPROM	359.00
5. 4 MHz A + T (64k) with printer buffer EPROM	459.00
6. 64k byte bank of RAM (8-4164s 200nsec)	79.00
S/H within N.A.	10.00
S/H foreign orders	15.00

BIG BOARD I (XEROX 820) PORT EXPANDER

- interfaces through the Z80 CPU socket and 1 jumper to connect the 'IEO-IEI' daisy chain
- adds 2-PIOs, SIO, CTC, and a DMA controller FULL MODE 2 INTERRUPT OPERATION
- Works with 2.5MHz and 4MHz systems
- Complete documentation

STAND ALONE U.I.E.

- 256k bytes of RAM with DMA capability
- 4 fully buffered 8 bit parallel ports
- 4 Mhz use Z80A parts and 200 nsec dynamic RAM
 2.5 MHz use Z80 parts and 250 nsec dynamic RAM
- configurable EPROM socket (2716 thru 27256)
- 4 fully buffered 8 bit parallel ports
- 2 configurable RS232C serial ports

- Complete documentation

all prices shown are in US funds

orders shipped within 10 days A.R.O.

Biegun & Associates

P.O. Box 4071, Stn "B" Winnipeg, Manitoba Canada R2W 5K8

BIG BOARD COLOR GRAPHICS

095Bare Board

TMS 9918A Based Graphics System 256H-192V * 16 Colors

- ★32 Simultaneous Fast Moving Sprites
- ★ Composite Video Output
- ★ Highest Quality PC Construction
- ★ Software Includes Character & Sprite Editor Demo Program In Pascal & Basic
- ★ Drivers Are Above The Monitor For Use With High Level Languages

Requires 1 trace cut and 1 jumper (see adding 6K of Ram MicroC#7) Plugs Into U7Ø (U7Ø Still Available for Prom with Jumper)

TMS9918A Graphics Chip *34°5



Check ★ Money Order ★ COD

GRAPHTECH

P.O. Box 1185, McPherson, KS 67460 — (316) 241-6330 Call for Availability & Price of Parts Kit Kansas Residents Add 4% Tax/Include \$3 For Postage & Handling Allow Four to Six Weeks for Delivery

CABINET FOR THE W-I-D-EDISK DRIVES (SA800-2)

Heavy CAST ALUMINUM Cabinet ---- \$50.00

Cabinet, Pwr Supply and Wiring for 2 drives-----\$150.00

Quantities Limited First Come, First Served. Cabinets are USED and sold AS IS. Pwr supplies have been tested.

ADD \$5 Shipp/Hand. Charge Cards ADD 5%

CASCADE ELECTRONICS ROUTE 1 BOX 8 RANDOLPH, MN. 55065 507-645-7997

MN. add 6% sales tax

BIG BOARD I DUAL DRIVE ENCLOSURE

Because of the unprecedented popularity of the original Big Board, we felt there would be a good market for an attractive yet low cost custom enclosure. We have had designed THE perfect enclosure for your Big Board and two eight inch NEW LOWER PRICE

FEATURES:

- * Custom Designed for the original Big Board
- * Heavy Duty all aluminum construction.
- * Mounts Two SA800/801R or equiv. drives (Vertically).
- * Has extra space for Switching or Linear Power Supplies.
- * Attractive painted cream finish with natural aluminum pre-punched backplate.
- * Pre-punched cut outs for cooling fan, 3 DB25 conn., video conn, keyboard conn., on off switch, AC power filter/plug, fuse, reset switch, and cooling slots.
- * Built in stand offs for mounting Big Board.
- * Can also be used for a dual drive enclosure for other systems besides the Big Board.
- * 20 x 12 x 10.25 inches in size.

Canadian Orders add \$8 shipping

NEW LOWER PRICE: \$69.95 (add \$4 UPS) Buy 2 or more at \$65 ea. (Units shipped unassembled)

Limited Qty. of mating PAMOTOR 8500D muffin fans avail. at \$12. Limited Qty. of CDE APF600CEE 6 amp AC 3 wire receptical and line filter that fits our enclosure are avail. at \$3.50 each.

Limited Qty. of 50 conductor dual disk drive ribbon cable and connector assemblies for your Big Board. These feature GOLD Winchester Electronics connectors! \$15 each.

Add extra \$1 UPS on above 3 items. We accept VISA, MC, money orders, or cash. Personal checks OK but cause an extra 2 week delay for clearing. Texas residents add 5% sales tax. We ship to USA and Canada only. \$15 min. order. No phone orders yet

> ODD BALL ELECTRONICS P.O. BOX 879 **DUNCANVILLE, TEXAS 75116**

SHUGART DISK DRIVES

SA800-2 \$109 SA850\$199 Standard Mount Guaranteed 60 Days

CABINETS

For Above Drives Includes Fans, Cord. And Switch ALL INCLUDE S&H

CASCADE **ELECTRONICS**

Route 1, Box 8 Randolph, MN 55065 507-645-7997

MN. Res Add 6% Tax Credit Card Add 5%

BB II: Modifying Andy Bakker's Interface

By Frank Ten Thy

Phenix Company of California 1619 S. Minnie St. Santa Ana CA 92707 (714) 547-4316

I just completed the modification on Andy Bakkers' BB II drive interface for a mixed variety of 8" and 5" floppies. I encountered a few problems getting the system up and running which I would like to share with everyone making this attempt. Once these problems were corrected, the system worked beautifully.

The following jumpers are to be left out: JB4, JB8 and JB35. These are no longer required for the default to 8" drives. This is not mentioned in the procedure, and with the great anticipation of getting the system working, this may be overlooked.

Offsets

The CP/M that I received with my BB II has the -200H offset so it originates at E400. Bakker's AUTOBIOS expects it to be the standard CP/M which originates at E600 for a 59K system. Take your editor or word processor and change the base equation to look like this: ((MSIZE-20)*1024)-200H in AUTOBIOS.MAC if

you are one of the unfortunate people to have this CP/M. Next assemble the AUTOBIOS as shown in Figure 1.

You are probably wondering why I didn't patch my CP/M to be a standard CP/M.

I tried the patch in Micro C #9 and it would not work for me, so for now this will have to do. Also, I made a little change in the file MEMORY.MAC. However, every time you boot up, you would have to run the CONFIG program to set up your drives because the boot automatically resets all drives to 8".

Drive Defaults

In this file I changed the binary number so it would default to A=8 inch, B=8 inch, C=51/4 inch and D=8 inch. Look for the label typeflag:. You will find a binary number 00001111b.

Change to 00001011b

1=8 inch, 0=5 inch.

^ is drive B ^ is drive C ^ is drive D


is Drive A

This will set up your drives automatically so you don't have to run the CON-FIG program after each boot.

Once everything was working, I reconfigured the 5¼" drive to read and write Eagle IIe disks. At the company where I work, we have several Eagles on which I need to download our existing 8" CP/M software. Andy's mod makes it much easier to do this downloading.

Figure 1 - Patch for Andy Bakkers' Interface

"ICO" IS THE BIGGEST BOARD!!



CPU: Z80 4MHz RAM: 128K Byte

A>SYSGEN8

A RETURN

RETURN

CRT CONTROLLER: On board 80 columns x 24 rows (cycle steal access non-blinking and fast) separate or composite

SERIAL PORT: Two RS232C, 110 Baud to 19200 Baud programmable

PARALLELL PORT: One Centronics standard 16 bit user's option

CALENDAR: Battery back-up

KEYBOARD: 7 bit or 8 bit ASCII positive

POWER: +5V 1.5A, ±12V 0.1A

PCB SIZE: 10" x 5.5"

FLOPPY DISK CONTROLLER: Auto density check 8" DDDS, 8" SDSS, 5" KayPro format, 8" compatible 5" drive (1.2 MB double track quad density)

FLOPPY DISK DRIVE, KEYBOARD, CRT, POWER SUPPLY ARE NOT INCLUDED

\$699 \$999 Assembled & Tested + CP/M PLUS (RMAC, MAC, ED, SID with manuals)

Assembled & Tested + CP/M PLUS + 8" compatible Disk Drive (1.2mb double track quad density)

*RAM DISK BOARD, NEC7220 Graphic Board with GSX, 68000 + CP/M-68K Board will be available soon!!

*CP/M PLUS, GSX, RMAC, MAC, ED and SID are trademarks of Digital Research

For more information write or call:

SOUTHERN PACIFIC LIMITED

1-3-18 Tsurumi-chuo, Tsurumi, Yokohama, Japan 230 Phone: (045) 501-8842 Telex: 3822320 SPACIF J

MOUNTAIN SIDE COMPUTER, INC.

will be incorporated in U.S.

Column by Arne A. Henden

7415 Leahy Road New Carrollton, MD 20784 (301) 552-1295

This month's column starts a multipart series entitled "Interfacing with Users." It is geared towards the individual or company wishing to market a FORTH-based product, but virtually all of the concepts discussed are also important for the home FORTH enthusiast. But first, a word from the vendors . . .

Native Mode Compilation

Laboratory Microsystems has introduced their native mode compiler for their FORTH systems. As I understand it, you first develop your application in your normal manner. You can then optimize specific high-level words by defining them with COMPILE: instead of ":" and then recompiling. They quote a sixtimes increase in speed over standard FORTH.

Is this true? I don't know, because I haven't used the new compiler. However, there are several ways of making any high level word faster, at the expense of memory space.

The easiest is to un-nest high level words. For example, if you define:

:TEST ?KEY IF ECHO THEN;
Where
: ?KEY KEY 48 = ;
: ECHO 64 + EMIT;

An un-nester would then expand TEST:

: TEST KEY 48 = IF 64 + EMIT THEN ;

Here every word mentioned in TEST is a primitive (containing only executable machine code). By removing the nesting, the colon-word run-time routine is not used, pointers are not stored on the return stack and TEST runs at the fastest possible FORTH speed.

The next step would be to have the compiler substitute the actual machine code embodied in KEY, EMIT, etc. and make TEST a "code" word requiring no action from the FORTH inner interpreter to execute.

However, the substituted machine code must be relocatable. For the 8080, all conditional branches are to absolute addresses, and the substitution would be very difficult indeed. The Z80 has some relative branch instructions, so if you took care and never used an absolute branch instruction anywhere in the FORTH kernel, you could build a native mode compiler for high-level words.

I would be interested in hearing from anyone who has used the compiler, both your experiences and any information you might be able to deduce about Laboratory Microsystem's method for producing speedy colon words.

Interfacing with Users

You make a spelling error, and FORTH spits the word back at you with a question mark. You try to dump memory—put the starting address on the stack but forget the count—now hundreds of numbers are scrolling up your screen. Sound familiar? If you've used FORTH at all, you've run across many more examples of good and bad error handling.

Error Handling

One of the biggest arguments in the FORTH community is over error handling. Should FORTH be smart, and warn or trap you every time it thinks you've made an error? Or should error handling be the responsibility of the user, so the FORTH can be compact and fast, and so that you can play tricks when you want to?

My feeling is this. The basic FORTH system needs some error handling, but it should be minimal. It should guard the programmer against common mistakes, like unpaired conditionals or dividing by zero, but not prevent the user from fully using his computer. For example, a common error with memory dump words like CDUMP is to interchange the arguments. The correct order is:

adr cnt CDUMP

But often you will enter: ent adr CDUMP

For large addresses, this second form will print for a long time! You might protect against this problem within CDUMP by making sure the top stack argument (count) is smaller than the next lower argument (address). However, this prevents you from performing long dumps or dumps at low addresses. In other words, be selective in your error handling in your basic system.

However, for an application program which will be sold or used heavily, you should add extensive error handling. Nothing turns the first-time user off more quickly than seeing his \$200 program crashing the first time he miscounts the number of arguments! If possible, much of this extensive error processing should be switchable; a single flag that can turn it on or off.

Types of Errors

For the purposes of this column, I will divide errors into three categories: hardware, compilation, and execution.

System programmers like the 8088 and the 68000 because they can detect hardware errors. Just like mainframes, if you try to divide by zero, address nonexistent memory or execute an illegal opcode, the CPU recognizes your error and "traps" to an interrupt table.

Hopefully, either you or your operating system has placed an error handling routine in the table that informs the user of the error before aborting. Think I'm kidding? Divide 23 by 0 and see what happens! The Z80 could care less so you have to catch the error before it occurs.

To me, hardware errors should be fatal. In this case, the interpreter/compiler should output an error message and execute an ABORT sequence before asking for more input. There are classes of "fatal" though.

Where possible, use FORTH, not the underlying operating system, to trap the error. For example, a word fetch from an odd address with the 68000 results in a trap. CP/M-68K will service this error by aborting the current task. A FORTH user would then have to restart his session!

Compilation Errors

Compilation errors come in two varieties: fatal and nonfatal. An example of fatality would be unbalanced conditionals during a word compilation—forgetting a THEN or using too many BEGINs. Obviously, the word isn't going to work, so why continue?

A nonfatal error might be the redefinition of a word. FORTH should tell you, but keep on executing. You could be smarter than the compiler and want to redefine words. A good article on compiler security was written by George Shaw and is found in FORTH Dimensions, volume III, n1, page 15. It discusses the pros and cons of this topic and should be required reading.

Execution Errors

Execution errors occur when the user makes an incorrect entry—too few parameters, incorrect order, etc. Here FORTH might abort the program or ignore the problem.

Be reasonable, though, because: (1) you can't catch all the errors, (2) you might catch too many and reject a correct entry, (3) your program will get large and slow.

Hardware and compiler errors should be handled by the FORTH vendor. An execution error should be trapped by the application programmer.

Trapping Errors

The FIG error handling word set contains 4 definitions: WARNING, MESSAGE, ERROR and ?ERROR, defined below.

n MESSAGE

n is a message number. FORTH divides the message number by 16 to yield a block number and line number within the block, with the $64-{\rm character}$ line printed on the console.

n ERROR Calls MESSAGE and then aborts.

cc n ?ERROR

A truth flag (cc) is tested. If true, ERROR is called; else the message number is dropped and execution continued.

WARNING n

A user variable/flag that, if true, allows the disk access to fetch the error message; if false, only the message number itself is printed.

I don't like ?ERROR for system error messages. A cryptic "257 ?ERROR" hidden in a word tells me nothing! The maximum size is a 64-character message and all messages must be duplicated in every disk (standalone) or file (captured). However, for those of you who prefer this method, we've left ?ERROR in UNI-

If we don't use ?ERROR, then what error handling method does UNIFORTH provide? Two new words are defined:

cc ABORT" ssss"

Test the truth flag on the stack top. If true, issue the error message ssss and abort execution. If false, bypass the error message and continue.

n ARGS? t

Test the size of the stack to be sure at least n arguments are present. If sufficient arguments exist, leave a true flag, otherwise leave a false flag. ABORT" is now part of the FORTH-83 standard. A public domain version of the word can be found in the article by David Boulton, FORML Proceedings, 1981, page 161. Use it often during the development of an application. An extra kilobyte of error messages often makes a real difference to the user.

ARGS? can be used as a precursor to ABORT". It guards against forgetting an argument, but can be fooled if the stack has leftover values already on it. You can define ARGS? very simply with the word DEPTH.

An example of the use of these two error handling words is shown below.

and those who use a separate stack for each data type (at least dividing integers and floating-point numbers).

Note that there are pros and cons for either method. For example, a single stack is conceptually easier and requires fewer pointers so you can use processor registers for these pointers. On the other hand, a separate floating-point stack would allow a FORTH system to use the stack built into the 8087 numeric processor or to use 48-bit internal floating-point, converting to 32-bit only for storage and retrieval.

My question to you is: Which camp do you feel should be the standard in future

: COPY (blk1 blk2 --- ...copy one block to another)
2 ARGS? ABORT" Insufficient arguments"
SWAP BLOCK SWAP BUFFER B/BUF CMOVE UPDATE
SAVE-BUFFERS:

Reader Survey—Floating Point

Just to get you involved in this column, I thought I would mention one of FORTH's problem areas and ask for your opinion.

In integer FORTH, all numbers are placed on one stack—the data or parameter stack. Easy argument passing is facilitated, and stack operators like ROT and SWAP give you the power to change argument order.

Problems arise when numbers are larger than a single stack cell, (usually 16 bits). A double precision integer is 32 bits. If a single precision value is underneath a double precision value on the stack, you must use the word ROT to bring the 16-bit value to the stack top instead of the usual SWAP.

The problem is further compounded if the floating-point data type is added. You can have single (32-bit) or double (64-bit) IEEE floating point numbers. Software floating point may follow these formats or may be 48-bit, as in some of Microsoft's languages, or even 80-bit (such as the 8087 temporary real).

One option is to divide data types into separate stacks. Then you wouldn't be aware of the internal size of the floating-point number or worry about having to rotate DO-LOOP limits ahead of double precision integers before entering a loop.

Therefore, FORTH systems tend to be divided into two camps: those who use a single, common stack for all data types

FORTH releases? Think carefully and mail your choice to me, indicating, if possible, which factors influenced your decision.

Next Month

I will continue the User series with a discussion about menus and form generation. Your replies to the survey will be evaluated. We will also cover FORTH on the Slicer and on the SBS Z8000.

The **DELPHI SYSTEM**15 Megabyte **HARD DISKS**

for

KAYPRO, XEROX 820, Big Board Televideo and S-100 computers

\$1995 complete

- 15 megabyte hard disk drive with plated media
- switching power supply and enclosure
- controller, cables and CP/M software

DELPHI DEVELOPMENT

6273 19th Ave. NE Seattle, WA 98115 (206) 524-5369

Column by Tony Ozrelic

6708 Melrose Los Angeles CA 90038

Oh No! Not Again! Yes, it seems that your intrepid columnist has once again screwed up—but first, a little background:

I maintain a mailing list for my chiropractor in exchange for treatments. That is, I have my wife type the names in (on a good day, she can do 90 wpm) and I process them (that is, I tell the computer to process them). Having typed in about two hours worth of names, my wife was ready to have the files saved, and I was anxious to get back to work.

I saved the file, and when I called up the directory to see how big it was, XDIR told me it was right around zero kbytes long.

After I stopped screaming, I looked at the amount of space left over on the disk—4 Kbytes. No wonder it couldn't save a 20 Kbyte file. There wasn't room for it!

Ugh. Now, how does one go about saving 2 hours of typing? After I calmed down I began to think.

The first thing I did was save all of memory by typing:

save 255 beverly

This saved all 64k of ram into a file named BEVERLY (I used another disk which had room on it this time). Next, I loaded my ramdisk with my trusty Q/C C compiler and associated program development tools and started typing in a program that would, eventually, skim all the ASCII text from BEVERLY and put it in a text file, which I could edit to recover the original text. The program SKIM. C is the result of my labors. To use SKIM, I just said:

skim beverly beverly.txt

SKIM read all the text and dumped it into the text file called beverly.txt. Twenty minutes later (after editing), I had my wife's original file.

Here's how SKIM works: first, the two filenames are picked up from the CP/M command line and used to open the files. If one of the files does not open properly, we complain about it and exit to CP/M. If all is well, we then examine the file character by character, looking for regular ASCII text and the standard formatting characters such as tabs, carriage returns, and line feeds. This is done by istext(c),

Figure 1 - SKIM.C

```
skim - skim ascii characters from file
 #include
                  "astdio.h"
         syntax is
         skim ramfile textfile
         where ramfile is the name of the file the machines' memory is
                  saved in
         and textfile is the name of the file you want the skimmed text
                  saved in
main(argc,argv)
 int argo;
char *argv[]:
         char c:
         int col:
         FILE *ramfile, *textfile;
                 open input and output files
                                                                             #/
         ramfile=fopen(argv[1], "rb");
         textfile=fopen(argv[2], "w");
                 complain and exit to CP/M if we can't open the files
         if(ramfile==NULL) cantopen(argv[1]);
         if(textfile==NULL) cantopen(argv[2]);
                 read file character by character and send good ones to
                 a regular file
         while((c=getc(ramfile))!=EOF) {
                 if(istext(c)) {
                                                   / good char?
                          col++:
                          if(c!='\n') {
                                                   /*yes, keep it
                                           putc(c,textfile);
                                           putchar(c);
                          /* the following code trims lines to <80 chars
so my editor doesn't blow up</pre>
                          if(col>=78 || c=='\n') {
                                  col=0;
                                  putc('\n',textfile);
                                  putchar('\n');
         fclose(ramfile):
         fclose(textfile);
         istext - is it regular ascii text?
istext(c)
char c;
        /* is it a tab, linefeed, or carriage return?
        if(c=='\t' || c=='\n' || c=='\r') return c;
        /* is it a printable ascii character?
        else if(c)=' ' && c<='~') return c:
        /* none of the above, so return with a zero
        else return 0;
```

which returns the character if it likes it or a zero if the character isn't up to spec.

The good character is then put in the text file and echoed to the screen, and we fetch another character until we get to the end of the file. We then close both files and go back to CP/M.

More Details

Note that this type of program works well with editors that maintain text in an orderly fashion in memory. If your editor spreads text all over memory or intersperses text with weird characters, this technique may not work too well (but it's better than typing it all over again, so why not give it a try?).

What comes out is a standard CP/M text file. Your editor still may throw up if istext() removed some special characters that your editor needs. If so, you'll need to find out which characters it needs and then add them to the istext() function.

For those using other C compilers, please note that the input file (ramfile) is opened as a binary file, not a text file.

The reason is that CP/M text files contain a control-Z to flag the end of the file. Since we are trying to skim a file that may be loaded with control-Z's, we have to open the file so that we can read each and every character up to the end of the file without fainting at the sight of a control-Z.

Potential Problems

Other compilers may not let you open a binary file, so you may have to use the lower-level functions open() and read() to read the file properly.

Also, my homebrew editor does not like lines of text longer than 80 characters, so I included a bit of code to cut off lines to this length. This was not too successful, but at least it worked well enough to allow me to edit my file.

Coming Up

I have just gotten my 512 by 480 bitmapped graphics board up and running. I am busily trying to write some software for it so I can play games and do some CAD (Computer Aided Design) work. More information about that project in the next issue.

CP/M GAME DISCS 8" \$9.95 EACH

From 'BASIC COMPUTER GAMES'

Disc 1 - 50 Games Disc 2 - 50 Games

From 'MORE BASIC COMPUTER GAMES'

Disc 3 - 50 Games Disc 4 - 38 Games

Disc 5 -TWO SCOT ADAMS ADVENTURES

- Adventureland-Recover 13 lost treasures
- Pirate Adventure-London to Treasure Island for more lost Treasure

Disc 6 - ORIGINAL **ADVENTURE**

- Bi-Lingual (English/French)
- Save Game Feature; Interactive
- Treasures/Dangers in Underground Cavern

SPECIAL BUY: All 6 - Only \$50

COMPUWARE

1500 Morning Drive Loveland, CO 80537 (201) 366-8540

Cables

For 5 1/4" hard disk: \$65

(Set includes one each control, data and Power cables and interfaces with xebec or Western Digital boards)

SASI interface cable: \$29

Both of the above: \$85

Also available...

Printer cables:

\$29

Parallel and Serial

Please specify type and host.

VSN International

P.O. Box 1688 West Chester, PA 19380

256K RAMDISK KIT NOW ONLY \$49.95!

CANNED LIGHTNING IS CHEAPER THAN EVER!

Make your spelling checker, assembler, or compiler programs run 35-300 percent faster by using dynaDisk!

dynaDisk is a 256k ram board that uses 5V at 1/2 A and plugs into BB1's parallel interface (J5). It comes with auto-patching software that makes it look like an 8" SS SD disk drive to CP/M. It uses 4164 ram chips, regular TTL, and transfers data 8-10 times faster than a regular floppy.

FOR \$49.95 YOU GET:

8½" by 6¼" bare PC board Software on 8" SS SD floppy (SOURCE INCLUDED) Assembly & Operation Manual

> 64K RAM CHIPS \$3.95 F &

These are PRIME QUALITY 300ns 64K Dynamic ram chips, gradeouts from a 200ns production line, perfect for use in dynaDisk. We have a limited quantity of these rams available to us at this RIDICULOUSLY LOW PRICE! WHY WAIT?? ORDER NOW!

DO-IT-YOURSELF CROSS ASSEMBLERS LANGUAGE TRANSLATORS STRUCTURED LANGUAGES **ALL IN ONE \$39.95** PROGRAM!

 Use the XLT Macro Processor as a pre-processor to your favorite assembler and do the job right! To translate, a file of definitions is read by XLT and compared to the input text. A match causes the input text to be replaced with the definition's contents.

XLT allows up to ten arguments in a definition, arguments containing spaces or tabs, incremen-ting/decrementing strings, a stack, and conditional text

• Includes definitions to translate Z80 to 8080 mnemonics and vice-versa, and definitions to implement CSAL, a C-structured assy. language, allowing code like add a.(hl) to be written $a + = {}^{4}hi$

. XLT users can pool their definitions via the XLT Users

NLT costs 39.95. For CP/M 2.2 8" single density disk Z80

Please add \$5.00 for postage and handling. All orders shipped first class. Satisfaction guaranteed. Please, no COD's or PO's. Send check or money order to:

L.A. Software Los Angeles Calif. 90038 213/932-0817

6708 Melrose

CA residents add sales tax CP/M is a trademark of Digital Research Prices and specifications subject to change without notice John P. Jones

6245 Columbia Ave. St. Louis MO 63139 (314) 645-1596

This column is a review of a new native code PASCAL compiler, Turbo Pascal, from Borland International. The product is available for CP/M 80 and 86 and MS/DOS.

I have used both JRT Pascal (JRT Systems) and Pascal/MT+ (Digital Research) regularly and have evaluated Pascal/M (Sorcim) in detail. All of these Pascal implementations are complete and useful for any application for which Pascal is appropriate. The Turbo package, however, is such a significant improvement that this column may sound like advertising copy.

I first saw an ad for this package in the November 1983 issue of Microsystems. The gentleman I spoke to at Borland's main office was very knowledgeable about the product. Based on his answers, I placed an order. Four weeks later the Pascal arrived. The turnaround was slow because they were waiting to get manuals back from the printer.

This review will be limited to the CP/M 80 version, but most of the information will apply to the 16-bit versions as well.

Turbo System Overview

Borland has produced a fast, efficient, complete and convenient Pascal system which is a joy to use. The package includes:

- 1. The integrated editor-compiler.
- 2. Terminal installation utility.
- 3. Program listing utility.
- Demo spreadsheet package (source).
 - 5. Reference manual (254 pages).

Turbo is a Pascal SYSTEM which operates within the CP/M environment. Those familiar with UCSD Pascal will find many similarities with Turbo. When bringing up the system, you specify a "work" file (normally a Pascal source file) which becomes the default for the single character commands Edit, Compile, Run or Save. If the work file is an "include" module, the Main command is used to specify the parent source program.

Turbo is set up for efficient program development. The file type of .PAS is assumed unless specified. If the current work file had not been compiled before the Run command is given, the compiler will be automatically invoked.

The eXecute command allows other programs to be run from within the Turbo system. For instance, if you find that a needed source module is not on a current disk, PIP can be run with the eXecute command to transfer the file, after which the Turbo system and the current work file will be reloaded.

The Dir command accepts the standard "wild card" ambiguous file references and also lists available disk space.

The Option command lets you specify compiler parameters.

Through appropriate selection of Work file, Main file and Options—programs can be compiled memory to memory, memory to disk (.COM file output), disk to memory or disk to disk. For advanced applications you can specify low-level parameters such as the absolute location of code and data within memory.

The Editor

The built-in editor is a WordStar compatible full-screen editor. Default commands for cursor movement, delete and insert, and block and control commands are identical to those for Wordstar. Also, commands can be fully customized with the terminal installation program.

The actions of a few commands have been optimized for writing Pascal source. For instance, a tab (cntl-I) moves the cursor to the position below the beginning of the next word on the line above. This makes indentation and column alignment convenient.

The Compiler

The compiler is a "standard" Pascal compiler with few exceptions and many extensions. When Turbo locates syntax errors, it invokes the editor and positions the cursor at the error. If you had the compiler include the optional error messages, you will get a description of the error as well as the error number. If you need more information, you can go to the manual.

Speed

Compilation is fast! The demo program provided with the system (a mini spreadsheet, 1262 source lines) compiles disk to disk in 74 seconds on a 4MHz

Kaypro 4. (Editor's note: The demo program compiles in 12 seconds on the Slicer—see the Slicer Column for more details.) Small programs which can be compiled memory to memory will compile in seconds.

Run-time errors can be located in the SOURCE! Run-time error messages include the value of the program counter; this value is then used as a parameter in the Find option. Once the error is located, the editor is called and the cursor points to the error.

The numerous extensions aside, Turbo has only six deviations from the Pascal standard. Lack of GET and PUT are the most significant (READ and WRITE have been extended), procedures may not be used as parameters to procedures, and NEW, MARK and RELEASE rather than NEW and DISPOSE are used to control dynamic variables.

There are nine compiler directives. These give you control over parameters like run-time index checking, user interrupts and recursive code generation. Their actions and consequences are fully explained in the manual.

As an example, if user interrupts are enabled, the user will be able to stop the program with a cntl-C at any time. However, in this mode execution will be significantly slower.

Extensions

Turbo has all the extensions the other compilers have, plus:

- 1. Up to 127 significant characters in identifiers.
 - 2. Hex input with the \$ prefix.
- 3. Variable type BYTE unsigned 8-bit integer subrange.
- 4. Dynamic strings—Though you must specify maximum length, full range of string handling procedures/functions, strings can be concatenated with '+', plus you get STR (which converts a number to a character string) and VAL (which converts a string to a numeric value).
- 5. The declaration part of a program is free-form. Although standard Pascal specifies that the LABEL, CONST, TYPE, VAR and PROCEDURE/FUNCTION declaration parts of a program may occur zero or one time and only in

(Pascal Procedures continued on page 32)

ENTER . . . THE FUTURE!



Extended Pascal for your IBM PC, APPLE CP/M, MS DOS, CP/M 86, CCP/M 86 or CP/M 80 computer features:

- Full screen interactive editor providing a complete menu driven program development environment.
- 11 significant digits in floating point arithmetic.
- · Built-in transcendental functions.
- Dynamic strings with full set of string handling features.
- Program chaining with common variables.
- Random access data files.
- Full support of operating system facilities.
- · And much more.

ORDER YOUR COPY OF TURBO PASCAL TODAY TO TAKE ADVANTAGE OF OUR INTRODUCTORY SPECIAL. For Visa and MasterCard orders call toll free

1-800-227-2400 X 968 IN CA: 1-800-772-2666 X 968

(lines open 24 hrs. a day, 7 days a week)

Dealer & Distributor Inquiries welcome.

	Turbo Pascal	IBM Pascal	Pascal MT+
PRICE	49.95	300.00	595.00
Compile & Link speed	1 second!!!	97 seconds	90 seconds
Execution speed	2.2 seconds	9 seconds	3 seconds
Disk Space 16 bit 8 bit		300K + editor Not Available	225K + editor 168K + editor
8 and 16 bit	YES	NO	YES
built-in editor	YES	NO	NO
Generate object code	YES	YES	YES
One pass native code compiler	YES	NO	NO
Locates Run Time errors directly in source code	YES	NO	NO

Benchmark data based on EightQueens in "Algorithms + Data Structures - Programs" by N. With, run en an IBM PC. Turbo Pascal is a trademark of Borland International. MT + is a trademark of MT MicroSystems. IBM is a trademark of International Business Machines.

Turbo Pascal \$49.95 + \$5.00

shipping per copy.

Check Money Order

VISA MasterCard

Card #: Shipped UPS



Borland International 4807 Scotts Valley Drive Scotts Valley, California 95066 Telex: 172373

LEARN TO WRITE A SPREADSHEET

Our introductory offer includes MICROCALC, a spreadsheet written in Turbo Pascal. It will be on your disk and ready to run. And we've included the source code to show you exactly how a spreadsheet is written!

Turbo Pascal includes a 250 page bound manual with extensive explanations and many illustrative examples.

My system is: 8 bit	16 bit
Operating system: CP/M	800
CP/M 86MS DOS_	PC DOS
Computer:Disk	Format:
Please be sure model nur	nber and format are correct.
NAME:	5.71
ADDRESS:	
CITY/STATE/ZIP:	Control of the Contro
TELEPHONE:	199
	ites tax. Outside North America add Bank, and In U.S. dollars. Sorry, no

that order, Turbo allows them in any order and any number of times, so it's convenient to use a library of source modules.

- Pi (11 digits) is a pre-defined constant.
- 7. Arithmetic as well as logical (boolean) AND, OR, NOT and XOR and the bit manipulation operators SHR and SHL (shift right and shift left).
 - 8. Else clause in the CASE statement.
- 9. Typed constants. This is unique to Turbo and extremely handy. Though declared in the CONST portion of the program, typed constants are really initialized variables and can be used as such. No more long sequences of assignment statements to give variables their default or initial values.
- 10. Random access file I/O is implemented with SEEK to position to a specific record. The FILEPOS function returns the current position of the file pointer. ERASE, RENAME and FILE-SIZE are built in. TEXT files are fully supported as are untyped files with BLOCK-READ and BLOCKWRITE.
- 11. There are no less than 8 pre-defined TEXT files (including the default INPUT and OUTPUT). To output to the printer, just write to the pre-defined file LST.
- 12. Turbo includes nine terminal-related procedure/functions. Their actions are defined by the terminal installation program and thus are customized to your system.
- 13. FRAC returns the fractional part of a real number, HI and LO return the high and low order bytes of an integer, and SWAP exchanges the high and low order bytes of an integer.
- 14. RANDOM returns a random real number between 0 and 1 and RANDOM(I) returns a random integer between 0 and I.
- 15. Variables can be declared as AB-SOLUTE, i.e., located at a defined memory location. This is useful for shared variables when CHAINing programs.
- 16. The MEM and PORT arrays (type BYTE) allow direct access to RAM and I/O devices.
- 17. Pointers can be assigned to integers with ORD and be assigned with PTR.
- 18. EXTERNAL procedure/functions are supported, with full parameter passing.

- Other programs can be CHAINed with common variables (shared globals and absolute) or EXECUTED.
- 20. Machine language subroutines can be entered in the Pascal source with the INLINE statement.
- 21. Direct BIOS and BDOS calls are supported with parameters passed in and returned from the registers.
- 22. The heap pointer (dynamic variable management), recursion stack pointer and even the hardware stack pointer (!) are accessible from Pascal.

Documentation

The Turbo documentation is as complete and well-organized as I have seen for any software product. The bound (softcover) manual has both a detailed table of contents and a complete index.

The installation and use of Turbo and its editor are detailed in the first section.

This is followed by information on the portions of the package common to all three implementations and operating system dependent portions. There are separate sections for CP/M 80 and the 16-bit versions.

The final portion of the manual is a quick-reference summary of all the features.

There are few typos in the manual. Some errors and omissions are detailed in an update file included on the distribution disk. Overall, EVERYTHING necessary for use of the package is explained with reasonable clarity and detail. There are even instructions on how to translate the error message file into other languages!

"Gut level" details such as memory utilization, data format in memory, stack structure for parameter passing and the like are all explained. They even go into detail on going beyond the normal uses of standard Pascal.

Performance

Although my timing methods weren't precise (I used a sweep second hand), I did run some benchmarks. It's obvious that Turbo code executes faster than either Pascal/MT+ or JRT Pascal. See the Figures for my results.

Limitations

The most significant limitations to Turbo are related to the 64K address space of the Z80. Source code files which are larg-

er than available RAM can NOT be edited or compiled with Turbo, nor can single programs larger than RAM be executed. However, there are ways around this.

Large source files can be split into fragments small enough to edit, then \$Included in the compile. The include facility, coupled with the free-form declaration part of Turbo programs, makes the generation and use of a library of source modules convenient and very practical.

If the object code is too large to compile to memory, a simple command sends the output to an executable .COM file. Large programs can be compiled as a number of smaller programs which can then be CHAINed for execution. Chain modules contain only program code, no runtime library, and thus use less disk space. Since chained programs can share variables, the lack of an overlay mechanism is not a serious problem.

Criticisms

I found it difficult to find anything significant to criticize in the package. There are, however, a few nitpicking details that can be mentioned.

- 1. I would have preferred a 3-ring binder for the documentation (This is obviously a personal preference).
- 2. The listing utility (TLIST.COM) does not use form feeds for pagination, and at least two printers lost track and got out of synchronization with page boundaries.
- 3. There is no default length for dynamic strings, the maximum length must be declared.
- 4. There is no way to override returning to the editor when compile time errors are encountered. At times it would be convenient to scan the entire source for errors before invoking the editor.

Conclusions

As a standard Pascal, Turbo is without question one of the most cost effective purchases you can make. There are enough extensions and built-in facilities to make the package as useful as 'C' for even low-level work while much more convenient to use.

I would not hesitate to recommend the package to anyone either currently using Pascal or interested in learning the language.

Listing 2

Turbo Pascal is available from:

Borland International 4807 Scotts Valley Dr. Scotts Valley, CA 95066 (408) 438-8400 (Office) (800) 227-2400 X 968 (Orders only)

PASCAL ILLUSTRATIONS

		TABLE 1		
	Turbo	MT+	JRT	
Accuracy (digits)	<=11	<=6	<=14	
Range	1E+/-38	1E+/-18	1E+/-63	

TABLE 2 Turbo JRT Program Sieve 23s. 23s. 375s. **Fptest** <1s. 33. 23. Tstlog 28. 18s. 1.58. 6s.

All tests run on 4MHz Kaypro, timing from bell to bell. For Turbo, compile times memory to memory were <1 sec. for all four test programs; for MT+, compile & link times were less than 2 min.; and for JRT, compiles were in the 40 sec. range. Default compiler options were used in all cases.

Listing 1

```
const
  size = 8190;
var
  flags : array [0..size] of boolean;
  i,prime,k,count,iter : integer;
  writeln('10 Iterations',chr(7));
  for iter := 1 to 10 do begin
    count := 0;
    for i := 0 to size do flags[i] := true;
    for i := 0 to size do
      if flags[i] then begin
        prime := i+i+3;
        {writeln (prime);}
        k := i + prime;
while k <= size do begin</pre>
          flags[k] := false;
          k := k + prime
        end:
        count := count +1
      end;
    end;
    writeln (count, 'primes.', chr(7));
```

program sieve;

The Sieve of Eratosthenes from Byte, Jan. 1983. This program tests general execution speed of a language without using any arithmetic beyond integer addition.

```
PROGRAM FPTEST;
  VAR I: INTEGER;
      X: REAL;
BEGIN
  WRITELN(chr(7));
  X:=(1.0E-04)/3.0;
  FOR I:=1 TO 30 DO
  BEGIN
    WRITE(' x=',X);
X:=0.~1*X;
WRITELN(' x=',X
                x=',X);
    X:=0.1*X;
  END:
  WRITELN (chr(7));
END.
This program, from ""Pascal Programs for Scientists and
Engineers' by Alan R. Miller, (Sybex 1981) tests the speed, range and accuracy of floating point calculations.
                           Listing 3
program test_log;
var
 1 : integer;
  x,y : real;
(JRT only, add these statements
function ln(x:real):real:extern:
function exp(x:real):real;extern;}
begin
(To insure that loading of external procedures is not
included in the timing, add these statements for JRT
  x := ln(1.0);
  x := exp(1.0);
  x := (1.0E-4)/0.3:
  WRITELN (chr(7));
  for i := 1 to 20 do
  begin
    y := ln(x);
    writeln('x=',x,', ln=',y,', exp(ln)=',exp(y));
    x := 0.5*x;
  end:
  WRITELN (chr(7));
Tests the accuracy of floating point calculations.
exp(ln(x)) should = x. From Miller.
```

Listing 4

```
program tstsin;
var
 i : integer:
 x : real:
(For JRT add the following statement
function sin(x):real:extern; }
begin
(for timing accuracy add this statement for JRT
 x := sin(1.0);}
 WRITELN(chr(7));
 x := (1.0E-4)/0.3;
  for i := 1 to 40 do
  begin
   writeln('x = ',x,' \sin = ',\sin(x));
    x := 0.1 4 x;
  end:
 WRITELN(chr(7)):
end.
```

Tests the sin function. From Miller.

By Jay Jaeckel

418 Kings Way Mundelein IL 60060

It seems like everytime you see a Z80, you find someone trying to patch an 8088 board onto it. Well, it turns out that the new Xerox 16/8 is an add-on board modification to their 820-II and it comes with 128K of RAM (another 128K is optional) along with CP/M 80, CP/M 86, and MSDOS.

In fact, from the outside, it looks like Xerox just stuck in an SWP board and called the whole thing an IBM. Actually, they didn't.

Friends at Xerox have told me that the company seriously considered using the SWP 8088 co-processor, with its internal 16-bit and external 8-bit I/O, but decided instead to use a real 16-bit 8086. (Xerox does offer an 8088 board in Europe but not here.)

Anyway, it looks like Xerox may be planning to incorporate one of the standard busses into their system and though no one is really saying which buss it will be, they aren't denying that it might be the S-100 (it ain't no school bus, that's for sure). They are also looking at high-res color graphics. I'll let you know when I get more information.

Cheap Parts.

One of the best sources for Xerox parts, believe it or not, is Xerox! Many manufacturers have discount outlets and the outlet for Xerox is:

Xerox Manufacturing Outlet 1341 W. Mockingbird MS 503 Dallas, TX 75247 (214) 960-3367

The people are friendly and shipping is excellent on phone orders with a VISA or MasterCharge card. However, if you must mail an order in, use a certified check. No COD's.

Be sure to put the "MS 503" in the address; it's very important! Minimum order is around \$10. See Figure 1 for some

of the fantastic deals I have seen there. Many may still be available.

From time to time I have seen Shugart 800, 801, 850 and 851 at excellent prices here also, but you have to move fast.


If you are just starting out, be sure to ask about their complete component sets (drives, monitor, board, cables, etc). Also, ask about CP/M. I have heard that they have a lot of 2.2 versions lying around with beautiful binders and lots of utilities along with CBIOS source.

More Cheap Parts

EPIC Sales POB 401471 132 Walnut Plano Center Garland, TX 75040 (214) 272-5724

EPIC seems to have a lot of the same stuff that the Xerox Outlet has. They also have disk controller chips, RAM (200ns 4164's @ \$5.00 each), ROM and other goodies.

I know that Bob at EPIC is working on a less-than-\$1000 package to give 820 people a hard-disk, interface, and BIOS. How much less, I don't know, but I have seen 5Mbyte drives as low as 380.00. I'll keep you posted on the special deals that I see from time to time.



For only \$95, Q/C is a ready-to-use C compiler for CP/M. You get complete source code for the compiler and over 75 library functions. Q/C is upward compatible with UNIX Version 7 C, but doesn't support long integers, float, parameterized #defines, and bit fields.

- · Full source code for compiler and library.
- · No license fees for object code.
- Z80 version takes advantage of Z80 instructions.
- Excellent support for assembly language and ROMs.
- · Q/C is standard. Good portability to UNIX.

Version 3.2 of Q/C has many new features: structure initialization, faster runtime routines, faster compilation, and improved ROM support. Yes, Q/C has casts, typedef, sizeof, and function typing. The Q/C User's Manual is available for \$20 (applies toward purchase). VISA and MasterCard welcome.



5266 Hollister Suite 224 Santa Barbara, CA 93111 (805) 683-1585

Q/C, CP/M, Z80, and UNIX are trademarks of Quality Computer Systems. Digital Research, Zilog, Inc., and Bell Laboratories respectively.

Figure 1 - Example Prices at the Xerox Outlet

820 Mother Boards Assembled and Working	300.00	
820-II Mother Boards (that's right 820-II) they tell me most are working but untested good luck. but for the money	350.00	
Display/Processor Power Supply,		
enough for 2 5-1/4 drives and monitor		
(XEROX powers 5-1/4's through cable)	75.00	
DS/DD 5-1/4" Shugarts W/Case & Cable	400.00	
5-1/4" Disk Drive Case only	10.00	
5-1/4 Disk Drive Cable assembly. For 8" use a tiny screwdriver to remove contacts from AMP 36 pin edge card connector and plug contacts into AMP 50 pin edge card connector (AMP PN# 1-583717). Works great!		
Motorola Monitors I suspect these are out of the 860		
line, as it includes power, chassis,		
& documentation	50.00	
820 MAXISWITCH keyboards	25.00	
820 cable assemblies		
saves chasing connectors	2.00-8.00	

EPIC SALES

Outstanding Buys in Disc Drives

SIEMENS FD 200 - 8P

THE QUALITY EQUIVALENT TO THE SHUGART 850/851

These Drives are compatible without modifications. They are burned in & quality checked prior to shipment. Manuals are included without cost.

\$229.00

► 5¼" WINCHESTER 10 Megabyte Capacity ◆ \$599.00

Seagate Model ST 412

Factory Fresh

Hacker's Kit

Host interfaces, controller cards, software, interconnect cables, and power supplies are available for the following computers:

IBM APPLE XEROX 820-1 XEROX 820-2 \$ 100 MULTIBUS

\$325.00

ALL SOFTWARE \$20.00

Xebec 1410 Controller

WD 1001 Controller \$195.00
Aztec Switching Power Supply \$95.00
IBM Host interface \$95.00
Apple Host Interface \$95.00
Xerox Host Interface (Plugs into Z80 includes software) \$65.00

∠ All Drives are backed with our 90 Day

No Questions Asked - Money Back Guarantee.

TERMS:

Master Charge, Visa, American Express, Money Orders. Allow 10 days for personal checks. Add 6% Sales Tax if Texas Resident. Add \$4.00 per Drive UPS Charges; \$1.50 for COD.

OPEN: Mon - Thurs till 8:00 PM Fri & Sat till 5:00 PM

Quality you can trust • Outstanding Prices!

132 Walnut - Plano Center • Garland, TX • 214-272-5724

Micro Cornucopia

KayPro Disk K1 Modem software

This disk is absolutely priceless if you will be using a modem to communicate with bulletin boards, other micros or mainframes. MODEMPAT. COM: Menu selection of baud

rate, bits/character, stop bits, & parity for serial

MODEM7.COM: Very popular MODEM 7 configured for KayPro.
MODEM7+.COM: This is MODEM7 & MODEMPAT combined - you can communicate with anything!

KMDM795.COM: Super-version of MODEM7

set up for KayPro.
TERM.MAC: Commented disassembly of the TERM program you get with your KayPro so you

can configure it for any interface. SQ/USQ.COM: Programs to squeeze and unsqueeze files for faster transfer.

KayPro Disk K2 Utilities

Really oodles of spiffy little (and big) programs to help you get full use of your KayPro. ZESOURCE.COM: A true Zilog format disassembler for 8080 and Z80 object(.COM) files. Now you can turn .COM files into . MAC

UNERA.COM: Simply enter "UNERA" followed by the name of the file you just erased and presto, the erased file is back! A lifesaver. FINDBD54.COM: Checks an entire disk, reports bad sectors, and then creates a special file containing those sectors. You save a bundle on disks.

CAT2: This a group of programs which create and maintain a single directory of all the programs you have on all your disks. Even keeps track of which programs are backed up and which aren't. UNSPOOL.COM: Use your KayPro II and print files at the same time. Doesn't slow down

system response! DUMPX, DU-77, COMPARE, SUPERSUB, FORMFEED, DIR-DUMP, . . . and all have documentation on disk.

KayPro Disk K3

Games
PACMAN.COM: Despite the KayPro's lack of graphics, this one looks and plays amazingly like

the real thing! Keep it hidden.

ZCHESS.COM: Chess with a 1-6 level look

OTHELLO.COM: You learn it in minutes,

master it in years.

BIO.COM: Generates custom graphic biorhythm. MM.COM: Master Mind. WUMPUS.COM: Classic wumpus hunting.

KavPro Disk K4 Adventure

This disk contains one 191K game, Adventure. ADV.COM: This is the latest, greatest, most cussed adventure ever devised by half-mortals. This is the 550-point version so the cave is greatly expanded and the creatures are much smarter.

> KayPro Disk K5 MX-80 Graphics

A complete MX-80 graphics package including

KayPro Disk K6 Word Processing Utilities

A powerful line oriented text editor that looks like Unix's EX, plus a scad of text utilities written in C which handles pretty printing, shortening a file, multiple space output, add tabs, remove trailing whitespace, and more. Also includes ROFF.COM a very neat text formatter.

KayPro Disk K7

Small C Version 2 Compiler
This is a greatly extended version of Ron Cain's
Small C compiler. Version 2 has more expressions
and larger library, true subset of Unix C. Disk
contains compiler, documentation, and library everything you need.

KAYPRO USERS DISKS

for KayPro II, 4 and 10

\$1200 each



The following are full disks of software assembled specifically for the KayPro. Each program has a .DOC (documentation) file and many come with source.

KayPro Disk K8 Small C Version 2 Source This disk contains the source (written in Small C)

of the Small C version 2 compiler. Get K8 if you want to try extending the compiler. (You must have K7.)

KayPro Disk K9 **ZCPR**

ZCPR: The big news on this disk is the self-installing version ZCPR available only from Micro C. Once you have ZCPR in your CP/M, you'll never go back to straight CP/M! For instance, ZCPR searches drive A for any program not found on drive B, so, even an empty disk in drive B, appears to contain every program on A. It's B appears to contain every program on A. It's great for text editors, compilers, etc. Plus many more new features to make CP/M easier to live with. In fact, Digital Research incorporated many features of ZCPR into CP/M 3.0. Works on Karpa II and A.

KayPro II and 4.

PASWORD: Lets you encrypt and decrypt your

precious files. Includes source.

EX14: a super replacement for SUBMIT.

Plus many more: TREK, FIX, FIND, SNOOPY ALIENS and DIF2.

KayPro Disk K10

Assemblers
We've received a lot of requests for a Z80 assembler. So Dana put in some long hours getting the Crowe Z80 assembler to run on the KayPro (and every other Z80 machine).
CROWECPM: This is a first class Z80 assembler with the Way and the Samuel CROWECPM: This is a first class Z80 assembler with the Way and the Samuel CROWECPM: This is a first class Z80 assembler with the Way and the Samuel CROWECPM: This is a first class Z80 assembler with the Samuel CROWECPM: This is a first class Z80 assembler with the Samuel CROWECPM: This is a first class Z80 assembler with the Samuel CROWECPM: The Samuel CROWECPM:

bler. We use this assembler daily (and we included its source). Takes standard Zilog mnemonics.

LASM: This is a more powerful version of the ASM assembler you received with the KayPro. This will link multiple programs together at

PRINTPRN: This program makes it easy to print the listing files generated by the Crowe

KayPro Disk K11
Library & Checkbook Programs
CHECKS: This has been a very popular group of programs. Categorizes checks so you can keep track which are tax deductible and which get charged to which projects. Includes source and

excellent example check files. Very powerful.

LIBR: This is a complete set of library routines which let you group files into a single file called a which let you group the since a single the canted a library. Then CP/M sees them as a single program, but with the library routines, you can list them out separately, run them separately, or divide them up again. Almost like a unix environment. DISPLAY, VLIST, PGLST: Additional screen and print utilities.

KayPro Disk K12 FORTH

Yep, this is FORTH, one of the most unique, most extendable languages known, and for a paltry \$12.00. This disk contains not just one FORTH, but two, along with an editor, decompiler and 8080 assembler! The editor even uses the cursor control keys.

FORTH: This is true fig-FORTH. KFORTH: A very nicely extended version of fig-FORTH. PLUS, all the rest of the FORTH goodies. (Forth KayPro Disk K13

Source of fig-FORTH
All this disk contains is the 40K ASM source of fig-FORTH with the hooks in place for the KayPro. This disk is for FORTH hackers who just can't leave anything alone. (Look, you probably have faults, too.) The source of FORTH is here because there isn't room on K12. This is the only disk that isn't stuffed.

> KayPro Disk K14 Smartmodem Programs

This is the disk for you if you have a Smartmodern compatible modern. With this disk you can communicate with anything but a recalcitrant spouse. Handles goodies like autodial along with multiple directories.

SMODEMK: Smartmodem program set up for

the KayPro (and source).

XMODEM: Lets you remotely control your KayPro from a distant computer.

KAYTERM: This is the information you need to run or write modem software on the KayPro.

KayPro Disk K15

Hard Disk Utilities
This disk is for the KayPro 10 or any KayPro with
a Winchester drive. With these routines you can not only backup files (with printed directories of the backup disks), you can also break up large files. The backed-up files are not encoded (as they are with KayPro's backup routine) so you can access them on any system.

> KayPro Disk K16 Pascal Compiler

This is a real Pascal compiler. It supports only a subset of the language (no records, pointers, booleans, reals or complex) but it generates a real COM file. Everything is on this disk: the compiler, its source, example programs and documentation.

KayPro Disk K17 **Z80 Tools**

This is for those of you who are into Z80 assembly

language. XLATE.COM: A very good 8080 to Z80 transla-

tion routine.

DASM.COM: An easier to use version of ZZSOURCE (the Z80 disassembler). This full disk includes source and documentation for both

KayPro Disk K18 System Diagnostics

NEW!

Just as we finished editing the routines on this disk, we received a copy of KayPro's diagnostic disk. The memory test, drive exercise, and drive alignment routines on this disk are more powerful than KayPro's versions. (Plus, it's only \$12!) Setup for KayPro II and 4.

KayPro Disk K19 **Prowriter Graphics**

This is a complete Prowriter graphics package written by the same Micro C subscriber who wrote the MX-80 graphics package. Plot points, lines, circles, boxes, and more. Examples, documentation, and more.

We have something special for your Kaypro!

ROMs from Micro Cornucopia

There are two ROMs in each Kaypro, a monitor ROM and a character ROM. The Monitor ROM supplies information for the Z80 processor on such things as how to get information from the disk drives, and which character to use as a cursor. The character ROM works entirely in the disk crives, and which character to use as a cursor. The character ACM which selected wide circuit and it determines what the characters look like on the screen (for instance, does the "f" have a high, small cross bar, or a lower, longer one of the Micro C character ROM). When you speed up your Kaypro, you are speeding up the processor clock so you have to use a monitor ROM that will also run at the higher speed. You are not changing the video clock when you speed up the Kaypro so you don't need to change the character ROM (unless you want the nicer looking character set). Since the monitor ROM tells the processor how to do disk accesses you consider the processor how to do disk accesses you are going to have to change that ROM in order to upgrade to larger drives.

Pro-Monitor II for Kaypro II

- 1. This ROM is a fast part so you can run 4 or 5 MHz with your Kaypro II
- It gives you a non-blinking block cursor (much less irritating), though you can specify a standard blinking underline if prefer it.
- It does faster disk accesses (even if you don't speed up your system).
 It throws away null characters (those little asterisks that sometimes garbage the screen during munications)
- Includes complete printed instructions for simple plug-in installation. (takes 5 minutes).

Pro-Monitor 4 for Kaypro 4

This ROM does everything the Pro-Monitor II does, only it's for a Kaypro 4. Though the ROM that comes in your Kaypro 4 will run 4 or 5 MHz (unlike the ROM that comes in the II), this ROM also gives you:

- 1. Non-blinking block cursor.
- Faster disk accesses.
 Throws away null characters.
- Complete printed instructions for simple plug-in installation (takes 5 minutes).

Pro-Monitor 8 package for Kaypro 4

This ROM package does everything the Pro-Monitor II and 4 do (it will run at 5 MHz, ignores nulls, has the fast disk accesses). In fact, even if you will be using your original 191K or 390K drives for now, you can use this ROM package. The Pro-Monitor 8 features include: 1. You get 784K per disk with quad density (96 tpi, double sided) Tandon 100-4 (or equivalent)

- drives.

 2. You can use any combination of Tandon 100-1 (Kaypro II), 100-2 (Kaypro 4), or 100-4 drives as drives A and B.
- You can boot from any disk with normal system tracks (Kaypro II, Kaypro 4, or Kaypro 8). The disk needs no modification.
- 4. You can choose any character (including space) as a cursor and you can choose to make the character blink or not blink. Plus, you can change the cursor at will.

 5. You get a disk which contains a new copy routine for copying and formatting 784K disks, and a drive diagnostic routine for checking out the quad density drives.
- 6. You get complete printed insturctions for installation of ROM and drives (takes 10 to 15 minutes, including drives). 7. The installation requires no cuts or jumpers, everything simply plugs into a Kaypro 4. (If you have a Kaypro II, see the modification article in Micro C issue 15 to turn your II into a 4.)

Pro-Character ROM (for Kaypro II and 4)

The character ROM gives you a nicer looking character set. Kaypros have come with two different character ROMs, the early character ROMs had a rotten g, y, q, f, and t as well a commas and semi-colons that were hard to tell from periods and colons. On the newer systems (manufactured since Sept 83) half of the characters (notably the g) have been improved, but they haven't gone all the way.

Also, many of the older character ROMs were poor quality parts so they generated snow as information scrolled up the screen. This white flecky snow disappears when you install a Pro-Character ROM.

The character ROM comes in two flavors:

- 1. The standard Greek Pro-Character has the nicer character set plus the standard Kaypro Greek
- 2. The Clean Pro-Character has the nicer character set but no Greek characters. This is the ROM for people who get strange Greek characters on the screen when interfacing with Mainframe
- Complete printed instructions for simple plug-in installation (takes 5 minutes) Note: These ROMs will not work in the KayPro 10 or the latest KayPro 4 with graphics (it contains the KayPro 10 board). We are working on new ROMs for these systems.

Titles.	
Pro-Monitor II	29.95
Pro-Monitor 4	29.93
Pro-Monitor 8 (package)	49.93
Pro-Character (either Greek or Clean)	29.95
Pro-Set II (Pro-Monitor II & Pro-Character)	55.00
Pro-Set 4 (Pro-Monitor 4 & Pro-Character)	55.00
Pro-Set 8 (Pro-Monitor 8 package & Pro-Character)	70.00



Pro-8 ROM Package

The PRO-8 package from Micro Cornucopia upgrades your KayPro 4 to a KayPro 8 with 784K bytes (96 directory entries) per Tandon 100-4 (or equivalent) quad-density drive. Plus, you can select your own cursor character (and change it at will).

The package includes the new PRO-8 monitor ROM, a disk of formatters and copiers, and printed instructions. (We even tell you how to turn your KayPro II into a KayPro 4.) All you add is one or two double-sided double-density (390K), or double-sided quad-density (784K) drives. You get over 1.5 Megabytes on a twodrive quad-density system!

This new system can read, write, and format KayPro II and KayPro 4 disks as well as KayPro 8 disks. And it recognizes each disk type automatically!

All this for only \$4995!

Watch Micro Cornucopia for more KayPro compatibles.

Call or write for information on the other KayPro II and 4 ROMS from Micro Cornucopia.

KayPro II Schematic Package

This is a complete schematic of the KayPro, logically laid out on a single 24" x 36" sheet no more searching to see where a signal goes or comes from. Even the unused gates are shown.

It's drawn in positive logic, lines are labeled, and we've tossed in hours and hours of careful checking for accuracy. Then we added a Theory of Operation that's keyed to the schematic.

\$2000

Micro Cornucopia

P.O. Box 223 Bend, OR 97709 503-382-8048



9-5 Pacific Time Monday-Friday



By David Thompson

I've been very guilty of bias in this column and so I'm taking this opportunity to set the record straight.

I have suggested (numerous times) that you do your own thing, start your own business as a consultant or whatever, and then reap the rewards of your effort.

Well, that's just fine, except for two things. First, if you don't make it, you'll have put in a lot of time and effort for little more than an education (which isn't necessarily all bad but wasn't exactly what you were hoping for).

Second, if you do succeed, you may well find that your success takes you away from what you really enjoy doing.

Micro C

Let's take Micro C as an example. It's been more successful than I had hoped it might be. We have over 4,000 subscribers (and who knows how many people read each copy). Subscriptions and advertising are paying for the printing, typesetting, and postage. Disks and ROMs are paying for the building, insurance, heat, help, and our time.

I started Micro C because I enjoyed building the Big Board and because I really enjoyed writing. At least I enjoyed writing when I felt like I was talking directly with my reader. (I always felt that was the purpose of writing.)

You see, after spending a couple of years on the city desk for a daily paper and a couple more years writing technical manuals for Tektronix (before moving over into engineering), I found that I felt stifled writing to their specifications. (What they called training was little more than teaching me the dimensions of their straightjacket.)

If you have ever seen a Tektronix manual, you'll know immediately that it was written by an inhuman object (a committee) for an inhuman object (an engineer). As manuals go, they aren't bad but you wouldn't take one to bed with you. (On the other hand, you probably wouldn't take a scope to bed with you either.)

Anyway, I started Micro C because I loved computers and because I wanted to write without the straightjacket. Well, now I spend about five percent of my time writing and another five percent working on computers.

The rest of the time I'm answering questions on the phone, ordering supplies, filing, cleaning off my desk (and I still don't do it often enough), writing ads, writing replies to subscribers, making sure we have the right unemployment insurance, fire insurance, workman's comp insurance, and generally doing all the other little and big things that have to be done to keep the business going.

I've always had the feeling that "in about six months" things would ease up, the long days would turn into something resembling eight hours, and the six- and seven-day weeks would eventually become five-day weeks.

Well, in three years it hasn't gotten much easier. What I'm doing is different now that Alice and Dorcas are taking and shipping orders and Dana is doing most of the hardware and software work (sigh). Plus, Eric is now keeping track of articles and deadlines. That should be a real help. Anyway, there is always a lot more to be done than I can possibly get done, and it doesn't seem to get better.

Don't get me wrong, Micro C is a real kick and a real education. I've enjoyed learning about business and I like to try things and see how you respond.

And, I really enjoy the SOG because it gives me a chance to see you and share some very special time. The synergy generated at the SOG is absolutely incredible, so it's the high point of my year. When you consider the amount of energy that 100 like-minded people can bring to one place, try to imagine what it must be like to be in the center of a network of over 4000.

The point I'm trying to make is that when you go out on your own, you are starting on a journey that could take you a long way. It could force you to travel long hours over arduous routes with no visible destination. The payoffs can be great, and they can come in a multitude of ways, but the emotional and physical costs can be substantial. Be aware of them before you leap in.

If you would rather not learn business and advertising, and writing, and customer relations, and promotion, and all the things that go into making a business work; if you would rather have a 40-hour week and a real vacation; and if you val-

ue security; then you'd better think seriously before jumping out on your own.

But then, it might all be worth it. It's even possible that you too might need to write without a straightjacket.

Turn in a Friend

Now that Eric Belden has joined Micro C (assistant editor and kitchen help), I'm going to get a chance to do something I've been wanting to do for a long time.

You see, I'd like to spend some time with the people who are moving and shaking in our end of the computer world, people who are surviving with a computer, hardware and software designers and writers. I'd like to get to know the famous early computer people like Ward Christianson, Leor Zolman, and Don Lancaster. If you know people who are doing great things with single board systems or who are just really interesting philosophers, designers, etc., whose ideas are way beyond mere mortals, then let me know.

I plan to take a camera and a pad (I know, I know, but no one has come up with a notebook-sized portable that meets my needs yet), so I can put them in Micro C (generally in this column).

I'm very excited about this. I think it will be a chance for all of us to get a real feel for the people who are working at the edges of this great technology.

So, if you know the whereabouts of any of these people please call or drop me a line. Include as much information as you can as well your name and phone number.

1984 West Coast Computer Faire

The Computer Faire people have tentatively scheduled a Micro C meeting for Saturday afternoon, March 24th. See the Faire schedule for confirmation of the meeting and for the exact time and

We are not having a booth at the Faire this year. I will, however, be in and out of the MicroSphere booth (No. 18) on Saturday.

David Thompson

Review by John S Allen

40 Rugg Road Allston, MA 02134

Inside CP/M By David E Cortesi Holt Rinehart and Winston 572 pages

Micro Cornucopia has already reviewed three other books on CP/M (see issue #1, page 5), and most readers probably already have one of these. So why buy a new book which costs \$26.00?

I bought *Inside CP/M* the first time I saw it in my local bookstore. You see, the day before, I'd tried to automate my disk initialization using a SUBMIT file. All I got was a brief disk access and a return to CP/M. None of my other books were any help.

Nuts and Bolts Information

When I opened *Inside CP/M*, the first page I turned to—quite by accident—explained exactly why SUBMIT and XSUB would not work in my application.

"XSUB sets up the monitor to answer line input requests with a line from the submitted file. It does nothing for byte input requests, for which the monitor continues to come to the terminal. It is somewhat of an adventure to discover which commands use line input..."

This book is chock full of such valuable inside information. Cortesi has evidently exhaustively tested all CP/M functions and commands and describes their idiosyncracies, not just how they are supposed to function. If you are doing CP/M systems programming, this book will help you avoid many, many pitfalls.

Beginners Too

But this book is not just for experienced programmer. It starts out with a tutorial for beginners and the information is very thorough without talking down to the reader. Plus it is organized such that you don't have to refer ahead to something that hasn't yet been covered.

The transition from user material to systems material is done via several short assembly language listings. These listings also introduce you to other aspects of CP/M such as assemblers and they introduce you to methods for generating screen displays.

Writing Style

Cortesi's style is a model of clarity. This is the first computer book I find myself picking up just because I enjoy the prose. (It has the same urbane, witty, gentle style as Micro C.)

Plus, Comments On Other Topics

I've got a request for those of you who have done multiple modifications to your systems. Which mods work together? What happens if you do a commercial double density upgrade and one of the 256K mods. Which 256K mod works with what software? Do keyboard translations routines interfere with use of other programs? Which programs?

Please let Micro C know so we can come up with a table of compatibles/incompatibles.

Also, I'd like to mention that the CBIOS on user disk 2 and 9 is really excellent! My Shugarts sounded like ma-

chine guns while loading Wordstar text file before I installed this routine. Plus, the parallel print driver works fine.

ZCPR is another winner. The only problem with it is that the paging goes too far if any of the lines are longer than 80 characters.

FORMAT4 crashes into PFM when finished and FORMAT5 works like a charm on blank disks but is very slow on previously formatted disks.

XMON is really strange. It translates all keyboard inputs to upper case (including punctuation). Does anyone know what is happening?

. . .

BIG BOARD I I/O EXPANDER

\$19.95 BARE BOARD AND DOCUMENTATION

- 3" x 5" Quality PC board with complete assembly and operating manual.
- Adds one fully buffered PIO with handshaking.
- Piggybacks right onto big board. Plugs into socket U89. (Requires 1 jumper)
- PIO U89 addressing remains unchanged.
- Added parallel output connector has same pin outs as big board J5 connector. Makes interfacing of present products easy.
- All orders shipped 1st class mail.

Send check or money order to:

LOGIC PLUS 10 Esquire Road, Norwalk, CT 06851

Please include \$2.00 for postage and handling. CT residents add $7\frac{1}{2}$ %. Allow 4 weeks for delivery.

Using dBase II Down Under

By Jim Reid

81 Parriwi Road Mosman, Australia NSW 2088

In 1981 I was attending a machinery exhibition in Los Angeles. I wanted to locate a database package and had been given a brief specification and a couple of names in California.

Most of my time had been spent doing battle with telephones that answer back, swallow coins as well as the best slot machines, or spit coins at me when I was crazy enough to insert the wrong amount. Then, of course there was the horror of horrors when I was able to supply the operator with the name of the corporation I wished to contact but did not know the area code. (If I had known the area code I wouldn't have needed to bother her in the first place.)

My search eventually led me to Software Distributors. The lass I met there must have realized I was a harmless Australian who wasn't trying to steal the software secrets of the United States and had not even taken the prescribed university course in reading a phone book. Anyway, she took pity on me and suggested I should explore this new package they had just received.

Iwas familiar with the hardware of micros but my programming experience was limited to small subroutines in assembly language.

dBaseII

I was first introduced to dBaseII by George Tate in 1981 (in an apartment house garage on Robinson Street).

I purchased the manual and returned home. No one in Australia had even heard of it and the general thought was that Condor was the way to go. I had previously purchased the Condor manual and after thoroughly examining both, felt that dBaseII had more to offer. So I bit the bullet and ordered my package.

We take a big chance when we order programs by post. There is no guarantee that we will receive what we order, and the lines of communication from Down Under are long, with no legal redress. Further, our customs is very aggressive and insists that we pay 35% import duty on the invoice cost of discs plus a further 20% sales tax (which amounts to 67%).

At the same time, I ordered my original Big Board from a nameless (hopeless) Australian agent and waited with bated breath for it all to arrive. I eventually received the Big Board together with CP/M and soon found that I needed a great deal of help getting started with CP/M.

This may seem a little off the track in an article dealing with Database systems, but I feel it is essential to inform you fully of my limited ability so that you may gauge the ease with which I can use dBaseII.

My main occupation is microcomputer consultant. Since learning to use dBase I have written many specific use programs for use in analysing clients' problems. I have used it mainly in writing front end programs to prepare data to be processed later by the traditional accounting programs. I have also, however, completed a sales management and automatic quote system, and a complete job estimate and cost analysis program for the printing industry. This printing package will be put into service using the Runtime package in the next few weeks.

My initial version was 2.02. I then updated to 2.3 and now have a 2.4 for evaluation. I suspect that this evaluation copy may have some bugs as it does not perform programs previously written using version 2.02 as fast nor with the same degree of reliability as previous versions. Unfortunately programs must run under 2.4, particularly memory files, in order to compile them using the db-code package. Also, I did find that some conditionals that work effectively using dBaseII give syntax error messages under Runtime. See Figure 1.

These may seem like small changes, however, they increase the number of

APPEND FROM B: JOBCOST FOR INVNUMB < > ' '

DELETE FOR INVNUMB < '&MINVTEMP'

USE INVREPT

disk accesses and slow program execution. In addition, there is the time to locate the problems.

A major improvement for Australian and European users has been the option to input dates in the DD/MM/YY. format or MM/DD/YY as is standard in most American software. This can be specified at the time of installation in version 2.4.

See Figure 2 for the new commands.

Without doubt the most major fault I have found has been the inability to delete temporary files which are created by combining data from a primary and secondary file. See Figure 3 for listing.

However, now you have to remove TEMPMEMO when exiting the program with the instruction:

QUIT TO 'ERA TEMPMEMO.MEM'

I have been a registered user of dbaseII since the early days and my serial number is 1871. However, not once have I been advised of an update or potential problem, and in fact many letters I sent to them are still unanswered. They even managed to lose my bank draft for the purchase of the runtime package and only found it when I arrived on their doorstep with a receipt from the bank.

I feel these problems are a great shame since the program has great potential and will ultimately be one of the programing standards. No doubt they are manifestations of the classic rapid growth syndrome and will eventually be rectified. I look forward to the day when this happens as I am sure my faith in this product will eventually be rewarded.

```
USE B:JOBCOST
COPY STRUCTURE TO INVREPT FIELDS CUSTNAME, JOBDESCR, JOBNO, ESTPHLAB,;
ESTSTLAB, ESTPRLAB, ESTFILAB, ESTINLAB, ACTPHLAB, ACTSTLAB,;
ACTFRLAB, ACTILLAB, ACTINLAB, ACTOFLAB, ESTPHMAT, ESTSTMAT, ESTPRMAT,;
ESTFIMAT, ESTINMAT, ESTOKMAT, SUBCONT, FREIGHT, SALEREP, INVNUMB,;
INVDATE, INVPRICE, SALETAX, PROFIT, MARKUP, PRINTED

Had to be changed to:

USE B:JOBCOST
COPY STRUCTURE TO INVREPT

And the following line:

USE INVREPT
APPEND FROM B:JOBCOST FOR INVNUMB < > ' ' .AND. INVNUMB > '&MINVTEMP'

Had to be changed to:

Figure 1-
```

Modifying Conditionals

for DBase II Runtime

Figure 2 - New DBase II Commands

New commands:

```
HELP
        - user aid command
REINDEX - rebuild index file
        - display multiple lines of text, terminated by ENDTEXT
Supplemented Commands:
APPEND, INSERT, EDIT, CREATE - can use a format file for screen control
BROWSE - can be given a list of fields to work with
DISPLAY STATUS - shows databases/indexes in use and SET settings
READ & REPLACE - can be directed to NOT update indexes via NOUPDATE
RELEASE
                - can release subsets of memory variables
RESTORE
                - can restore additively to existing memory variables
SAVE
                - can save subsets of memory variables
SET RAW ON
                - eliminates extra spaces in DISPLAY and ? commands
                 - replace clause can have WITH phrases
UPDATE
```

Figure 3 - Getting Around DBase II Delete Problems

```
USE TIMEWEEK
COPY STRUCTURE TO B: NEWWEEK
USE B: THISWEEK
SORT ON JOBNO TO B:WEEKSORT
USE
* DELETE FILE B: NEWWEEK (WORKS OK HERE)
SELECT PRIMARY
USE B: NEWWEEK
SELECT SECONDARY
USE B:WEEKSORT
DO WHILE . NOT. EOF
SELECT PRIMARY
APPEND BLANK
REPLACE P.JOBNO WITH S.JOBNO
 IF S.SECTION= '1
REPLACE ACTPHLAB WITH S. HOURCHRG
ENDIF
 IF S.SECTION= '2'
  REPLACE ACTSTLAB WITH S. HOURCHRG
  IF S.SECTION= '3'
  REPLACE ACTPRLAB WITH S. HOURCHRG
  IF S.SECTION= '4'
  REPLACE ACTFILAB WITH S. HOURCHRG
  IF S.SECTION= '5'
   REPLACE ACTINLAB WITH S. HOURCHRG
   IF S.SECTION= '6'
   REPLACE ACTOFLAB WITH S. HOURCHRG
   ENDIF of
 SELECT SECONDARY
 SKIP
 IF EOF
ERASE
? ' UPDATING FILES '
 ENDIF eof
 ENDDO
USE (this should normally close all files)
* DELETE FILE B: NEWWEEK (THIS GIVES FILE CURRENTLY OPEN MESSAGE)
I spoke with Ashton Tate while in Los Angeles they suggested the
following fix which does work,
SAVE TO TEMPMEMO
CLEAR
USE
DELETE FILE B: NEWWEEK
RESTORE FROM TEMPMEMO
```

E Z PROMMER

EPROM PROGRAMMER

FOR THE BIG BOARD AND XEROX 820

FEATURES:

- Supports 2716, 2732, 2732A, 2764
- Easily installed with only two connections
- No external supply needed, all power derived from +5 Volts
- All power controlled by software
- Extensive MENU driven software to Read, Program, Save, Load, Verify CRC check, Dump, Erase check complete with source code
- Over one year of troublefree use.

EZPROMMER

A&T w/Harness, Disk\$125 Kit with Disk \$90

APL

CHARACTER GENERATOR FOR XEROX 820-II

Upgrade kit allows the 820-II to display all the standard characters and attributes while permitting the display of all APL characters. Kit includes ROM and software

APL UPGRADE KIT ... \$49.95

NY RES. ADD LOCAL TAX. POSTAGE AND HANDLING \$2.00 VISA, MC, CHECK or COD

716-377-0369



P.O. BOX 81 PITTSFORD, NY 14534

Integrated BIOS for BB II

This BIOS adds special features for floppy and winchester users.

Floppies

Read and write almost any 8" and/or 5" disk format. 20 formats included (KayPro, Osborne, IBM . . .)

Use any type of 5" and/or 8" drive (SS, DS, 40 tracks, 77 tracks, 80 tracks).

Boot from any format of disk.

Winchester

Winchester formatter with check for bad sectors automatically assigns alternate track(s) for track(s) with bad sectors.

Winchester sysgen (can make the winchester drive A:)

Also includes codes for New BB II monitor

(with all known bugs fixed).

Note: You must already be running the Bakker's 8" and 5" interface (available from Micro C) before installing the integrated BIOS.

Price \$129.95

SASI Interface for BB I and Xerox 820 I

Includes Card, BIOS, Formatter, and Sysgen Price **\$99.95**

ANDY BAKKERS

De Gervelink 12 7591 DT Denekamp The Netherlands

GET IN THE FAST LANE

WITHOUT BURNING YOUR WALLET with a

U. S. ROBOTICS 1200 BAUD MODEM

 Product:
 Features:
 Price:
 List 1-4 5+mix

 Auto Dial 212A:
 1200/300 baud, auto answer/dial.\$599.\$425.\$405

 Password:
 Coat-pocketable Auto Dial 212A.\$449.\$339.\$319

 S-100:
 Auto Dial 212A on an S-100 card.\$449.\$350.\$325

 Telpac:
 Modem Software from USR..........\$79..\$69..\$59

 Lamp:
 Modem Software from Widener Consulting.\$20...\$20

Latest Technology-----Fewer Parts-----Two Year Warranty

All units are direct connect, full or half duplex 212A, software compatible with the Hayes Smartmodems. The Auto Dial has two RJ1lC jacks, analog selftest, status LED's and a metal case; Password has a smaller plastic case and built-in RS232 cable.

--- NEW PRODUCTS FOR BBI AND KAYPRO! ---

All those who have lusted after several add-ons for the Big Board I, but been discouraged by the shortage of parallel ports, take notice! Now you can run all the add-ons at once with the

Parallel Port Expander.....\$119 assembled, \$60 board + instructions

- eight I/O ports, compatible with Big Board I and Kaypro II & IV.
- operate 2 parallel printers, rom burner, hard disk, and Dynadisk!
- And if you are a real hog, parallel four expanders for 32 ports!

THE ULTIMATE

255 CONTINUOUS CHARACTER AND REVERSE VIDEO CURSOR BIG BOARD I AND KAYPRO II MOD

Now you can have a significant increase in the writing power of your system, with the ability to key in, display, edit, and print 212 characters, including continuous line graphics. Other features are blinking or constant reverse video cursor, character sets to match NEC 8023 and C.Itoh Prowriter printers, key labels, integration with Perfect Writer, and improvements in BBI and Kaypro monitor roms.


NEC Extended character set (C.Itoh has same set, just re-arranged):

Cash price with U.S. shipping; Visa/MC/Net30 add 3%, COD \$6. Please specify RS232C connector sex on Password.

Widener Consulting 2835 NE Brogden Hillsboro, OR 97123 (503) 648-0363



\$2995 PRINTER NOW \$795



\$2995 PRINTER FOR \$795.

THE REASON?....These XEROX Word Processor Printers were built by DIABLO to be the finest money could LEASE—Now there are back off lease fully remanufactured by XEROX and upgraded to state of the art — microprocessor controlled performance.

IT'S ABOUT TIME ... AND SPEED.

Now you can have all the HIGH SPEED and COMMERCIAL GRADE FEATURES such as:

BI-DIRECTIONAL PRINTING

2,000 CHARACTER PRINT BUFFER

VERTICAL & HORIZONTAL MOTION OPTIMAZATION That can save you hundreds of hours of time. These features make it possible to actually print the average letter faster than printers rated at over 80CPS (Characters per second) although our rating is a very respectable 33CPS. That's 0 to 33 Characters — in one second.

YES, IT WORKS WITH YOUR COMPUTER.

Industry standard interface design (Standard Centronics Parallel or RS232) gives you immediate PLUG-IN compatability with the IBM-PCTM, APPLETM, KAYPROTM, OSBORNETM, EPSONTM, RADIO SHACKTM, as well as other popular systems AND its microprocessor intelligence unleashes all the power of sophisticated programs such as WORDSTARTM, MICROSOFT BASICTM and popular disc operating systems.

LET YOUR COMPUTER DO ITS TRICKS.

Professional word processing features such as BOLD PRINTING, SHADOW PRINTING, and UNDERLINING adds impact and emphasis to your documents. SUBSCRIPT and SUPERSCRIPTS lets you write footnotes and formulas like $\rm H_2O$ and $\rm E=MC^2$.

TRUE PROPORTIONAL SPACING makes your text easier to read with up to 1/3 more words on a page and, of course, it looks more professional. It's the way books and magazines are

GRAPHICS CAPABILITIES let you print charts and graphs. The high resolution enables you to black out an entire page with periods, if you choose.

UP TO 75% OFF YOUR SUPPLIES.

PRINTWHEELS—Dozens of long lasting Diablo Standard Metal Printwheels rated at 14,000,000 + characters of clear crisp copy are available world-wide in a variety of languages and special applications.

RIBBONS—Drop-in Cartridge Ribbons are available in HIGH-CAPACITY MULTI-STRIKE, SINGLE-STRIKE or FABRIC and all types come in a variety of colors.

THE PAPER CHOICE

WIDE CARRIAGE—lets you print out up to 195 columns (15 pitch) for financial reports (158 columns at 12 pitch).

STANDARD FRICTION FEED—takes letterhead, cards, envelopes and fan fold paper up to 15" wide.

(OPTIONAL) TRACTOR DRIVE—for precise printing positioning of tabular and graphics data.

(OPTIONAL) SHEET FEEDER—for high volume original letter automatic output.

JOHNSON & JOHNSON

(817) 589-2000

2229 E. LOOP 820 - FORT WORTH, TEXAS 76118

TECHNICAL TIPS

Pushing Your Modem

The price of 1200 baud modems is still a bit steep but there is another way you can cut down on your phone bill. Most 300 baud modems are capable of more than 300 baud, particularly if the distance is not too great, or if the quality of the connection is good. Some modems, for example the S-100 PMMI modem can be pushed as fast as 710 baud with good results. External modems usually will not support this speed, but we can still do better than 300 baud.

I'm using the new Novation J-cat. The cost was about \$125 and I'm really satisfied with it. The modem has been absolutely reliable for 2 months now, and I've yet to have a single reception error using MODEM7. Definitely an improvement over the accoustic coupled modem it is replacing.

Now for the trick. The Novation will also work perfectly at 450 baud. You're probably wondering, "How do I get 450 baud?" The 8116 Baud rate generator can only put out 300 or 600 baud. 450 baud takes a few tricks.

The 8116 outputs a clock that is 16X the actual clock rate, the Z80-SIO is then programmed with a divide by 16 (register 4 is set up with 044H). If we instead program the 8116 for 1800 baud, and then set up the Z80-SIO for divide by 64 the outcome is 1800/4 or (you guessed it . . .) 450 baud. To do this, modify the initialization routine in MODEM7 to send an 0C4H to register 4, and a 08H to the baud rate generator (see MODEM-45.COM for a port B version). (Note, this same port A information also applies directly to the Kaypro.)

The advantage is 50% faster transfers over the phone. Many of the standard dial ups will recognize 450 baud (especially those based on S-100 PMMI modems). See the RCPMLIST.27 on BB disk #B16 for the dialups that are so equipped.

More on 5 MHz:

I'm also running 5 MHz now. The improvement is really noticeable, especially when compared to 2.5 MHz. During the conversion I noticed that:

- 1. 2716-1's are barely making it at 5 MHz. They will often not restart the computer once they are warm. I have had good luck with hand-selected Intel parts. I'm going to switch to using 1/2 of a 2732A-2 (200 ns) as soon as it arrives.
- 2. Patches to PFM: In the CTC initialization, change F119H from 93 (decimal) to 186 (decimal). This will return the CTC interrupts to the normal 1/second. In the AUTO BAUD routine (F0CBH) shift the table down one byte. This will correct the doubled clock rate.
- 3. Use a Z80-B. "A" parts for the SIO/PIO/CTC seem to work fine.
- 4. If you're using the EZ-Prommer, remember to adjust the pulse timing or you'll underburn all of your proms.
- 5. Forget PACMAN. It's just too quick! Gary Kaufman 2001 Hamilton St. Box 87 Philadelphia, PA 19130 (215) 496-0687

Modem Warning

We've gotten some feedback on the Anchor Signalman modems. Their signal output appears to be significantly lower than other direct-connect modems. Therefore, if you are having trouble communicating with bulletin boards and you have a Signalman, you might just try a new modem.

Dave Thompson

Winchester Disk Closeout \$299.95

6 megabytes unformated. Seagate ST 506 -Like new with only a few hours power on fully time. Each drive has been tested, with comes warranty, cabling manuals and data. Shipping sales tax (Wash. State only) not included. Contact Tracy :

> LIBERTY BAY COMPUTING, INC. P.O.Box 459 Poulsbo WA 98370 (206) 779-5656

WANT ADS

The following folks are reaching you for only 20 cents per word. If you would like to reach the same audience, send your words and 20 cents for each to Micro Cornucopia.

Protect your schematics. Heavy duty vinyl sheet protector, 11X17, 3-hole punched, perfect for BB schematics! Six for \$6.00 postpaid. Tony Ozrelic, LA Software, 6708 Melrose, Los Angeles CA 90038.

Designers Available for contract hardware/software work. Also selling non-exclusive rights to Commodore peripherals. Very reasonable prices. C.M.P., Box 123, Waterloo Ont., N2J BZ9.

Factory assembled Xerox 820-1 board with manual, disk, conn., \$160 working. 5" drive cabinet & cable, \$40. Several keyboards, monitors, S-100 boards; full list on request. Noor Singh, 1562 N Hill, Pasadena CA 91104 818-794-8730.

dBASE II Consulting Service. Los Angeles area. Give us a call, we may be able to help you solve your dBASE II problems. Call 213-375-6391. Ralph Freshout, consultant.

WANTED: KAYPRO USERS!!!! Join the National KAYPRO Users Group. \$8 per year. Members get newsletters & discounts. Checks to: Peoples Computer (NATKUG) PO Box 28360, Queens, NY 11428.

Public Domain UG Software Rental: CP/ M UG Vol 1-92 on 46 8" Flippies \$45.00, SIG/M UG Vol 1-150 on 75 8" Flippies \$75.00, PICONET Vol 1-34 on 17 8" Flippies \$25.00, Pascal-Z UG Vol 1-25 13 8" Flippies \$20.00, UG Games 20 Vols of the best ones \$20.00, UG Modem 20 Vols of the best \$20.00, UG Business 20 Vols of the best \$25.00, UG Utilities 10 Vols of the best \$20.00. Rental is for 7 days after receipt with 3 more days grace for return. Credit cards accepted (preferred). 5" disk formats also available. Downloading-disk format conversions. Call. User Group Software Automatic Update Service—\$7.50 per 2 volume set PP. 619-727-1015 24 hrs. 619-941-0925 info. P.J.'s National Public Domain Software Center, 1062 Taylor Street, Vista CA 92083.

TURBO PASCAL, \$49. New 18Mhz monitors in original cartons, \$50.300/1200 baud auto-dial, auto-answer modem, \$259. WYSE WY-50, \$519. Shipping \$2. B.W. Systems, Box 9791, Austin, TX 78766. (512) 255-8350.

Especially for the Big Board-From Micro Cornucopia

REMEMBER

FREE Users Disks in exchange for submitted software or articles

P.O. Box 223 Bend, OR 97709 (503) 382-8048





BB II DRIVE INTERFACE

For 5¼" and 8" Drives
Andy Bakkers is making this special software package
available through Micro C. Complete source, HEX,
& documentation files on an 8" SS SD disk. Also outlines on disk the hardware changes needed.

\$29.95

BB I, BB II, and XEROX 820 USERS DISKS

The following are full 8" disks of software. Each program has a .DOC (documentation) file and many come with source.

USERS DISK #1

1-Two fast disk copiers 4-Two disk formatters 2-The manual for Small C+ 5-Modem 7 3-Crowe Z80 Assembler 6-Othello

7-Serial print routine-Port B

USERS DISK #2 1-Two single disk drive copy programs, both with

source
2-Crowe 280 Assembler source
3-New Crowe COM file, debugged version
4-New CBIOS with parallel print driver & other extensions for CP/M 1.4 & 2.2

5-Disk mapper with source

USERS DISK #3

1-EPROM burning software for BB 1 2-Reset bit 7 (un WordStar a file) 3-Disk file CRC checker

4-New fast copy program & source 5-DU77, disk inspector/editor 6-FINDBAD, isolates bad disk sectors 7-Print fancy page headings

USERS DISK #4

1-CBIOS, custom bios for Tandon drives 2-ZCPR, dynamite CCP checks drive A for missing .COM files; improved commands 3-ZCPRBLOC, identifies CCP location

USERS DISK #5

1-CAT, disk cataloging routines 2-Modem 7 for Port A 3-Modem 7 for Port B 4-PACMAN, the arcade game 4-FACMAN, the arcade game
5-FAST, buffers the disk to speed up assemblies
6-NOLOCK, removes BB 1 shift lock
7-VERIFY, cleanup & verify a flaky disk
8-DUMPX, enhanced for BB 1 9-UNLOAD, create .HEX file from .COM file

USERS DISK #6 1-REZ, 8080/Z80 disassembler, TDL mnemonics

2-PRINTPRN, prints Crowe listings
3-RUNPAC, run-time utility package for 8080 assembly language programs. Has 51 functions. Includes source which assembles under ASM.

USERS DISK #7

1-CHNGPFM, PFM monitor mods
2-TERM, terminal routines let you set up BB as simple terminal, as a file receiver, or as a file sender 3-Checkbook balancing package 4-Disk Utilities - copy to memory, from memory,

and dump.

USERS DISK #8 1-BDSCIO, custom BDSC I/O for BB 1 (both .h

and c)
2-YAM, Yet Another Modern program in source & .COM form. Turns BB into paging intelligent terminal, complete with printer interface, baud rates to 9600. 3-ROFF, text formatter

4-SIGNS, prints large block letters

USERS DISK #9
1-ADVENTURE, expanded 550 pt version
2-Keyboard translation program
3-CBIOS, serial & parallel printer interface

4-EPROM programming package for BB II, for 2732s

USERS DISK #10 - Lots of Disk Utilities 1-REBOOT, sets up the CP/M auto load 2-SWEEP, directory/file transer routine 3-A, Lets BB I recognize a double sided drive as one drive with 494K of usable space

4-FIX, super disk utility, does everything, much easier to use than DU77

5-Compare files routine 6-UNERA, retrieve erased files

O-UNERA, retrieve erased into 7-FIND, check all drives on system for a file 8-MENU, menu program for CP/M 9-NEWCAT, enhanced disk catalog program 10-Single drive copy program that does track by track copies rather than file by file

USERS DISK #11 - Printer Utilities

1-Microline 92 printer routine 2-Graphics display package for MX-80 with Graftrax,

very fancy
3-Epson MX80 setup for BB 1 with 59.5K CP/M
4-Epson MX8 setup for any CP/M, lets you set print

5-Micro Tek print driver, Ports A & B

USERS DISK #12 - Games for BB I

1-ALIENS, a fast, exciting arcade game 2-ZCHESS, chess with a 1-6 level look ahead 3-MASTERMIND, match wits with the computer 4-BIO, Biorhythm charts complete with graphics on the BB I

5-LIFE, so fast it's real animation! 6-CRAPS, see how much you'd lose in Vegas 7-WUMPUS, a caver's delight, kill the Wumpus or 8-PRESSUP, similar to Othello

Games, 7 games in one program, includes blackjack, maze and animal

USERS DISK #13 - General Utilities, BB 1 1-ZZSOURCE, disassembles to real Zilog mnemonics

2-EX14, superset of submit or supersub
3-MOVPATCH, lets you use MOVECPM on other

copies of CP/M 4-XMON, 3K expanded BB I monitor, use in ROM or as overlay . 5-CURSOR, prompts you for cursor char you want

6-UMPIRE, very fancy RAM test 7-ZSIDFIX, display improvement for ZSID

8-PIPPAT, modify PIP so you can reset system from within PIP 9-@, Lets you use the BB as a calculator, including

10-SORT, sort package written in C80.

USERS DISK #14 - BB II Software 1-PRO32, latest 2732 reader & programmer 2-SMODEM2, lets BB II talk to Hayes Smartmodem 3-GRAFDEMO, demonstrates BB II graphics (in

4-ATTRTEST, demonstrates BB II graphics (in JRT

5-INITSIO, initializes port B for 300 or 1200 baud 6-MENU, displays menu of .COM files, enter number to run file

7-SETCLK, sets realtime clock built into BB II 8-PRINT2, modified print which accesses BB II clock 9-BOX, draws a thin line box on screen determined

by HL and BC 10-ALIENS, space invaders arcade game 11-LISTSET, printer interface, auto-enables RTS, ignores DCD.

USERS DISK #15 - Word Processing
1-EDIT, very fancy line editor similar to EX (Unix).
Includes help menu, programmable key, and full manual on disk.
TED rivels mind and line editor, every to learn for

2-TED, simple minded line editor, easy to learn &

use. Very fast.
3-TTYPE, typing training program written in BASIC
4-TINYPLAN, very simple-minded spreadsheet.
Whets your appetite for a fancy one.
5-C80 Text Utilities
6-CHOP, cuts off file after N bytes

7-ENTAB, replace spaces with tabs where possible 8-MS, double or triple spaces a file to output 9-RTW, removes trailing spaces from file 10-TRUNC, truncates each line to specified length 11-WRAP, wraps at column 80, plus pretty pretty

printing, page #s . .

USERS DISK #16 - BB I Modem Software
1-RCPM27, list of U.S. bulletin boards
2-SMODEM, interfaces BB I with Hayes Smartmodem
3-PLINK66, easy to use with non-CP/M host, for

+BBPAT, menu selection of BAUD rate, bits/char, parity, & stop bits 5-MODEM 7+, Modem 7 plus BBPAT, lets you talk

to anything from port A

USERS DISK #17 - Small C version 2 SMALLC2, this substantially expanded version of SMALLC2, this substantially expanded version of Small C now includes for, goto, label, switch (case); external declarations; new preprocessor commands; expanded I/O includes redirection; initializers; plus 12 new expressions. The I/O and runtime libraries

have been greatly expanded (including printf). Source & documentation on one full disk.

USERS DISK #18 - FORTH

IFORTH, this is Idaho FORTH which can be burned into ROM or loaded from disk. It replaces the PFM monitor & handles all the monitor functions. See issue #11 FORTH column for more info about IFORTH and this disk.

USERS DISK #19 - BB I Double Density New BB I Monitor, BIOS, character ROM, Winches-ter Interface, ZCPR, and formatter from Trevor Marshall. See BB I expansion article in Issue #11.

USERS DISK #20 - Assemblers CROWEASM: This is the Crowe assembler modified so that it runs on any CP/M system (including the BB I, BB II, Xerox...). Includes .COM .Z80 and

DOC files.

LASM: This assembler is similar to the ASM that comes with CP/M except that it can link files at

PRINTPRN: Print routine for CROWEASM .PRN

LIBRARY: Utilities which let you combine many files into one, then you can run, type, or extrace any file within the larger system.

USERS DISK #21 - Winchester Utilities BACKUP: Helps you back-up the winchester onto multiple floppies. Creates a catalog of the files on each disk and includes the date of the latest backup. Will not back-up an unchanged file more than once.

Plus many more super features. FLOPCOPY: Lets you make floppy copies (with only one floppy drive) by using the winchester as a

BIGBURST: Backs up a very large winchester file onto multiple floppies. Joins the copies to recreate the original file.

MULTCOPY: Use this like PIP but it prompts you to change disks. Accepts ambiguous file names.

to change disks. Accepts ambiguous file names.

MDIR: Displays files in all user areas on selected drive. Many features.

MAKE, MOVE: PIP-like utilities that make it easy to move files between user areas.

SWEEP: The famous disk cleanup and transfer routine that does just about everything you can do with TYPE, ERA, DIR, and PIP.

UNSQ: This is the latest, greatest file unsqueezer. Enter UNSQ *.* and it will check every file on the disk. All squeezed files will be unsqueezed.

8" Users Disks

\$15.00 each


OTHER GOODIES

Screen Editor in Small C \$39.00 A simple but full-function screen text editor plus a text formatter, all written in Small C by Edward Ream. This package includes the editor and formatter COM files setup for the Big Board, Small C itself, and source code for all. With the documentation this is over 400K on a flippy disk. Edward is selling this package for \$50, you can buy it from us for \$39 (and Ed gets a royalty). Where else can you get an editor, a formatter, a C compiler, and source for all, for under

More ROMS: Fast monitor ROMs for speed freaks and our famous 'better than Texas' character ROM (V2.3) for screen freaks. Fast Monitor ROM BB1 Deluxe Character ROM BB1 or

KayPro

SWP's CO-POWER-88 makes Z80, CP/M microcomputers IBM-PC compatible!



CO-POWER-88 is a 16-bit 8088 coprocessor for Z80 CP/M computers. Both versions of CO-POWER-88, 128k and 256k RAM, include both CP/M-86 and MSDOS, complete with IBM-PC compatibility. A facility for transferring data files between CP/M and MSDOS is included.

> Simple commands move system control between the Z80 and 8088 processors. CO-POWER-88's RAM can be used in CP/M as a RAM drive! Currently available for Kaypro, Bigboard, Zorba.

> Xerox, Access Matrix, Televideo, and ATR8000

computers.

ATR8000: SWP's \$499.95 CP/M Computer

SWP's ATR8000 is a 64k RAM, Z80A, 4 MHz computer that includes double density CP/M 2.2. The ATR-8000 runs up to four disk drives that are any mixture of size (51/4" and 8"), type (single-sided and doublesided), and density (single, double and quad). The ATR8000 has an RS-232 port for a modem or serial printer and includes software for both. There's also a parallel port with a parallel printer driver. The ATR8000 inferfaces to an RS-232 terminal or to an ATARI home computer. Software includes a program that allows the ATR8000 to use CP/M disks from other comptuers. The ATR8000 can be upgraded to also run CP/M-86 and MSDOS by adding CO-POWER-88.

Bigboard Dual Density

We've just released a new version!

Hardware

- · A daughter board that plugs into the 1771 socket. With this board the system employs automatic density select.
- Instructions tell how to run 5¼" drives. A 50-34 pin disk drive adapter board is included with 51/4" disk orders.

Price: \$149.95

Software V#061983

- . One 8" version includes the code to make a 60k double density CP/M for: 8" DS 2.5 MHz 8" SS 2.5 MHz 8" SS 4 MHz 8" DS 4 MHz 51/4" SS 2.5 MHz
- · Printer drivers are built-in, selectable in the IOBYTE.
- · Easy to change port parameters.

- 8" SSDD disk storage is 674k; DS is twice as much! 51/4" is 183k.
- . Includes DDINIT for SD and DD initializing and DDSYSGEN for DD sysgening.
- · Special features have been added including a deluxe pause, screen print and clock.
- · Source code is available for \$25 after you sign a disclosure agreement.

For orders: We accept MasterCard, Visa, money orders or checks. Shipping charges and applicable taxes will be added. Call or write for delivery Trademarks: CO-POWER-88, ATR8000, SWP, Inc. Z80, Zilog, CP/M, CP/M-86. Digital Research. Inc. IBM-PC, IBM. MSDOS, Microsoft Prices and specifications subject to change without notice



2500 E. Randol Mill Rd - 125 Arlington, Texas 76011 817/469-1181

(We used to be Software Publishers, Inc.)

Dear Editor,

I speeded-up my Kaypro a few weeks ago and I am much happier with it. I installed an SGS brand Z80-B and monitor ROM and have been able to get the system to run dependably at 4 MHz but I get garbage on the screen at 5. The 4 MHz is great (in fact, I haven't found a single program that won't work with it) but I'd like to try 5, what should I do? (Also, does the speed-up work on a Kaypro 4?)

Matthew Kesner 6345 Lochmoor Drive San Diego CA 92120

Editor's note:

I'd check out the monitor ROM. We were getting very good AMD 2716-1s for a long time, but lately the quality of even these parts has not been up to 5 MHz (at least not all the parts make it). So, we've modified the code and are burning it into 2732As which are faster (and considerably more expensive and harder to find). These 2732s for the Kaypro II plug right into the 2716 socket with no wiring changes required.

Yes you can do the speed up modification to the Kaypro 4. In fact, the monitor ROM in the Kaypro 4 is already capable of 5 MHz so you only need to change the Z80 to a Z80B and do the wiring changes.

Dear Editor,

I would like to know how IOBYTE is incorporated into BIOS.

Dennis W. Juve 2935 6th St. Marion IA 52302

Editor's note:

It isn't on the Big Board. In fact, IOBYTE is one of those little features of CP/M that few folks know about. Perhaps someone could write up a short thing on this mysterious object.

Dear Editor,

I have to run my Kaypro on 12V dc when I'm home in Gold Hill, Oregon. I don't have store-bought power so I have to make do with a water wheel and batteries. I'm not sure about the disk drives. are they ac or dc?

I wrote to Kaypro about using a 110V inverter that generates square waves. They said NO! So now I'm trying to build up a sine wave inverter. One problem is that running the inverter for hours will really drain my batteries. Any suggestions?

Gary Stookey 215 Josselyn Ln Woodside, CA 94062

Editor's note:

Your drives are DC. In fact, all you need for any Kaypro (II, 4, or 10) is +12V, +5V, and -12V. The supply in the Kaypro II and 4 can supply about 6 amps of +5V (although the system uses only about 3 amps) and about 3 amps of +12V for the drives. You only need about 0.1 amp of -12V. The Kaypro 10 needs a couple more amps of +12V during winchester start up.

The +5V should be regulated to within 0.25V of 5V, the +12V should be within 0.6V of 12V, and the -12V should be within a

If you keep your batteries charged to +13.4V or higher you should be able to put a large 3-terminal regulator in series and get it to regulate (use a TO-3 case and a good heat sink). You can use another series pass regulator circuit to get +5V but you'll be losing quite a bit of efficiency doing it this way.

You'll need an extra battery for the -12V or you can add a small switcher to generate it.

A complete switching dc to dc supply would be the most efficient but also the most expensive. Perhaps someone in the group would like to design an inexpensive version and sell any special parts.

You don't say how much of your time you spend in Gold Hill or what you do there but I'd really appreciate it if you could fill us in.

Dear Editor,

I'm working on a SASI interface and I/O expansion port for the BBI. The interface will drive a Xebec controller and IMI 15 MB drive. It will also drive the Xebec 1401 controller for multi-format 8" and 5" floppies. This means, of course, a new monitor and BIOS. I hope to get an article in about this project.

David Bell 609 Craig Ave Campbell, CA 95008

Editor's Note: Wow!

BUSINESS COMPUTERS ASSOCIATES BBISOFTWARE

BB SPOOL

Do you wait for your printer, then your computer, and then your printer? BB SPOOL is a one-page (3K) spooler that lets you overlap waiting time, cutting job time nearly in half. BB SPOOL resides in upper memory and lets you use your application program normally. If output is longer than 3K, BB SPOOL will wait. Easy to install; for serial ports you select the "null" characters sent after LF. IOBYTE not required. Intefaces with BIOS LST:.

SCREEN PRINTER with BB TYPEWRITER

\$1995

Now you can print the contents of your display screen without disrupting it. Print split-screen displays generated by your spreadsheet program or any of your application program displays. SCREEN PRINTER resides in upper memory allowing normal use of application programs. Any display you want to save, SCREEN PRINTER will send it to your printer. Easy to install, you select the control character which invokes it. As part of SCREEN PRINTER you get BB TYPE-WRITER, which lets you type directly to your display. Auto LF with CR; scrolling is locked out so no information is lost. You select the control characters for ON and OFF during installation. BIOS LST: used.

GET BOTH TOGETHER

\$29⁹⁵

Get both BB SPOOL and SCREEN PRINTER with BB TYPEWRITER in one integrated package. Lets you spool the screen print function.

USINESS

26 James St.

For BBI only 8"SSSD Check or COD NY residents add 7% COD \$2 more SSOCIATES Binghamton, NY 13903 (607) 723-0279 5-10 PM EST

(continued from page 1)

don't want us to publish your phone number.

6. Wanted: articles and reviews on D/A and A/D interfaces, new single board systems, inexpensive new assemblers and compilers, music synthesizer interfaces, speech recognition, multiprocessing, multiprocessors, multitasking, new operating systems and system ideas, and new processors (to name a few).

And that's about it unless I think of something else.

The SOG

We are less than 6 months away from the annual SOG (July 26-29) so it is not too early to start throwing things into a suitcase. (Just the bare essentials like disk drives, Z80 boards, waterwings, and the spare 5V supply.)

This year's SOG (Semi-Official Gettogether) should be as laid back as last year's even though there will, no doubt, be more attendees (meaning you).

Like last year, there will be food tables set up for your potluck contributions (that way we will be able to eat our way through two solid days of computer mania). If possible, bring regional specialties. If bringing food is particularly inconvenient, you can contribute spare change to the food pot.

Saturday evening we'll have an informal western cookout catered by an informal western cook (who else). During the dinner, we'll also present some very special awards to some very special people. (That got some chuckles around the office.) We're open to any contributions to the awards chest, serious and otherwise.

I think you'll find the awards quite interesting. With your help, we'll present an award (in absentia we hope) for the worst new software package of the year and for the most inscrutable documentation (this award should make interesting, though painful, reading). I will also be giving out awards to some notable individuals for their past (mis)deeds (should lead to some interesting acceptance speeches).

White Water Rafting (Thursday)

Of course we'll have white water rafting again this year. In fact you'll have your choice of a full day of rafting or the 2½ hour trip.

The full day includes transportation, a box lunch, and dinner afterward (everyone will be together for the dinner). This is 14 miles of class 4 white water. Everyone gets to paddle and each boat has a professional guide (safe but exciting).

The 2½ hour trip is the same event that made such a splash at the last SOG (see Issue #13). It includes the dinner and transportation.

Of course you may also opt for dinner only.

We have rented the fish hatchery (a large log structure in Bend's Shevlin Park) for all four days (Thursday through Sunday) and that is where the trips will begin and end. So if you have family members who won't be rafting, there'll be a very pleasant place for them (with supervision for the young ones). In fact, they might not even miss you.

Note that both raft trips are through protected scenic areas so the number of people who can raft these waters on any one day is strictly controlled. Those of you who have your heart set on a raft trip (particularly the full day trip) should get your reservations in as soon as possible.

Thursday is also setup day for people who have brought goodies to demonstrate. We'll have tables and plenty of power (especially if Ron Anderson makes it again) on the main floor for demonstrations. There'll be room upstairs for two meetings at a time.

Friday and Saturday

This is the official part of the SOG. These are the two days of equipment demonstrations, swap meet, talks and meetings. There will be meetings for Big Board I, Big Board II, Slicer, Xerox, Kaypro, and amateur radio enthusiasts so you will have a chance to share problems and solutions no matter what you're interested in.

Rex Buddenberg mentioned that we ought to have the Slicer folks bring a bunch of boards and tools. You'll be able to build your own Slicer right at the SOG. The boards are so compact that people could finish one in an hour or two, and then the Slicer folks could fire it up right there.

I called Otto and he was very excited about the idea. Stay tuned for further developments. We'll no doubt get to play with some of the very exciting new boards from Slicer at the same time. (Be sure to call Slicer for more details if you are interested.)

We're going to put up a bulletin board (a wooden one) where you can post buy and sell messages as well as information requests. (In fact, if you can't attend the SOG but want something posted, just send it in on a postcard size piece of paper and we'll take care of it.) Plus, I asked Trevor Marshall to bring along his portable bulletin board. Hopefully, I'll be able to coerce the local phone company into installing a line for the event. Then those of you who can't be here in body can be here in baud. (And think of all the happy sysops you could talk to.) More on this as it develops.

Sunday Sightseeing

We'll collect again at the hatchery for a last look at the equipment and then we'll break up into groups for guided hiking and sightseeing.

All the details aren't worked out, but there are more interesting things to do here than any one person could do in a lifetime.

For instance, Bend is in the center of one of the most varied geological areas in the U.S. There has been very dramatic and recent volcanic activity here as well as older (pre-8080) formations. You can explore great lava flows or try your hand at professional caliber rock climbing (several of last year's attendees went climbing during their stay). You can see the Metolius River appear full blown from a large hole in the ground and you can watch a large waterfall plunge forever into a small crystal pool that never fills and has no obvious outlet. (The water is as icy cold as the ghostly white fog which enfolds the great evergreens.)

You see, Bend is located right on the dividing line between the Cascades and the high desert. On the eastern edge of town the ground cover is mostly sagebrush and juniper. The western edge is dominated by tall puzzle-bark pines. Going west means going up and since the lowest spot in Bend is already at 3500 feet, you don't have to go up much to be really up.

Bend is less than 30 minutes drive from some very beautiful day hikes in the rugged, high cascades wilderness. You can hike trails that wind through alpine meadows kept moist and green by great glaciers.

Or, if hiking is not your cup of tea, you can (assuming it is open) take a drive over the MacKenzie pass. Some years it is blocked by snow well into July. Even at the end of July, there'll be spring flowers just beginning to peep out from beneath the melting snow. Bring your camera.

Actually, I'm planning these Sunday tours so I'll get a chance to get out into the mountains myself. I love it here but Micro C (and the SOG) keep me pretty much chained to my Big Board.

Families

Yes, yes, yes! Bring the whole tribe! The SOG is not just for those of us who are terminally freaked on computers (or just freaked at our terminals). This is a chance for the other halves (and the smaller halves) to get together and plot major campaigns aimed at waylaying your attention during the coming year.

Plus, if you equip your other half with a tape recorder, you'll get a chance to hear presentations that you would have otherwise missed.

Taxes

Let there be no mistake, however, this is a technical conference in the highest sense. This is a chance for you to rub shoulders (an ancient engineering custom) with some of the top designers in the single board systems world. You'll get a chance to hear some of these folks discuss their new projects and you'll get a chance to see some of these projects in action. You'll even get a chance to present your own ideas and projects (get in touch right away): the feedback (not to mention appreciation) should be invaluable. (Plus, we'll love you!)

There is no question that your employer should be sending your whole family to this great event. But barring that, you certainly should be able to write off the expenses. Check with your tax advisor, I'm sure you'll be delightfully surprised.

Prices

(please preregister)

Inursaay	
All day white water raft trip	
plus lunch and dinner	\$65.00
21/2 hour white water raft trip	
plus dinner	\$25.00
Evening dinner only	
(with the rafters)	\$10.00
Saturday	
Evening western cookout	
(followed by awards)	\$10.00

Not So Anonymous

Daniel Haney called to say that he is the person who turned me on to using tri-flow and tri-flon to lubricate disk drives. He also mentioned that he is now running an RBBS. It is 300 and 1200 baud, 8 bits per character, no parity, one stop bit, (the standard configuration) and the number is 703-759-6627.

After all this, he said he'd be sending more drive information, this time on paper. Thanks Dan.

David J. Thompson

Are you signing your name with an X because spelling doesn't come easily?

Then you need SpellSys!

With this full-feature package, you can write prose with the pros. SpellSys features a 42,000 word dictionary and all the bells and whistles of those expensive checkers-including rhyming, crossword search, letter unscrambling, etc.

SpellSys is made up of a group of individual programs which you can use together or separately. With SpellSys you can setup and maintain your own custom dictionary (in addition to the main dictionary). These are real dictionaries, not hash tables, so you edit or remove words from your own dictionary at will.

IT'S EASY TO USE!

Just enter "SPELLSYS", select which disks you'll use, and file you're checking. Then SpellSys takes over. Everything is self-prompting-so sit back and relax.

Word Review Operations

C .. show Context in file

L .. Lookup word in dictionary

M . . Misspelled (correct file to)

D .. put in user Dictionary

1 ... Ignore

N .. Next word

P . . Previous word

E .. Exit review

? .. (or any other key) displays menu

ORDER AT NO RISK!

Check out the manual and if you don't agree that SpellSys is a super bargain, just return the package with the disk unopened within 30 days and we'll refund your money.

SPELLSYS

\$29.95 ppd. in US & Can Other Foreign add \$5.00

Requires 32K CP/M*

Formats: 8" SS SD or

5" SS DD for KayPro, Xerox, Osborne, Morrow, Superbrain.

*CP/M is a trademark of Digital Research

Bend, OR 97709 P.O. Box 65 (503) 382-8048

LOW COST DISK CONTROLLER NOW FOR BB & BBII

- LESS THAN \$10 COMPLETE -

SAVE WEAR AND TEAR ON YOUR DISK DRIVES SAVE WEAR AND TEAR ON YOUR DISK DRIVED AND FLOPPIES WITH THE MODEL 3801 ALL SOLID STATE RELAY. SMALL ENOUGH TO FIT EASILY INSIDE YOUR DISK DRIVE, THE 3801 CAN BE INSTALLED IN MINUTES. YOUR BIG BOARD WILL THEN TURN YOUR DRIVES ON AND OFF AUTOMATICALLY AS THEY ARE NEEDED.

- FEATURES -

- * SMALL SIZE 1.75 X 1.40 X
- O.35 * FAST INSTALLATION DIAGRAM
- * FAST INSTALLATION DIAGRAM INCLUDED

 * ZERO CROSSING ELIMINATES ALL SWITCHING NOISE

 * TRIAC OUTPUT NO MECHANICAL PARTS

 * DUDT FILTER INCLUDED

 * LOW COST ONLY \$8.88 EACH

 * 1 YEAR WARRANTY

 * 38 DAY MONEY BACK GUARANTEE

COMPANY OF CALIFORNIA 1619 SOUTH MINNIE STREET SANTA ANA, CALIFORNIA 92707

(714) 547-4316

CALIF. RES. ADD 6% SALES TAX ADD \$1.00 POSTAGE & HANDLING

PLEASE SPECIFY BB OR BB II



12" GREEN ball brothers TV-12 monitor in enclosure 19 \times 16.5 \times 14". Room for mounting BB1, BB2 & X820 type SBC's; 8" drive(s) & power supply (see below). Needs +15 Vdc @1.2 Amp, Non composite (separate sync) input. Used & 100%Tested

MONITOR & ENCLOSURE (30#) \$65.00

Matching keyboard & enclosure 19×4×5", 77 keys. Non-functional lighted pushbuttons on far right missing, sold only with monitor.

KEYBOARD & ENCLOSURÉ (6#) \$45.00

Unregulated power supply, outputs: 9 v @10 A, 30 vct @ 2 A, 18v @ 1.5A, 14 v @ 0.5 A. Includes transformer, capacitors, rectifiers & heatsinks. Add 3 terminal regulators for cheap power. Removed from used equipment.

UN-REG POWER SUPPLY (25#) \$15.00

Regulated power supplyu; 6 outputs: 5v @ 4 A, +/- 12 v @ 0.2 A, +24v @ 1.2A, -24v @ 0.2A, +15v @ 2.6 A. 14×4×3", 10 lbs, New. REGULATED POWER SUPPLY \$35.00

ARKON ENGINEERING


PO BOX 60, Rome NY. 13440 (315) 336-4381 anytime or (339-2232 evenings)

TERMS: Prepaid or UPS COD (CASH OR CERTIFIED CHECKS ONLY.)

The Little Board®

Quantity One...

The world's simplest and least expensive single board computer



*Substantial Quantity discounts available

- 4mHz Z80A[†] CPU, 64K RAM
 Two RS232 serial ports
- · Mini floppy controller
- · Parallel printer port
- On-board -12V converter
- Only 5.75 × 7.75 inches
- Power Requirement: +5VDC @ .75A; +12VDC @ .05A
- · Screws directly onto a mini floppy drive



All this ... and CP/M^{††} 2.2 also!

† ZBOA is a registered trademark of Zilog, Inc. †† CP/M is a registered trademark of Digital Research.

67 East Evelyn Ave. ● Mountain View, CA 94041 ● (415) 962-0230

HELIX Winchester Disk Drives

H-5	5 mb sub-system A&T	1840
H-10	10 mb sub-sysem A&T	2120
H-17	17 mb sub-system A&T	2280
H-23	23 mb sub-system A&T	2400
	Parts	
2006	Miniscribe 6 mb drive	700
2012	Miniscribe 12 mb drive	800
4020	Miniscribe 17 mb drive	900
RO-204	Rodime 27 mb drive	1000
S1410	Xebec controller 2 drv.	330
2020.02	switching power supply	140
2014	3" quiet fan	20
2022	cabinet: 2 drvs., p.s. with switch, fuse box	80
2021	Z-80 adaptor & software for all CP/M computers	300
2021.A	Apple adaptor & software specify DOS or Pascal	200
2021.B	IBM adaptor & software	200
2004	power supply harness	20
2007,8	50 pin cable interface to crt'l with disconnect	45
2005	34 pin cable	20
2006.0	20 pin cable	20
2015	fan protector cover	3
2017	5" drive opening cover	8
2001,2,3	brackets: drive, ps, ctr'l & hardware	20
	SALE	
KayPro	II .	1350
Morrow	MD-2 w/terminal	1350
	Sprint 11 40 cps	1295
5 MHz u	ipgrade package	30

may also need Z80B and PRO monitor ROM. Does not include switch for 2.5 MHz (won't run COPY).

Plug-in replacements for U66 and U86 to make your KayPro run 5 MHz. Depending on your KayPro, you

POLYGON INDUSTRIES, INC. 8600 Ponchartrain Blvd./New Orleans, LA 70124 (504) 282-5372

POWER SUPPLY

For the BIG BOARD and other SBC's Assembled, tested and burned-in 48 hours.

- IN STOCK! . + 5V @ 4A + DVP, 24V @ 2.5A. ± 12V @ 2A
- . All supplies have over-current protection
- Bell circuit and Piezo speaker for BB
 Low line warning circuit brown out
- 4.5"H, 3.8"D, 11"L 5 lb.
 PLUS \$5 SHIPPING & HANDLING

DOUBLE DENSITY HARDWARE

\$19 PCB with DRAWINGS

Cheep! DAUGHTER BOARD FOR THE WD2795 DSDD CONTROLLER

\$79 KIT with DRAWINGS

KIT OF 2 EACH WITH PINS \$5 Plus \$1 Shipping & Handling

AMP

CONNECTORS

FOR YOUR

DISK DRIVE

KIT W/O WD2795 \$30 Plus \$1 Shipping & Handling

IN STOCK!

brother. HR-15

LOW COST DAISY WHEEL PRINTER

BIG BOARD

COMPATIBLE

- RS232-C OR CENTRONICS PARALLEL BI-DIRECTIONAL PLATEN AND HEAD PROPORTIONAL (MICRO ADJUSTMENT) GRAPHIC PRINTING
- BOLD PRINTING
- INSTALLS LIKE DIABLO 620/630

CABLES AVAILABLE

PLUS \$12 SHIPPING CALIF. RES. ADD 6% TAX




BIG BOARD

The "LA CAJA" Enclosure w/Power Supply

STANDARD FEATURES INCLUDE

- · Power Supply 5V @ 4A + OVP, 24V @ 2.5A, ± 12V @ .2A All voltages are current protected
- Reset Switch
 - Fan
- · Key-lock Power · Solid State AC Relay
- . Bell Circuit and Piezo Speaker
- · 2 AC Outlets, One Switched
- . Color, Beige and Chocolate
- . 6" H x 12" W x 16" D 24"W for 2 Drive Unit

"La Caja" can be supplied fully wired for the Big Board with all ports disk DC and timed AC for \$150.00



SINGLE DRIVE ENCLOSURE SHOWN



CALIF. RES. ADD 6% TAX



(714) 734-6006

1137 TOPAZ ST CORONA, CA 91720 ORDER FORM

hat kind orking on	of exciting adventure (misadventure) are you				
		3			
	9 a 5	x			
		*			
0 28					
	(28) (20) (4) (20)		Price Each		2000 110000
Quantity	Description	U.S.	Can & Mex	Other Foreign	Total
, ,	SUBSCRIPTION (1 year—6 issues) □ New □ Renewal	□ \$16 (Bulk) □ \$20 (1st Class)	□ \$20 (Air Mail)	□ \$26 (Air Mail)	
	USERS DISKS — 8" SSSD, CP/M #'s	\$15	\$15	\$15	2
	CP/M 86 DISKS — 8" SSSD #'s	\$15	\$15	\$15	5
	KAYPRO DISKS for the II, 4, & 10 – 5" SSDD #'s	\$12	\$12	\$12	, j
	BACK ISSUES #'s	\$3	\$3	\$5	
	OTHER ITEMS:		S 2		12
N E					
					-
5.5			e e ^e e		
Check or	ide media, package, 1st Class postage (Air Mail for C money order enclosed Is only, payable on a US bank)	Other Foreign) Make checks p MICRO COR		TOTAL ENCLOSED	
	0	Exp.	Signature		
AME	y and en her e e	I	PHONE (?) _		
	ESS		**************************************		

BACK ISSUES

\$3.00 each US, CAN, MEX

\$5.00 each Other Foreign

ISSUE NO. 1 (8/81) Power Supply RAM Protection Video Wiggle ½ PFM. PRN 16 pages

ISSUE NO. 2 (10/81)
Parallel Print Driver
Drive Motor Control
Shugart Jumpers
Program Storage Above PFM
½ PFM.PRN
16 pages

ISSUE NO. 3 (12/81) 4 MHz Mods Configuring Modem 7 Safer Formatter Reverse Video Cursor FORTHwords begins 16 pages

ISSUE NO. 4 (2/82) Keyboard Translation More 4 MHz Mods Modems, Lync, and SIOs Undoing CP/M ERASE Keyboard Encoder 20 pages

ISSUE NO. 5 (4/82) Word Processing Two Great Spells Two Text Editors Double Density Review Scribble, A Formatter 20 pages ISSUE NO. 6 (6/82) BB I EPROM Programmer Customize Your Chars Double Density Update Self-Loading ROM Terminal in FORTH 24 pages

ISSUE NO. 7 (8/82) 6 Reviews of C Adding 6K of RAM Viewing 50 Hz On Your Own begins 24 pages

ISSUE NO. 8 (10/82) Drive Maintenance Interfacing Drives Installing a New BIOS Flippy Floppies C'ing Clearly begins Xerox 820 begins 28 pages

ISSUE NO. 9 (12/82) BB II EPROM Program Relocating Your CP/M Serial Print Driver Big Board I Fixes Bringing Up WordStar Cheap RAM Disk 32 pages

ISSUE NO. 10 (2/83) Saving a Flaky Disk Hooking Wini to BB II The Disk Inspector JRT Fix Serial Keyboard Interface Pascal Procedures begins 36 pages

ISSUE NO. 11 (4/83)
BB I Expansions
BB II Details
Dyna, RAM Disk Review
Easier Reverse Video Cursor
PlannerCalc Review
KayPro Column begins
36 pages

ISSUE NO. 12 (6/83) 256K for BB I Bringing Up BB II dBase II Look at WordStar Double Sided Drives for BB I Packet Radio 5MHz Mod for KayPro 40 pages

ISSUE NO. 13 (8/83) CP/M Disk Directory More 256K for BB I Mini Front Panel Cheap Fast Modem Nevada Cobol Review BB I Printer Interface KayPro Reverse Video Mod 44 pages

ISSUE NO. 14 (10/83)
BB II Installation
The Perfect Terminal
Interface to Electronic Typewriter
BB I Video Size
Video Jitter Fix
Slicer Column starts
KayPro Color Graphics Review
48 pages

ISSUE NO. 15 (12/83) Screen Dump Listing Fixing Serial Ports Playing Adventure SBASIC Column Begins Upgrading KayPro II to 4 Upgrading KayPro 4 to 8 48 pages

ISSUE NO. 16 (2/84)
Xerox 820 Column Restarts
BB I Double Density
BB II 5"/8" Interface Fix
KayPro ZCPR Patch
Adding Joystick to Color Graphics
Recovering Text from Memory
52 pages

CP/M 86 DISKS

DISK 86-1 — Disk Utilities SD.CMD/A86, XDIR.CMD/A86: Three extended directory programs. Each does it differently, so we included all three.

FILE-EXT.CMD/A86: Disk status program with good display format.

PAGE. CMD/A86: A text paging program. Displays 24 lines at a time.

PRINT.CMD/A86: File printing routine. Puts a header at the top of each page along with page number and file name.

MUCHTEXT.CMD/A86: Counts words and lines in a text file.

ERQ.CMD/A86: Selective file erase program. Displays all selected files and then asks you one at a time for a Y/N.

INUSE.CMD/A86: Prints "In Use" on your terminal and asks for a password. It will not release the console until you enter the password.

FINDBAD.CMD/A867. Finds and collects bad sectors on a disk. If there are no bad sectors, information on the disk is unaltered.

Disk 86-2 — DU and Modem Programs DU-V75.CMD/A86/DOC: This is the popular disk utility from CP/M 80. It lets you read, write, and modify disk sectors.

MODEM4.CMD/A86: This is a modem program set up for the Slicer. This program includes a built-in help file.

MODEM7SL.CMD/A86/DOC: No modem disk would be complete without this standard. This is modem? set up for the Slicer. It displays a menu when it is called.

Disk 86-3 — Small C
C86.CMD: This is the original Snall C compiler which appeared in Dr Dobbs Journal in 1980. It runs under CPM-86 and generates 8086 source for the ASM86 assembler.
C86. COM: This is the C86 compiler which runs under CPM-80. This 8080 program produces 8086 assembly language.
C86LIB.A86: This is the C86 I/O library.
SMALLC86.DOC: Documentation on Small C.
CTTT.C: Source of the C86 compiler.
Plus, there are a number of demonstration files and ENTAB (insert tabs in place of spaces) and DETAB (replace tabs with sprices) programs all written in Small C.

8" CP/M-86 Disk \$15.00 each

BOOKS



Your Fortune in the Microcomputer
Business \$26.45 (US, Can, Mex)
\$36.45 (Other foreign)
This is the best, most complete collection of "working
for yourself" information I've found (and I've heard
nothing but good comments from those who have
received it). This two-volume set is perfect for those
times when you need a break from monitor warching.

Inside CP/M \$27.95 (US, Can, Mex)
\$37.95 (Other foreign)
This is one of the best books on CP/M. It covers the whole spectrum of users from novice to guru. There are a few books that include more programming examples but none work better for the whole range of users and this book is perfect for reference use. Micro C's copy of Inside CP/M is showing definite signs of overuse.

FERGUSON ENGINEERING

817-640-0207

XEROX 820 COMPUTER BOARDS

CLOSEOUT

UNTESTED

These boards are in like-new condition. Two out of three will run right out of the box. 820 is VERY similar to BIGBOARD I. Limited supply.

I have 12 known defective 820 bds @
STD BUS connector for BBII
CRYDOM S312 DV switching SSR
Linear power supply, new, 5V @ 6A, +/-12V @ 2A \$45.00 ALPHA 6' 3 wire AC power cord w/mating
SWITCHCRAFT EAC-301 connector
NEC UPD416 16K dyn RAM
Complete 820 Documentation Package
820 Video Cable 10 Pin Header to CRT edge card 1' \$ 5.00
820 CBIOS & Rom monitor source
CP/M Primer [Xerox CP/M handbook]\$10.00

BIGBOARD CABLE SETS

8" Dual Drive Cable 17"
10 Pin Header to CRT Edge Card. 12" \$ 5.00
DB25S to 26 Pin Header. 18" Long
AMP-8" Drive AC Power Connector W/Pins\$.75,
AMP-8" Drive DC Power Connector W/Pins
AMP-5 1/4" Drive Power Connector W/Pins \$ 1.10
XEBEC to Hard Disk Data Cable
AMP Mini-Jumpers for easy configuration strapping
XEBEC to Hard Disk Mounting Brackets & Hardware
Hard to get BIGBOARD I & II Parts


NEW-NEVER USED 3M-HCD75 67 MB TAPE CARTRIDGE TRANSPORT AND CONTROLLER. FULL DOCUMENTATION AND SCHEMATICS. 1/2 QUANTITY PRICE @\$1500.00

If you are a user of the BIGBOARD I or II, the XEROX 820, or of the KAYPRO, and you wish to be included in my mailing list, please send a post card with your name and address.

Jim B. Ferguson

FERGUSON ENGINEERING

817-640-0207 P.O. BOX 300085 ARLINGTON, TEXAS 76010



UNINTERRUPTABLE POWER SUPPLY UPS 5-200 \$19500

+5 V @ 8.5 AMPS, +12 V @ 7.2 AMPS -12V @ .5 AMP, +24V @ 2 AMPS [4A Pk]

This supply is designed to power entire computer systems with Winchester and floppy disk subsystems, as well as providing emergency battery backup capability. Designed to meet the needs of single-board Winchester systems. 24V 4.5 AH battery pack, BP-1

FEATURES:

High Reliability

High Efficiency [75% TYP.] High Power - 200 Watts

25 Khz Switching Frequency (inaudible)

Soft Start


Built-In Quick-Response O.V.P.

Cycle-By-Cycle Fold-Back Current Limiting

Drop-Out Immunity for up to 250 Ms (without battery) Uninterruptable (with addition of BP-1 battery pack)

5 Output Voltages

GENERAL PURPOSE INDUSTRIAL CONTROLLER



LB-I

Bare Board & Doc

ACCOMMUDATES

- Z80, Z80A, OR Z80B Series Parts
- Dual RS232 Serial I/O W/Current Loop Option on "A" Channel (both strappable as terminal or modem in RS232 Mode)
- 16 Programmable Baud Rates on each serial
- 32 Bits Buffered Parallel I/O Assignable on 4 Bit Boundaries, W/Strappable Handshake Polarity
- 4 Channels of Counter-Timer. 4 Inputs, 3 Outputs
 Accommodates 16K Mix of Ram or Rom or EEPROM on 2K Boundaries in 2716 or 2016 or XICOR EEPROM
- 2.3" x 10" Sea of Holes Prototyping Area
- · All I/O Fully Mode II Interrupt Compatible
- Watchdog Timer for Long-Term Unattended Operation




TERMS: MasterCard/VISA add 3%, money order, certified check, UPS cash COD. Allow 2 weeks for personal or company checks to clear. Shipping/handling extra. Texas order add 5% tax.

LEAP INTO A NEW DIMENSION WITH AZTEC CIL

Full implementation of "C" with standard floating point, library, and I/O subroutines. UNIX VER 7 compatible. Produces relocatable 8080 (optional 0Z80) assembler code. Relocating assembler and linker supplied with package or use Microsoft M80 and L80, SID/ZSID debugger interface. FAST COMPILATION AND EXECUTION.

AZTEC CII FOR CP/M \$199 (Special price for Micro C subscribers \$149)





Also available for Apple DOS, HDOS, CP/M-86, PC-DOS

ICs PROMPT DELIVERY!!! SAME DAY SHIPPING (USUALLY)

DYNAMIC RAM				
256K	200 ns	\$69.00		
64K	200 ns	5.87		
64K	150 ns	5.99		
64K	120 ns	7.50		
16K	200 ns	1.56		
	EPROM			
27128	300 ns	\$22.50		
2764	250 ns	8.75		
2732	450 ns	5.30		
2716	450 ns	3.60		
2532	450 ns	4.75		
STATIC RAM				
6264P-15	150 ns	\$39.00		
6264LP-15	150 ns	41.00		
6116P-3	150 ns	5.75		

MasterCard/VISA or UPS CASH COD

Factory New, Prime Parts

wP∞

MICROPROCESSORS UNLIMITED

24,000 South Peoria Ave. (918) 267-4961

Prices shown above are for Feb. 16, 1984

Please call for current & volume prices. Prices subject to change. Please expect higher prices on some parts due to world wide shortages. Shipping and Insurance extra. Cash discount prices shown. Small orders received by 6 PM CST can usually be delivered to you by the next morning, via Federal Express Standard Air @ \$5.991

Tired of the slowness of BASIC? Find that the bugs in FORTRAN are bugging you? Step up to FORTH, the language that gives you total control over your computer! UNIFORTH is the only version of FORTH available either "captured" under an operating system (such as CP/M), or "standalone", acting as its own operating system. Our standalone versions are customized to your single board computer, providing serial and parallel port support, a real-time clock, formatting, fast disk copy, and disk access up to twice as fast as CP/M! All systems are FORTH-79, and include a video editor, macro assembler, debugger, decompiler, top-notch documentation, and much more. Write for our free brochure, or order direct from the special Micro-C reader prices listed below.

	UNIFORT	'H Version		
System	Integer	Floating Point	Multi- Tasking	Multi- User
Big Board	\$ 60	\$100	\$125	\$150
Big Board II	80	125	150	200
Slicer	100	150	200	250
Any CPM-80	60	100		

Unified Software Systems

P.O. Box 2644, New Carrollton, MD 20784, 301/552-9590

DEC, VAX.PDP.RT-11, RSX-11 (TM) Digital Equipment Corp; CP/M (TM) Digital Research; MSDOS (TM) Microsoft; VIC-20 (TM) Commodore.

The Single Board Systems Journal

P.O. BOX 223 BEND, OREGON 97709

392 NOTTINGHAM HED, PINES SCRIVENER 550

0



